

LANE
57561

RECEIVED

NOV 04 1999

STATE OF OREGON
WATER SUPPLY WELL REPORT
(as required by ORS 537.765)
WATER RESOURCES DEPT.
SALEM, OREGON
Instructions for completing this report are on the last page of this form.

WELL I.D. # L-25897
START CARD # 116293

(1) OWNER: Well Number #1
Name Closen Christian
Address P.O. Box #5
City Vida State Oregon Zip 97488

(2) TYPE OF WORK
☒ New Well ☐ Deepening ☐ Alteration (repair/recondition) ☐ Abandonment

(3) DRILL METHOD:
☒ Rotary Air ☐ Rotary Mud ☐ Cable ☐ Auger
☐ Other

(4) PROPOSED USE:
☒ Domestic ☐ Community ☐ Industrial ☐ Irrigation
☐ Thermal ☐ Injection ☐ Livestock ☐ Other

(5) BOREHOLE CONSTRUCTION:
Special Construction approval ☐ Yes ☒ No Depth of Completed Well 305 ft.
Explosives used ☐ Yes ☒ No Type _____ Amount _____

HOLE			SEAL			
Diameter	From	To	Material	From	To	Sacks or pounds
10"	0	20	Bentonite	0	20	145 sacks
7.5"	20	59				
5.5"	59	305				

How was seal placed: Method ☐ A ☐ B ☐ C ☐ D ☐ E
☒ Other Poured in & Tamped
Backfill placed from _____ ft. to _____ ft. Material _____
Gravel placed from _____ ft. to _____ ft. Size of gravel _____

(6) CASING/LINER:

Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing: 6"	1'	59'	250	☒	☐	☒	☐
Liner: 4"	-5'	305'	160	☐	☐	☐	☐

Final location of shoe(s) 59' - 5.5" underdrum shoe

(7) PERFORATIONS/SCREENS:

From		To	Slot size	Number	Diameter	Tube/pipe size	Casing	Liner
205'	305'	6"	75	18"	4"		☐	☒

(8) WELL TESTS: Minimum testing time is 1 hour

Yield gal/min	Drawdown	Drill stem at	Flowing Time
11		305	1 hr.

Temperature of water 53 Depth Artesian Flow Found _____
Was a water analysis done? ☒ Yes By whom Analytical Lab
Did any strata contain water not suitable for intended use? ☒ Too little
☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other _____
Depth of strata: _____

(9) LOCATION OF WELL by legal description:
County Lane Latitude _____ Longitude _____
Township 17-S N or S Range 2-W E or W. WM.
Section 20 SE 1/4 NE 1/4
Tax Lot 400 Lot _____ Block _____ Subdivision _____
Street Address of Well (or nearest address) High Ranch Drive
Lot - 7

(10) STATIC WATER LEVEL:
98 ft. below land surface. Date 10-25-99
Artesian pressure _____ lb. per square inch. Date _____

(11) WATER BEARING ZONES:
Depth at which water was first found 240'

From	To	Estimated Flow Rate	SWL
240'	283'	11 gpm	98

(12) WELL LOG:
Ground Elevation 600' - 700'

Material	From	To	SWL
Topsoil - Brown	0	1	
Claysoil - Brown - w/ Boulders	1	10	
Claystone - Gray-Black	10	43	
Claystone - Brown-Red	43	95	
Claystone - Gray-Black	95	142	
Claystone - Red	142	160	
Claystone - Gray Brown	160	240	
Claystone - Gray-White	240	283	98
Claystone - Brown	283	290	98
Claystone - Tan	290	305	98

Date started 10-19 Completed 10-25-99

(unbonded) Water Well Constructor Certification:
I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.
Signed _____ WWC Number _____ Date _____

(bonded) Water Well Constructor Certification:
I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.
Signed Kirst Lee WWC Number 613 Date 10-28-99