

RECEIVED

L25899

APR 18 2000

(START CARD) # 101661

LANE
58074

STATE OF OREGON WATER SUPPLY WELL REPORT (as required by ORS 537.765)

Instructions for completing this report are on the last page of this form WATER RESOURCES DEPT.

(1) OWNER:

Well Number L25899

Name RICK SMITH
Address P.O. BOX 141
City VIDA State OR Zip 97788

(2) TYPE OF WORK

☒ New Well ☐ Deepening ☐ Alteration (repair/recondition) ☐ Abandonment

(3) DRILL METHOD:

☒ Rotary Air ☐ Rotary Mud ☐ Cable ☐ Auger
☐ Other

(4) PROPOSED USE:

☒ Domestic ☐ Community ☐ Industrial ☐ Irrigation
☐ Thermal ☐ Injection ☐ Livestock ☐ Other

(5) BORE HOLE CONSTRUCTION:

Special Construction approval ☐ Yes ☒ No Depth of Completed Well 281 ft.

Explosives used ☐ Yes ☒ No Type — Amount —

HOLE				SEAL			
Diameter	From	To	Material	From	To	Sacks or pounds	
10"	0	19	Bentonite	0	19	10 SKS.	
7.25"	19	281					

How was seal placed: Method ☐ A ☐ B ☐ C ☐ D ☐ E

☒ Other POURED & TAMPED

Backfill placed from — ft. to — ft. Material —

Gravel placed from — ft. to — ft. Size of gravel —

(6) CASING/LINER:

Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing: 6"	+1	281	250	☒	☐	☒	☐
Liner: NONE				☐	☐	☐	☐

Final location of shoe(s) 281-5 1/2" shoe

(7) PERFORATIONS/SCREENS:

☒ Perforations Method OKY, ACE
☐ Screens Type SLOT Material STEEL

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
230	276	6"	22	1 1/4"	6"	☒	☐
						☐	☐
						☐	☐
						☐	☐

(8) WELL TESTS: Minimum testing time is 1 hour

☐ Pump	☐ Bailer	☒ Air	☐ Flowing Artesian
Yield gal/min	Drawdown	Drill stem at	Time
21	—	280'	1 hr.

Temperature of water 53° Depth Artesian Flow Found —

Was a water analysis done? ☒ Yes By whom DELTA

Did any strata contain water not suitable for intended use? ☐ Too little

☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other NO

Depth of strata: NONE

(9) LOCATION OF WELL by legal description:

County LANE Latitude — Longitude —
Township 16 N or S Range 02 E or W. WM.
Section 02 N.E. 1/4 N.E. 1/4
Tax Lot 200 Lot — Block — Subdivision —
Street Address of Well (or nearest address) ABOVE
VIDA

(10) STATIC WATER LEVEL:

76 ft. below land surface. Date 04/14/00
Artesian pressure — lb. per square inch. Date —

(11) WATER BEARING ZONES:

Depth at which water was first found 241'

From	To	Estimated Flow Rate	SWL
241'	281'	21 GPM	76'

(12) WELL LOG:

Ground Elevation APPROX 1500'

Material	From	To	SWL
CLAY RED BAS. BLDGS.	0	6	
CLAY YELLOW/BROWN	6	10	
CLAYSTONE LT. BROWN	10	28	
CLAYSTONE BROWN BAS BLDGS	28	34	
CLAYSTONE BROWN	34	55	
CLAYSTONE GREY	55	67	
CLAYSTONE YELLOW/BROWN	67	81	
CLAYSTONE BROWN BAS BLDGS	81	87	
CLAYSTONE YELLOW/BROWN	87	96	
CLAYSTONE BROWN BAS BLDGS	96	110	
CLAYSTONE GREY	110	123	
CLAYSTONE GREY BAS BLDGS.	123	139	
CLAYSTONE GREY QUARTZITE	139	194	
SANDSTONE GREY FRAC. BAS.	194	241	
SANDSTONE CONGLOMERATE	241	281	76'
GREY BROWN, BLACK, WHITE QUARTZ, (WATER BEARING)			

Date started 04/06/00 Completed 04/14/00

(unbonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

WVC Number —
Signed — Date —

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

WVC Number 613
Signed — Date 04-14-00