

APR 24 2000

STATE OF OREGON
WATER SUPPLY WELL REPORT
(as required by ORS 537.765)

LANE
59004

WATER RESOURCES DEPT.
SALEM, OREGON

WELL I.D. # L. 25900
START CARD # 116294

Instructions for completing this report are on the last page of this form.

(1) OWNER:

Name KEVIN BELDEN Well Number 25900
Address 92502 PLOCH LANE
City SPRINGFIELD State OR. Zip 97148

(2) TYPE OF WORK

☒ New Well ☐ Deepening ☐ Alteration (repair/recondition) ☐ Abandonment

(3) DRILL METHOD:

☒ Rotary Air ☐ Rotary Mud ☐ Cable ☐ Auger
☐ Other

(4) PROPOSED USE:

☒ Domestic ☐ Community ☐ Industrial ☐ Irrigation
☐ Thermal ☐ Injection ☐ Livestock ☐ Other

(5) BORE HOLE CONSTRUCTION:

Special Construction approval ☐ Yes ☒ No Depth of Completed Well 99' ft.
Explosives used ☐ Yes ☒ No Type Amount

HOLE			SEAL			
Diameter	From	To	Material	From	To	Sacks or pounds
10"	0	20	Cement	0	20	564 lbs.
7.25	20	99'				

How was seal placed: Method ☐ A ☐ B ☒ C ☐ D ☐ E
☐ Other

Backfill placed from ft. to ft. Material
Gravel placed from ft. to ft. Size of gravel

(6) CASING/LINER:

Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing: 6"	*1.5	99'	1.250	☒	☐	☒	☐
Liner: -NONE-				☐	☐	☐	☐

Final location of shoe(s) 5 1/2' ID @ 99'

(7) PERFORATIONS/SCREENS:

Perforations		Method		Type		Material	
From	To	Slot size	Number	Diameter	Slot size	Casing	Liner
89'	94'	2"	12	7/8"	2"	☒	☐

(8) WELL TESTS: Minimum testing time is 1 hour

☐ Pump		☐ Bailor		☒ Air		☐ Flowing	
Yield gal/min	Drawdown	Drill stem at	Time	Temperature of water	Depth Artesian Flow Found	Was a water analysis done?	Did any strata contain water not suitable for intended use?
45	-	98	1 hr.	53°	-	☐ Yes By whom <u>NO</u>	☐ Too little
				☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other <u>NO</u>			
				Depth of strata: <u>NO</u>			

(9) LOCATION OF WELL by legal description:

County LANE Latitude Longitude
Township 16 N or S Range 02 E or W WM
Section 14 S.W. 1/4 N.W. 1/4
Tax Lot 100 Lot Block Subdivision
Street Address of Well (or nearest address) 92502 PLOCH

(10) STATIC WATER LEVEL:

21 ft. below land surface. Date 04/19/00
Artesian pressure lb. per square inch. Date

(11) WATER BEARING ZONES:

Depth at which water was first found 89'

From	To	Estimated Flow Rate	SWL
89'	99'	45	21

(12) WELL LOG:

Ground Elevation APPROX 500'

Material	From	To	SWL
TOPSOIL LOAM	0	5	
GRAVEL SAND LOAM	5	11	
CLAY BROWN GRAVEL	11	14	
CLAYSTONE GREY	14	29	
CLAYSTONE YELLOW GREY	29	40	
CLAY RED	40	48	
CLAYSTONE RED BROWN	48	55	
CLAY LT. GREY	55	78	
SANDSTONE RED BROWN GREY	78	84	
CLAY LT. GREY	84	89	
SANDSTONE GREY FRAC.	89	99	21

Date started 04/17/00 Completed 04/18/00

(unbonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

Signed WWC Number Date

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

Signed Kurt WWC Number 613 Date 04/18/00