

STATE OF OREGON
WATER SUPPLY WELL REPORT
 (as required by ORS 537.765)

WELL I.D. # L 59143
 START CARD # 153297

lane
61919

Instructions for completing this report are on the last page of this form.

(1) **LAND OWNER** Well Number 2168
 Name James Guilford
 Address 25077 Strawberry Ln.
 City Veneta State OR Zip 97487

(2) **TYPE OF WORK**
 New Well Deepening Alteration (repair/recondition) Abandonment

(3) **DRILL METHOD:**
 Rotary Air Rotary Mud Cable Auger
 Other

(4) **PROPOSED USE:**
 Domestic Community Industrial Irrigation
 Thermal Injection Livestock Other

(5) **BORE HOLE CONSTRUCTION:**
 Special Construction approval Yes No Depth of Completed Well 215 ft.
 Explosives used Yes No Type _____ Amount _____

HOLE			SEAL			
Diameter	From	To	Material	From	To	Sacks or pounds
10"	0'	44'	Cement	0'	44'	17 Sacks
6"	44'	215'				

How was seal placed: Method A B C D E
 Other
 Backfill placed from _____ ft. to _____ ft. Material _____
 Gravel placed from _____ ft. to _____ ft. Size of gravel _____

(6) **CASING/LINER:**

Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing: 6"	42'	198'	2.50	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Liner: None				<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

Drive Shoe used Inside Outside None
 Final location of shoe(s) _____

(7) **PERFORATIONS/SCREENS:**

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
None							

Perforations Method _____
 Screens Type _____ Material _____

(8) **WELL TESTS: Minimum testing time is 1 hour**

Yield gal/min	Drawdown	Drill stem at	Time
20 GPM		215'	1 hr.

Pump Bailer Air Artesian

Temperature of water 56° Depth Artesian Flow Found _____
 Was a water analysis done? Yes By whom _____
 Did any strata contain water not suitable for intended use? Too little
 Salty Muddy Odor Colored Other _____
 Depth of strata: _____

(9) **LOCATION OF WELL by legal description:**
 County Lane Latitude _____ Longitude _____
 Township 18S N or S Range 06W E or W W.M. 0
 Section 30 NW 1/4 SW 1/4
 Tax Lot 1000 Lot _____ Block _____ Subdivision _____
 Street Address of Well (or nearest address) 25077 Strawberry Ln Veneta, OR

(10) **STATIC WATER LEVEL:**
86' ft. below land surface. Date 12-14-02
 Artesian pressure _____ lb. per square inch Date _____

(11) **WATER BEARING ZONES:**
 Depth at which water was first found 194'

From	To	Estimated Flow Rate	SWL
194'	198'	20 GPM	86'

(12) **WELL LOG:**
 Ground Elevation _____

Material	From	To	SWL
Topsoil	0	2	
Yellow Clay	2	23	
Brown Clay	23	38	
Tan Sandy Clay	38	91	
Blue Grey Sand	91	145	
Blue Sand w/Gravel	145	161	
Brown Sand	161	194	
Blue Gravel w/Sand	194	198	86
Grey Shale	198	215	86

RECEIVED

JAN 17 2003

WATER RESOURCES DEPT
SALEM, OREGON

RECEIVED

NOV 17 2004

WATER RESOURCES DEPT
SALEM, OREGON

Date started 12-13-02 Completed 12-14-02
(unbonded) Water Well Constructor Certification:
 I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.
 Signed Leonel P. Hebert WWC Number 1742 Date _____

(bonded) Water Well Constructor Certification:
 I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.
 Signed Donald J. Foving WWC Number 751 Date 12-15-02