

L13885

STATE OF OREGON
WATER SUPPLY WELL REPORT
(as required by ORS 537.765)

(START CARD) # 99646

Instructions for completing this report are on the last page of this form.

(1) OWNER: Well Number 7
Name James H. Welsh
Address 15899 Pasadena Ave, Suite 220
City Tustin State CA Zip 92780

(2) TYPE OF WORK
 New Well Deepening Alteration (repair/recondition) Abandonment

(3) DRILL METHOD:
 Rotary Air Rotary Mud Cable Auger
 Other

(4) PROPOSED USE:
 Domestic Community Industrial Irrigation
 Thermal Injection Livestock Other hot well

(5) BORE HOLE CONSTRUCTION:
Special Construction approval Yes No Depth of Completed Well 175 ft.
Explosives used Yes No Type _____ Amount _____

HOLE			SEAL			
Diameter	From	To	Material	From	To	Sacks or pounds
10"	0	38	Cement w/	0	38	9
6"	38	175	4" bentonite			

How was seal placed: Method A B C D E
 Other _____
Backfill placed from _____ ft. to _____ ft. Material _____
Gravel placed from _____ ft. to _____ ft. Size of gravel _____

(6) CASING/LINER:

Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing: 6"	+1 1/2	39 1/2	.250	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Liner:				<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

(7) PERFORATIONS/SCREENS:

From		To		Slot size	Number	Diameter	Tele/pipe size	Casing	Liner

(8) WELL TESTS: Minimum testing time is 1 hour
well output may fluctuate
 Pump Bailer Air Artesian
Yield gal/min 120 Drawdown 173 Drill stem at 175 Time 1 hr.

Temperature of water 51 Depth Artesian Flow Found _____
Was a water analysis done? Yes By whom _____
Did any strata contain water not suitable for intended use? Too little
 Salty Muddy Odor Colored Other _____
Depth of strata: _____

(9) LOCATION OF WELL by legal description:
County Lane Latitude 43° 59.442' Longitude 123° 2.926'
Township 18 S N or S Range 3 W E or W. WM.
Section 21 SE 1/4 NE 1/4
Tax Lot 202 Lot _____ Block _____ Subdivision _____
Street Address of Well (or nearest address) 32475 Dillard Rd. Eugene, OR

(10) STATIC WATER LEVEL:
_____ ft. below land surface. Date _____
Artesian pressure 1.5 lb. per square inch. Date 8/16/97

(11) WATER BEARING ZONES:
Depth at which water was first found 78

From	To	Estimated Flow Rate*	SWL
78	82	25	
96	103	45	
130	136	24	
148	162	26	

(12) WELL LOG:
Ground Elevation _____

Material	From	To	SWL
Topsail	0	2	
Chy - sandy, weathered	2	29	
Tuff blue soft	29	36	
Tuff blue firm	36	175	

RECEIVED

MAY 02 2003

WATER RESOURCES DEPT
SALEM, OREGON

Date started 8/15/97 Completed 8/16/97

(unbonded) Water Well Constructor Certification:
I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

Signed _____ Date _____
WWC Number _____

(bonded) Water Well Constructor Certification:
I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

Signed _____ Date _____
WWC Number 636