

STATE OF OREGON
WATER SUPPLY WELL REPORT

WELL I.D. # L 63736
START CARD # 156996

(as required by ORS 537.765)
Instructions for completing this report are on the last page of this form.

(1) LAND OWNER Well Number 2212
Name Swanson Bros.
Address PO BOX 309
City Noti State OR Zip 97461

(2) TYPE OF WORK
 New Well Deepening Alteration (repair/recondition) Abandonment

(3) DRILL METHOD:
 Rotary Air Rotary Mud Cable Auger
 Other _____

(4) PROPOSED USE:
 Domestic Community Industrial Irrigation
 Thermal Injection Livestock Other _____

(5) BORE HOLE CONSTRUCTION:
Special Construction approval Yes No Depth of Completed Well 280
Explosives used Yes No Type _____ Amount _____

HOLE		SEAL		Sacks or pounds	
Diameter	From To	Material	From To		
12"	0 19'	Bentonite	0 19'	18	Sacks
8"	19' 280'				

How was seal placed: Method A B C D E
 Other Placed @ 1 sack pr. 5 min rate
Backfill placed from _____ ft. to _____ ft. Material _____
Gravel placed from _____ ft. to _____ ft. Size of gravel _____

(6) CASING/LINER:

Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing: 8"	11'	19'	25	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Liner: <u>None</u>				<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

Drive Shoe used Inside Outside None
Final location of shoe(s) _____

(7) PERFORATIONS/SCREENS:

Perforations Method _____
 Screens Type _____ Material _____

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
<u>None</u>							

(8) WELL TESTS: Minimum testing time is 1 hour

Yield gal/min	Drawdown	Drill stem at	Time
<u>100+ GPM</u>		<u>280'</u>	<u>1 hr.</u>

Temperature of water 57° Depth Artesian Flow Found —
Was a water analysis done? Yes By whom _____
Did any strata contain water not suitable for intended use? Too little
 Salty Muddy Odor Colored Other —
Depth of strata: _____

(9) LOCATION OF WELL by legal description:
County Lane Latitude _____ Longitude _____
Township 17S N or S Range 06W E or W WM.
Section 32 NW 1/4 NE 1/4
Tax Lot 51907A Block _____ Subdivision _____
Street Address of Well (or nearest address) 21409 Vaughn Rd, Veneta OR

(10) STATIC WATER LEVEL:
25' ft. below land surface. Date 7-9-03
Artesian pressure _____ lb. per square inch Date _____

(11) WATER BEARING ZONES:

Depth at which water was first found 225'

From	To	Estimated Flow Rate	SWL
<u>225'</u>	<u>231'</u>	<u>100+ GPM</u>	<u>25'</u>

(12) WELL LOG:
Ground Elevation _____

Material	From	To	SWL
<u>Topsoil & Clay Fill</u>	<u>0</u>	<u>1</u>	
<u>Brown Clay</u>	<u>1</u>	<u>8</u>	
<u>Weathered Sandstone</u>	<u>8</u>	<u>12</u>	
<u>Grey Sandstone (Med)</u>	<u>12</u>	<u>280</u>	<u>25'</u>

RECEIVED
JUL 22 2003
WATER RESOURCES DEPT.
SALEM, OREGON

Date started 7-9-03 Completed 7-9-03

(unbonded) Water Well Constructor Certification:
I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.
Signed John P. Hobart WWC Number 1742 Date _____

(bonded) Water Well Constructor Certification:
I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.
Signed Donald J. Joving WWC Number 751 Date 7-9-03