

STATE OF OREGON
WATER SUPPLY WELL REPORT
(as required by ORS 537.765)

WELL I.D. # L N/A
START CARD # 174 864

Instructions for completing this report are on the last page of this form.

(1) LAND OWNER City of Springfield Well Number DW2FS
Name City of Springfield
Address 225 S 5th St
City Springfield State OR Zip 97477

(2) TYPE OF WORK ☒ New Well
☐ Deepening ☐ Alteration (repair/recondition) ☐ Abandonment ☐ Conversion

(3) DRILL METHOD
☐ Rotary Air ☐ Rotary Mud ☐ Cable ☒ Auger ☐ Cable Mud
☐ Other

(4) PROPOSED USE
☐ Domestic ☐ Community ☐ Industrial ☐ Irrigation
☐ Thermal ☐ Injection ☐ Livestock ☒ Other Recreation

(5) BORE HOLE CONSTRUCTION Special Construction: ☒ Yes ☐ No
Depth of Completed Well 39 ft.
Explosives used: ☐ Yes ☒ No Type Amount

BORE HOLE			SEAL			Sacks or Pounds
Diameter	From	To	Material	From	To	
16" +	0	39	Concrete	0	18	21

How was seal placed: Method ☐ A ☐ B ☐ C ☐ D ☐ E
☒ Other poured through tremie from bottom up
Backfill placed from ft. to ft. Material
Gravel placed from 18 ft. to 19 ft. Size of gravel 8-12 Sand

(6) CASING/LINER
Diameter From To Gauge Steel Plastic Welded Threaded
Casing: 8 1 39 40 ☐ ☒ ☐ ☒
Liner: ☐ ☐ ☐ ☐ ☐ ☐ ☐ ☐

Drive Shoe used ☐ Inside ☐ Outside ☒ None
Final location of shoe(s)

(7) PERFORATIONS/SCREENS Machine Slot
☒ Perforations Method Machine Slot
☐ Screens Type Material
From To Slot Number Diameter Tele/pipe Casing Liner
19 39 060 3860 8 175 ☒ ☐

(8) WELL TESTS: Minimum testing time is 1 hour
☒ Pump ☐ Bailer ☐ Air ☐ Flowing Artesian
Yield gal/min 180 Drawdown 39 Drill stem at Time
58

Temperature of water 58 Depth Artesian Flow Found
Was a water analysis done? ☐ Yes By whom
Did any strata contain water not suitable for intended use? ☐ Too little
☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other
Depth of strata:

(9) LOCATION OF WELL (legal description)
County Lane
Tax Lot ROW Lot
Township 17S N or S Range 3W E or W WM
Section 22 SW 1/4 SE 1/4

Lat _____ " or _____ (degrees or decimal)
Long _____ " or _____ (degrees or decimal)

Street Address of Well (or nearest address) 2705 Pheasant Blvd
Springfield, OR 97477

(10) STATIC WATER LEVEL
11 ft. below land surface. Date 5/18/05
_____ ft. below land surface. Date
Artesian pressure _____ lb. per square inch Date

(11) WATER BEARING ZONES
Depth at which water was first found 15
From To Estimated Flow Rate SWL
15 39 _____ 11

(12) WELL LOG Ground Elevation
Material From To SWL
Top Soil 0 4
Brown Silt 4 15
Brown Silt w/ coarse sand & gravel 15 39 11
RECEIVED
AUG 01 2005
WATER RESOURCES DEPT
SALEM, OREGON
Date Started 5/18/05 Completed 5/18/05

(unbonded) Water Well Constructor Certification
I certify that the work I performed on the construction, deepening, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

WWC Number _____ Date
Signed _____

(bonded) Water Well Constructor Certification
I accept responsibility for the construction, deepening, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

WWC Number 1437 Date 5/19/05
Signed [Signature]



LANE 64653

RAM STEEL INC.
Service is our Business

(503) 588-1311 or toll free 1-800-452-7880
P.O. Box 5288 • 992 7th St. N.W. • Salem, OR 97304
FAX: 503 / 370-3799 • EMAIL ramsteel@teleport.com

N ↑

Game Farm Rd.

Silt Fence

DW11A ○ DW12A ○ DW13A ○ DW14A ○

DW15A ○

DW16A ○

DW17A ○ DW18A ○ DW19A ○ DW20A ○ DW21A ○

Access Road

RECEIVED

AUG 01 2005

WATER RESOURCES DEPT
SALEM, OREGON



(503) 588-1311 or toll free 1-800-452-7880
P.O. Box 5288 • 992 7th St. N.W. • Salem, OR 97304
FAX: 503 / 370-3799 • EMAIL ramsteel@teleport.com

Site Map



AUG 01 2005

**WATER RESOURCES DEPT
SALEM, OREGON**



Oregon

Theodore R. Kulongoski, Governor

Water Resources Department

North Mall Office Building
725 Summer Street NE, Suite A
Salem, OR 97301-1271
503-986-0900
FAX 503-986-0904

April 20, 2005

BRUCE EBERLE
10830 NE STEVENSON RD
NEWBERG OR 97132

FINAL ORDER


Dear Bruce:

The Special Standard request you submitted for owner: City of Springfield, Start Card numbers 174816 thru 174865 is approved for the following: You may construct these dewatering wells by utilizing a 10.25 inch I.D. HSA to a total depth of 40 feet bgs. The wells shall be cased with eight inch nominal diameter PVC casing. The seal shall consist of 18 feet of cement grout which is to be pumped through a tremie pipe from the bottom up. These wells shall not have well identification labels and shall be permanently abandoned within 90 days from the date of this Final Order. See Oregon Revised Statute (ORS) 537.789 and Oregon Administrative Rule (OAR) 690-210-0130. All other construction requirements apply. Your Special Standard request form is enclosed.

The Well Construction Standards serve to protect ground water resources. By approving and issuing this special construction standard the Oregon Water Resources Department is not representing that a well constructed in accordance with this condition will maintain structural integrity or that it meets engineering standards. The well constructor/or landowner is responsible for ensuring that a well is constructed in a manner that protects ground water resources as required under Oregon Administrative Rules 690-200 through 690-240.

If you have any questions concerning this letter, I may be contacted at (503) 986-0851, or by e-mail at Kristopher.R.Byrd@wrdd.state.or.us.

Sincerely,


Kristopher Byrd

Well Construction Program Coordinator
Enforcement Section

enclosures

cc: Ken Wilcke, NW Region Well Inspector
File

This is a final order in other than contested case. This order is subject to judicial review under ORS 183.484. Any petition for judicial review must be filed within the 60 day time period specified by ORS 183.484(2). Pursuant to ORS 536.075 and OAR 137-004-0080 you may either petition for judicial review or petition the Director for reconsideration of this order. A petition for reconsideration may be granted or denied by the Director, and if no action is taken within 60 days following the date the petition was filed, the petition shall be deemed denied.