

STATE OF OREGON
WATER SUPPLY WELL REPORT
(as required by ORS 537.765)

MAY 15 2017

WELL I.D. # L 85085

START CARD # 186358

Instructions for completing this report are on the last page of this form. SALEM, OR

(1) LAND OWNER Well Number 1
Name RICHARD SARIBS
Address PO Box 2225
City JASPER State OR Zip 97438

(2) TYPE OF WORK ☒ New Well
☐ Deepening ☐ Alteration (repair/recondition) ☐ Abandonment ☐ Conversion

(3) DRILL METHOD
☒ Rotary Air ☐ Rotary Mud ☐ Cable ☐ Auger ☐ Cable Mud
☐ Other

(4) PROPOSED USE
☒ Domestic ☐ Community ☐ Industrial ☐ Irrigation
☐ Thermal ☐ Injection ☐ Livestock ☐ Other

(5) BORE HOLE CONSTRUCTION Special Construction: ☐ Yes ☒ No
Depth of Completed Well 165 ft.
Explosives used: ☐ Yes ☒ No Type Amount

BORE HOLE			SEAL			Sacks or Pounds
Diameter	From	To	Material	From	To	
10"	0	20'	150T	0	20'	10 SACKS
7 1/2"	20	59'				
5 1/2"	59'	165'				

How was seal placed: Method ☐ A ☐ B ☐ C ☐ D ☐ E

☒ Other POURED & TAMPED

Backfill placed from ft. to ft. Material
Gravel placed from ft. to ft. Size of gravel

(6) CASING/LINER

Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing: 6"	+1	59'	250	☒	☐	☒	☐
Liner: 4"	-5	160'	CL160	☐	☒	☐	☐

Drive Shoe used ☒ Inside ☐ Outside ☐ None
Final location of shoe(s) 59' (5 1/2")

(7) PERFORATIONS/SCREENS

☒ Perforations Method Skill SAW
☐ Screens Type Material

From	To	Slot Size	Number	Diameter	Tele/pipe size	Casing	Liner
65	165	6"	150	1/8"	4"	☐	☒

(8) WELL TESTS: Minimum testing time is 1 hour

☐ Pump ☐ Bailer ☒ Air ☐ Flowing Artesian

Yield gal/min	Drawdown	Drill stem at	Time
21 GPM	85'	165'	1 H2.

Temperature of water 56° Depth Artesian Flow Found

Was a water analysis done? ☐ Yes By whom

Did any strata contain water not suitable for intended use? ☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other

Depth of strata:

(9) LOCATION OF WELL (legal description)

County LANE
Tax Lot 200 Lot
Township 18.5 N or S Range 2W E or W WM
Section 12 NE 1/4 SE 1/4

Lat " or (degrees or decimal)
Long " or (degrees or decimal)

Street Address of Well (or nearest address) 36835 RR Baker RD
SPRINGFIELD, OR 97478

(10) STATIC WATER LEVEL

80' ft. below land surface. Date 6/15/06
ft. below land surface. Date
Artesian pressure lb. per square inch Date

(11) WATER BEARING ZONES

From	To	Estimated Flow Rate	SWL
107'	155'	21 GPM	80'

(12) WELL LOG

Material	From	To	SWL
TOP SOIL	0	13	
CLAY - BROWN w/ SAND	13	21	
GRAVEL - GRAY CLAY - HARD	21	63	
SAND w/ WEATHERED	63	68	
STRAKS (CRUING) (HARD)	68	81	
CLAY - BROWN - SOFT	81	87	
CLAY - DARK BROWN - SOFT	87	165	80'
CLAY - GRAY - SOFT w/ SAND			
SS - GRAY - MED TO SOFT			
(Fractured)			

Date Started 6/13/06 Completed 6/15/06

(unbonded) Water Well Constructor Certification

I certify that the work I performed on the construction, deepening, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

WWC Number Date

Signed

(bonded) Water Well Constructor Certification

I accept responsibility for the construction, deepening, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

WWC Number 1723 Date 6/21/06

Signed