

STATE OF OREGON
WATER WELL REPORT
(as required by ORS 537.765)

RECEIVED
LANE 6719
JUN 16 1988

LANE
6719

15/5W-33
Start Card
4450

(1) OWNER:

Name FireCrest Farms
Address P.O. Box 8
City Creswell State OR Zip 97426

(2) TYPE OF WORK:

☒ New Well ☐ Deepen ☐ Recondition ☐ Abandon

(3) DRILL METHOD

☒ Rotary Air ☐ Rotary Mud ☐ Cable
☐ Other

(4) PROPOSED USE:

☒ Domestic ☐ Community ☐ Industrial ☐ Irrigation
☐ Thermal ☐ Injection ☐ Other

(5) BORE HOLE CONSTRUCTION:

Special Construction approval Yes ☐ No ☒ Depth of Completed Well 405 ft.
Explosives used ☐ Yes ☒ No ☐ Type _____ Amount _____

HOLE			SEAL			Amount sacks or pounds
Diameter	From	To	Material	From	To	
10"	0	19	Cement	0	19	5 Sacks
6"	19	405				

How was seal placed: Method ☐ A ☐ B ☒ C ☐ D ☐ E
☐ Other

Backfill placed from _____ ft. to _____ ft. Material _____
Gravel placed from _____ ft. to _____ ft. Size of gravel _____

(6) CASING/LINER:

Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
6"	+1	19	.250	☒	☐	☐	☐
				☐	☐	☐	☐
				☐	☐	☐	☐
				☐	☐	☐	☐
				☐	☐	☐	☐

Final location of shoe(s) 19 ft

(7) PERFORATIONS/SCREENS:

☒ Perforations Method Elect Drill
☐ Screens Type _____ Material _____

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
30	405	2	600			☐	☒
						☐	☐
						☐	☐
						☐	☐
						☐	☐

(8) WELL TESTS: Minimum testing time is 1 hour

☐ Pump ☐ Bailer ☒ Air ☐ Flowing
Yield gal/min 12 Drawdown _____ Drill stem at 405 Time 1 hr.
☐ Artesian

Temperature of water _____ Depth Artesian Flow Found _____
Was a water analysis done? ☐ Yes By whom None
Did any strata contain water not suitable for intended use? ☐ Too little
☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other None
Depth of strata: _____

WHITE COPIES - WATER RESOURCES DEPARTMENT

YELLOW COPY - CONSTRUCTOR

PINK COPY - CUSTOMER

9909C 10/86

(9) LOCATION OF WELL by legal description:

County Lane Latitude _____ Longitude _____
Township 15S N or S, Range 5W E or W, WM.
Section 33 1/4 _____ 1/4 _____
Tax Lot _____ Lot _____ Block _____ Subdivision _____
Street Address of Well (or nearest address) STA #6
High Pass Rd.

(10) STATIC WATER LEVEL:

6 ft. below land surface. Date 5/30/88
Artesian pressure _____ lb. per square inch. Date _____

(11) WATER BEARING ZONES:

From	To	Estimated Flow Rate	SWL
30	31	2 GPM	6
76	77	3	6
221	222	5	6
254	255	2	6

(12) WELL LOG:

Material	From	To	SWL
Topsoil	0	4	
Yellow Clay	4	12	
Grey Clay	12	14	
Grey Shale	14	185	30
Grey Sandstone	185	190	-
Grey Shale	190	243	-
Grey Sandstone	243	372	-
Light Grey Sandstone	372	405	-

Date started 5/16/88 Completed 5/18/88

(unbonded) Water Well Constructor Certification:

I certify that the work performed on the construction, alteration, or abandonment of this well is in compliance with Oregon well construction standards. Materials used and information reported above are true to my best knowledge and belief.

Signed _____ WWC Number _____
Date _____

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon well construction standards. This report is true to the best of my knowledge and belief.

Signed Donald J. Forry WWC Number 751
Date 5/30/88

RECEIVED

MAY 18 1988

"START CARD"
NOTICE OF BEGINNING OF WELL CONSTRUCTION
 (as required by ORS 537.762)

WATER RESOURCES DEPT.
 SALEM, OREGON

This form must be completed, signed by both the owner (or authorized agent) and constructor, and the original delivered to the Water Resources Department prior to commencement of construction, alteration or abandonment of each well.

Owner's Name and
 Mailing Address

Fir Crest Farms
P.O. Box 8
Creswell, Or. 97426

Proposed Commencement Date 5/16/88

Proposed Well Depth 160, Diameter 6"

and Use:

☒ Domestic

☐ Thermal

☐ Community

☐ Injection

☐ Industrial

☐ Other

☐ Irrigation

Proposed Well Location: County Lane

Township 155 (N or S) Range 5W (E or W) Section 33

At least 2
 of these
 must be
 provided

1. 1/4 of 1/4 of above section

2. street address of well location Fir Crest Farms

Sta. #6 16th pass Rd.

3. tax lot number of well location

4. attach approved map with location identified.
 (see reverse of this form for approved maps)

We hereby certify that we have read the back of this form, and that to the best of our knowledge the information provided herein is accurate and the well is being properly located from septic tanks and septic drain fields.

x Rob Rubottom (over phone)
 Owner's Signature

x Donald J. Long
 Bonded Water Well Constructor

Supervisor
 Title

License No. 751

5/12/88
 Date

Company Mid Valley Drilling

Note: This is not a Water Right application. The owner is responsible for obtaining a Water Right through the Water Resources Department if required.