

STATE OF OREGON
WATER WELL REPORT
(as required by ORS 537.765)

RECEIVED

LANE 6720

LANE
6720

155/5W-33

APR 12 1988

(1) OWNER:

Name Fir Crest Farms WATER RESOURCES DEPT 335
Address P.O. Box 8 KEM. OREGON
City Creswell State OR Zip 97426

(2) TYPE OF WORK:

☒ New Well ☐ Deepen ☐ Recondition ☐ Abandon

(3) DRILL METHOD

☒ Rotary Air ☐ Rotary Mud ☐ Cable
☐ Other

(4) PROPOSED USE:

☒ Domestic ☐ Community ☐ Industrial ☐ Irrigation
☐ Thermal ☐ Injection ☐ Other

(5) BORE HOLE CONSTRUCTION:

Special Construction approval Yes ☐ No ☒ Depth of Completed Well 245 ft.
Explosives used ☐ Yes ☒ No ☐ Type _____ Amount _____

HOLE			SEAL			Amount sacks or pounds
meter	From	To	Material	From	To	
10"	0	39	Cement	0	39	9
6"	39	245				

How was seal placed: Method ☐ A ☐ B ☒ C ☐ D ☐ E

☐ Other

Backfill placed from _____ ft. to _____ ft. Material _____

Gravel placed from _____ ft. to _____ ft. Size of gravel _____

(6) CASING/LINER:

	Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing:	6"	0	39	250	☒	☐	☒	☐
					☐	☐	☐	☐
					☐	☐	☐	☐
					☐	☐	☐	☐
Liner:	4"	0	245	160	☐	☒	☐	☐
					☐	☐	☐	☐

location of shoe(s) None

(7) PERFORATIONS/SCREENS:

☒ Perforations Method Elect Drill
☐ Screens Type _____ Material _____

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
40	80	1/2"	100	1 1/2"		☐	☒
120	180		120	1 1/2"		☐	☒
220	245		75	1 1/2"		☐	☒

(8) WELL TESTS: Minimum testing time is 1 hour

☐ Pump ☐ Bailer ☒ Air ☐ Flowing
Artesian

Yield gal/min	Drawdown	Drill stem at	Time
7		245	1 hr.

Temperature of water _____ Depth Artesian Flow Found _____

Was a water analysis done? ☐ Yes By whom None

Did any strata contain water not suitable for intended use? ☐ Too little

☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other None

Depth of strata: _____

(9) LOCATION OF WELL by legal description:

County Lane Latitude _____ Longitude _____
Township 15S N or S, Range 5W E or W, WM.
Section 33 1/4 _____ 1/4 _____
Tax Lot _____ Lot _____ Block _____ Subdivision _____
Street Address of Well (or nearest address) Fir Crest Farms
Station #6 High pass Rd.

(10) STATIC WATER LEVEL:

5 ft. below land surface. Date 3/16/88
Artesian pressure _____ lb. per square inch. Date _____

(11) WATER BEARING ZONES:

Depth at which water was first found		46 ft	
From	To	Estimated Flow Rate	SWL
46	47	3	5
135	136	4	5

(12) WELL LOG:

Ground elevation _____

Material	From	To	SWL
Topsoil	0	3	
Brown clay	3	31	
Grey shale	31	61	5
Grey sandstone	61	63	
Grey shale	63	245	

Date started 3/14/88 Completed 3/16/88

(unbonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon well construction standards. Materials used and information reported above are true to my best knowledge and belief.

WWC Number _____
Signed _____ Date _____

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. all work performed during this time is in compliance with Oregon well construction standards. This report is true to the best of my knowledge and belief.

WWC Number 751
Signed Donald J. Joving Date 4/4/88

NO 2867
RECEIVED

"START CARD"
NOTICE OF BEGINNING OF WELL CONSTRUCTION
(as required by ORS 537.762)

DEC 28 1988

WATER RESOURCES DEPT.
SALEM, OREGON

This form must be completed, signed by both the owner (or authorized agent) and constructor, and the original delivered to the Water Resources Department prior to commencement of construction, alteration or abandonment of each well.

Owner's Name and
Mailing Address

Fir Crest Farms
P.O. Box 8
Creswell, OR
97426

Proposed Commencement Date 3/14/88

Proposed Well Depth 100 ft, Diameter 6"
and Use:

☒ Domestic
☐ Thermal

☐ Community
☐ Injection

☐ Industrial
☐ Other

☐ Irrigation

Proposed Well Location: County Lane

Township 15S (N or S) Range 5W (E or W) Section 33

At least 2
of these
must be
provided

1. SW 1/4 of SW 1/4 of above section

2. street address of
well location Station #6

High Pass Rd.

3. tax lot number of well location _____

4. attach approved map with location identified.
(see reverse of this form for approved maps)

We hereby certify that we have read the back of this form, and that to the best of our knowledge the information provided herein is accurate and the well is being properly located from septic tanks and septic drain fields.

x Donald J. Janning
Owner's Signature

x Donald J. Janning
Bonded Water Well Constructor

Dealings over Phone
Title

License No. 1751

3/12/88
Date

Company Mid Valley Drilling

Note: This is not a Water Right application. The owner is responsible for obtaining a Water Right through the Water Resources Department if required.