

STATE OF OREGON
WATER SUPPLY WELL REPORT

(as required by ORS 537.765)

WELL I.D. # 44113
START CARD # W 169140

Instructions for completing this report are on the last page of this form.

(1) LAND OWNER Well Number _____
Name RICHARD MOSIER
Address 90972 S. COLEMAN ST.
City COBURG State ORE. Zip 97408

(2) TYPE OF WORK
☒ New Well ☐ Deepening ☐ Alteration (repair/recondition) ☐ Abandonment

(3) DRILL METHOD:
☐ Rotary Air ☐ Rotary Mud ☒ Cable ☐ Auger
☐ Other _____

(4) PROPOSED USE:
☒ Domestic ☐ Community ☐ Industrial ☐ Irrigation
☐ Thermal ☐ Injection ☐ Livestock ☐ Other _____

(5) BORE HOLE CONSTRUCTION:
Special Construction approval ☐ Yes ☒ No Depth of Completed Well 68 ft.
Explosives used ☐ Yes ☒ No Type _____ Amount _____

HOLE			SEAL			Sacks or pounds
Diameter	From	To	Material	From	To	
10"	0'	20'	CEMENT	0'	20'	15
6"	+1'	67'				

How was seal placed: Method ☐ A ☐ B ☒ C ☐ D ☐ E
☐ Other _____

Backfill placed from _____ ft. to _____ ft. Material _____
Gravel placed from _____ ft. to _____ ft. Size of gravel _____

(6) CASING/LINER:

Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing: 6" + 1'	67'	250'		☒	☐	☒	☐
Liner: NONE				☐	☐	☐	☐

Drive Shoe used ☒ Inside ☒ Outside ☐ None
Final location of shoe(s) 67'

(7) PERFORATIONS/SCREENS: NONE
☐ Perforations Method _____
☐ Screens Type _____ Material _____

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
						☐	☐
						☐	☐
						☐	☐
						☐	☐

(8) WELL TESTS: Minimum testing time is 1 hour
☒ Pump ☐ Bailer ☐ Air ☐ Flowing
Yield gal/min Drawdown Drill stem at Time
40 GPM 12' 4 HRS.

Temperature of water 58° Depth Artesian Flow Found _____
Was a water analysis done NO ☐ Yes By whom _____
Did any strata contain water not suitable for intended use? YES ☒ Too little
☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other _____
Depth of strata: 39'-41'

(9) LOCATION OF WELL by legal description:
County LANE Latitude _____ Longitude _____
Township 16 N or S Range 3 E or W. WM.
Section 33 1/4 _____ 1/4 _____
Tax Lot 01100 Lot _____ Block _____ Subdivision _____
Street Address of Well (or nearest address) EAST OF 90948 S. WILLAMETTE ST. COBURG, OREGON 97408

(10) STATIC WATER LEVEL:
14 ft. below land surface. Date 10-5-10
Artesian pressure _____ lb. per square inch Date _____

(11) WATER BEARING ZONES:

Depth at which water was first found 39'

From	To	Estimated Flow Rate	SWL
39'	41'	20 GPM	14'
55'	60'	40 GPM	14'

(12) WELL LOG:

Ground Elevation -0-

Material	From	To	SWL
TOP SOIL	0'	7'	
CEMENTED SAND & GRAVEL	7'	39'	14'
SAND & SMALL GRAVEL	39'	41'	
LOOSE	39'	41'	14'
SAND & GRAVEL	41'	52'	
WITH CLAY - TIGHT	52'	55'	14'
LOOSE SAND	55'	60'	
SAND & SMALL GRAVEL - LOOSE	60'	69'	
SAND & SMALL GRAVEL WITH CLAY - TIGHT	69'		

RECEIVED

NOV 12 2010

WATER RESOURCES DEPT
SALEM, OREGON

Date started 6-23-10 Completed 10-5-10

(unbonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

Signed _____ WWC Number _____ Date _____

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

Signed Clayton Heas WWC Number 502 Date 10-5-10