

LANE 72336

STATE OF OREGON
 WATER SUPPLY WELL REPORT
 (as required by ORS 537.765)

WELL I.D. # L 107165

START CARD # 208726

Instructions for completing this report are on the last page of this form.

(1) **LAND OWNER** Well Number _____
 Name Country View Estates - Attn: Don Harkins
 Address 91000 Ridgeview Rd
 City Eugene State OR Zip 97408

(2) **TYPE OF WORK** New Well
 Deepening Alteration (repair/recondition) Abandonment Conversion

(3) **DRILL METHOD**
 Rotary Air Rotary Mud Cable Auger Cable Mud
 Other _____

(4) **PROPOSED USE**
 Domestic Community Industrial Irrigation
 Thermal Injection Livestock Other _____

(5) **BORE HOLE CONSTRUCTION** Special Construction: Yes No
 Depth of Completed Well 300 ft.
 Explosives used: Yes No Type _____ Amount _____

BORE HOLE			SEAL			Sacks or Pounds
Diameter	From	To	Material	From	To	
12"	0	38	bentonite	0	38	26 sacks
8"	38	300				

How was seal placed: Method A B C D E
 Other as per OAR 690-210-340
 Backfill placed from _____ ft. to _____ ft. Material _____
 Gravel placed from _____ ft. to _____ ft. Size of gravel _____

(6) **CASING/LINER**

Casing:	Diameter	From	To	Gauge	SEAL			
					Steel	Plastic	Welded	Threaded
8"	+2	38	.250	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Liner:								

Drive Shoe used Inside Outside None
 Final location of shoe(s) _____

(7) **PERFORATIONS/SCREENS**
 Perforations Method _____
 Screens Type _____ Material _____

From	To	Slot Size	Number	Diameter	Tele/pipe size	Casing	Liner
						<input type="checkbox"/>	<input type="checkbox"/>

(8) **WELL TESTS: Minimum testing time is 1 hour**
 Pump Bailer Air Flowing Artesian

Yield gal/min	Drawdown	Drill stem at	Time
50	287	300	1 hr
<i>well output may fluctuate</i>			

Temperature of water 50 Depth Artesian Flow Found _____
 Was a water analysis done? Yes By whom _____
 Did any strata contain water not suitable for intended use? Too little
 Salty Muddy Odor Colored Other _____
 Depth of strata: _____

(9) **LOCATION OF WELL (legal description)**
 County Lane
 Tax Lot 203 Lot _____
 Township 16 S Range 3 W WM
 Section 27 SE 1/4 SE 1/4

Lat _____ ° _____ ' _____ " or _____ (degrees or decimal)
 Long _____ ° _____ ' _____ " or _____ (degrees or decimal)

Street Address of Well (or nearest address) located at the very end of Oakcrest Street, Eugene - off of Van Dyne

(10) **STATIC WATER LEVEL**
13 ft. below land surface. Date 11-16-12
 _____ ft. below land surface. Date _____
 Artesian pressure _____ lb. per square inch Date _____

(11) **WATER BEARING ZONES**
 Depth at which water was first found 47

From	To	Estimated Flow Rate	SWL
47	48	1	13
62	63	+13	13
83	84	+18	13
140	141	+ 5	13
165	166	+ 5	13
257	258	+ 8	13

(12) **WELL LOG** Ground Elevation _____

Material	From	To	SWL
Topsoil	0	3	
Clay, brown	3	12	
Clay w/ gravel	12	25	13
Tuff, blue gray	25	40	13
Tuff, gray	40	70	13
Tuff, blue gray	70	123	13
Tuff, gray	123	142	13
Tuff, blue gray	142	162	13
Tuff, blue gray w/ white	162	165	13
Tuff, glue gray	165	182	13
Tuff, blue gray fractured	182	247	13
Tuff, gray light	247	300	13

RECEIVED BY OWRD

Date Started 11/13/12 Completed MAR 13 2013

(unbonded) **Water Well Constructor Certification**
 I certify that the work I performed on the construction, deepening, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

WWC Number _____ Date _____
 Signed _____

(bonded) **Water Well Constructor Certification**
 I accept responsibility for the construction, deepening, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

WWC Number 636 Date _____
 Signed Paul Christensen Pres
Christensen Well Drilling Co.