



STATE OF OREGON
WATER SUPPLY WELL REPORT
(as required by ORS 537.765 & OAR 690-205-0210)

WELL I.D. LABEL # 111755
START CARD # 1022270
ORIGINAL LOG # LANE

(1) LAND OWNER
Owner Well I.D. _____
First Name RANDY Last Name HERBERT
Company _____
Address 1889 N. PILGRIM AVE
City BOISE State ID Zip 83701
(2) TYPE OF WORK ☒ New Well ☐ Deepening ☐ Conversion
☐ Alteration (complete 2a & 10) ☐ Abandonment (complete 5a)

(2a) PRE-ALTERATION
Dia + From To Gauge Stl Plstc Wld Thrd
Casing: ☐ ☐ ☐ ☐ ☐ ☐ ☐ ☐
Material From To Amt sacks/lbs
Seal: ☐ ☐ ☐ ☐ ☐ ☐ ☐ ☐

(3) DRILL METHOD
☐ Rotary Air ☐ Rotary Mud ☒ Cable ☐ Auger ☐ Cable Mud
☐ Reverse Rotary ☐ Other

(4) PROPOSED USE ☒ Domestic ☐ Irrigation ☐ Community
☐ Industrial/ Commercial ☐ Livestock ☐ Dewatering
☐ Thermal ☐ Injection ☐ Other

(5) BORE HOLE CONSTRUCTION Special Standard ☐ (Attach copy)
Depth of Completed Well 230.00 ft.
BORE HOLE SEAL
Dia From To Material From To Amt sacks/lbs
10 0 48 Bentonite 0 48 32 S
6 48 230
How was seal placed: Method ☐ A ☐ B ☐ C ☐ D ☐ E
☒ Other DRY POUR
Backfill placed from _____ ft. to _____ ft. Material _____
Filter pack from _____ ft. to _____ ft. Material _____ Size _____
Explosives used: ☐ Yes Type _____ Amount _____

(5a) ABANDONMENT USING UNHYDRATED BENTONITE
Proposed Amount _____ Actual Amount _____
(6) CASING/LINER
Casing Liner Dia + From To Gauge Stl Plstc Wld Thrd
☐ ☐ 4 130 230 pvc ☐ ☐ ☒ ☐
☐ ☐ 6 1 48 ☐ ☐ ☒ ☐
Shoe ☒ Inside ☐ Outside ☐ Other Location of shoe(s) 53
Temp casing ☐ Yes Dia _____ From _____ To _____

(7) PERFORATIONS/SCREENS
Perforations Method skillsaw
Screens Type _____ Material _____
Perf/ Casing/ Screen Screen Liner Dia From To Scrn/slot Slot # of Tele/
Perf Liner 4 180 230 width length slots pipe size
1 4 60
(8) WELL TESTS: Minimum testing time is 1 hour
☐ Pump ☒ Bailer ☐ Air ☐ Flowing Artesian
Yield gal/min Drawdown Drill stem/Pump depth Duration (hr)
10 230 1
Temperature 53 °F Lab analysis ☐ Yes By _____
Water quality concerns? ☐ Yes (describe below) TDS amount
From To Description Amount Units

(9) LOCATION OF WELL (legal description)
County LANE Twp 17.00 S N/S Range 6.00 W E/W W
Sec 6 NW 1/4 of the SW 1/4 Tax Lot 17-06-06-00-0300
Tax Map Number _____ Lot _____
Lat _____ " or _____ DMS or DE
Long _____ " or _____ DMS or DE
☒ Street address of well ☐ Nearest address
21935 COOK RD 21985 Cook Rd
NOTI OR

(10) STATIC WATER LEVEL
Date SWL(psi) + SWL(ft)
Existing Well / Pre-Alteration 3/14/2014 126
Completed Well 3/14/2014 126
Flowing Artesian? ☐ Dry Hole? ☐

WATER BEARING ZONES Depth water was first found 160.00

SWL Date	From	To	Est Flow	SWL(psi)	+ SWL(ft)
3/17/2014	160	165	2		126
3/13/2014	210	225	8		126

(11) WELL LOG Ground Elevation 675.00
Material From To
top soil 0 1
clay 1 15
clay stone 15 50
gray sandstone 50 160
broken brown sandstone 160 170
gray sandstone 170 230
RECEIVED BY OWRD
JUN 23 2014
SALEM, OR

Date Started 2/17/2014 Complete 3/14/2014

(unbonded) Water Well Constructor Certification
I certify that the work I performed on the construction, deepening, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.
License Number _____ Date _____
Signed _____

(bonded) Water Well Constructor Certification
I accept responsibility for the construction, deepening, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.
License Number 1635 Date 3/26/2014
Signed JERRY MADSEN (E-filed)
Contact Info (optional) Madsen well drilling