

(Amended)

RECEIVED BY OWRD
LANE 73113

STATE OF OREGON
WATER SUPPLY WELL REPORT
(as required by ORS 537.765)

MAY 05 2014

WELL I.D. # L 112552

SALEM, OR

START CARD # 210052

Instructions for completing this report are on the last page of this form.

(1) LAND OWNER Well Number _____
Name Dan Gee
Address 18964 Little Lake Road
City Blachly State OR Zip 97412

(2) TYPE OF WORK ☒ New Well
☐ Deepening ☐ Alteration (repair/recondition) ☐ Abandonment ☐ Conversion

(3) DRILL METHOD
☒ Rotary Air ☐ Rotary Mud ☐ Cable ☐ Auger ☐ Cable Mud
☐ Other _____

(4) PROPOSED USE
☒ Domestic ☐ Community ☐ Industrial ☐ Irrigation
☐ Thermal ☐ Injection ☐ Livestock ☐ Other _____

(5) BORE HOLE CONSTRUCTION Special Construction: ☐ Yes ☒ No
Depth of Completed Well 225 ft.
Explosives used: ☐ Yes ☒ No Type _____ Amount _____

BORE HOLE				SEAL			
Diameter	From	To	Material	From	To	Sacks or Pounds	
10"	0	51	cement	0	51	38 sacks	
8"	51	151					
8"	151	200	cement	160	200	7 sacks	
6"	160	225					

How was seal placed: Method ☐ A ☐ B ☐ C ☐ D ☐ E
☐ Other _____

Backfill placed from _____ ft. to _____ ft. Material _____
Gravel placed from _____ ft. to _____ ft. Size of gravel _____

(6) CASING/LINER

Casing:	Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
6"	+1.5	151	.250	☒	☐	☒	☐	☐
				☐	☐	☐	☐	☐
				☐	☐	☐	☐	☐
				☐	☐	☐	☐	☐
Liner:				☐	☐	☐	☐	☐

Drive Shoe used ☐ Inside ☐ Outside ☒ None

Final location of shoe(s) _____

(7) PERFORATIONS/SCREENS

☐ Perforations Method _____
☐ Screens Type _____ Material _____

From	To	Slot Size	Number	Diameter	Tele/pipe size	Casing	Liner
						☐	☐
						☐	☐
						☐	☐
						☐	☐

(8) WELL TESTS: Minimum testing time is 1 hour

☐ Pump ☐ Bailer ☒ Air ☐ Flowing Artesian

Yield gal/min	Drawdown	Drill stem at	Time
20 gpm	195	225	1 hour
well output	may fluctuate		

Temperature of water 50 Depth Artesian Flow Found _____

Was a water analysis done? ☐ Yes By whom _____

Did any strata contain water not suitable for intended use? ☐ Too little

☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other _____

Depth of strata: _____

(9) LOCATION OF WELL (legal description)
County Lane
Tax Lot 600 Lot _____
Township 16 S Range 7 W WM
Section 19 NW 1/4 NW 1/4

Lat _____° _____' _____" or _____ (degrees or decimal)
Long _____° _____' _____" or _____ (degrees or decimal)

Street Address of Well (or nearest address) 18964 Little Lake Road
Blachly, OR 97412

(10) STATIC WATER LEVEL

30 ft. below land surface. Date 11-19-13

_____ ft. below land surface. Date _____

Artesian pressure _____ lb. per square inch Date _____

(11) WATER BEARING ZONES

Depth at which water was first found 215

From	To	Estimated Flow Rate	SWL
215	216	5 gpm	30
220	221	15 gpm	30

(12) WELL LOG

Ground Elevation _____

Material	From	To	SWL
clay, brown w/sand	0	12	
sandstone, brown, soft	12	15	
sandstone, gray, soft	15	23	
sandstone, brown, soft	23	25	
sandstone, gray, soft	25	46	30
sandstone, gray, firm w/shales	46	225	30

RECEIVED BY OWRD

MAR 10 2014

SALEM, OR

Date Started 10-30-13 Completed 11-19-13

(unbonded) Water Well Constructor Certification

I certify that the work I performed on the construction, deepening, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

WWC Number 1886 Date _____

Signed _____

(bonded) Water Well Constructor Certification

I accept responsibility for the construction, deepening, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

WWC Number 636 Date _____

Signed _____