

NOTICE TO WATER WELL CONTRACTOR

The original and first copy of this report are to be filed with the

STATE ENGINEER, SALEM, OREGON 97310 within 30 days from the date of well completion.

WATER WELL REPORT

STATE OF OREGON

(Please type or print)

(Do not write above this line)

State Well No.

State Permit No.

(1) OWNER:

Name WALLACE KRENICK
Address CHESHIRE ORE Box 223-97419

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐
If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☐ Driven ☐
Cable ☒ Jetted ☐
Dug ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☐ Industrial ☐ Municipal ☐
Irrigation ☒ Test Well ☐ Other ☐

(5) CASING INSTALLED:

Threaded ☐ Welded ☒
5" Diam. from 0 ft. to 35 ft. Gage 258
" Diam. from ft. to ft. Gage
" Diam. from ft. to ft. Gage

(6) PERFORATIONS:

Perforated? ☒ Yes ☐ No
Type of perforator used Acetylene
Size of perforations 1/4 in. by 4 in.
66 perforations from 25 ft. to 35 ft.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No
Manufacturer's Name _____
Type _____ Model No. _____
Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.
Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.

(8) WATER LEVEL: Completed well.

Static level 4'-6" ft. below land surface Date 6/23/69
Artesian pressure _____ lbs. per square inch Date _____

(9) WELL TESTS:

Drawdown is amount water level is lowered below static level
Was a pump test made? ☒ Yes ☐ No If yes, by whom? Driller
Yield: 50 gal./min. with 16 ft. drawdown after 2 hrs.
" " " "

Bailer test _____ gal./min. with _____ ft. drawdown after _____ hrs.
Artesian flow _____ g.p.m. Date _____
Temperature of water 53 Was a chemical analysis made? ☐ Yes ☒ No

(10) CONSTRUCTION:

Well seal—Material used Bentonite
Depth of seal 19 ft.
Diameter of well bore to bottom of seal 9 in.
Were any loose strata cemented off? ☐ Yes ☒ No Depth _____
Was a drive shoe used? ☐ Yes ☒ No
Did any strata contain unusable water? ☐ Yes ☒ No
Type of water? _____ depth of strata _____
Method of sealing strata off _____
Was well gravel packed? ☐ Yes ☒ No Size of gravel: _____
Gravel placed from _____ ft. to _____ ft.

(11) LOCATION OF WELL:

County LANE Driller's well number _____
1/4 1/4 Section 7 T. 16S R. 4W W.M.
Bearing and distance from section or subdivision corner _____

(12) WELL LOG:

Diameter of well below casing 5
Depth drilled 37 ft. Depth of completed well 35 ft.
Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level as drilling proceeds. Note drilling rates.

MATERIAL	From	To	SWL
<u>Topsoil + Brown clay + gravel</u>	<u>0</u>	<u>22</u>	
<u>yellow clay + gravel</u>	<u>22</u>	<u>25</u>	
<u>medium Brown sand</u>	<u>25</u>	<u>28</u>	<u>4'-6"</u>
<u>Water bearing</u>			
<u>packed sand</u>	<u>28</u>	<u>35</u>	
<u>yellow clay</u>	<u>35</u>	<u>37</u>	

Work started 6/18 1969 Completed 6/21 1969
Date well drilling machine moved off of well 6/23 1969

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] O. B. Nye Date 6/23, 1969
(Drilling Machine Operator)

Drilling Machine Operator's License No. 211

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

NAME O. B. Nye (Type or print)
(Person, firm or corporation)

Address JUNCTION CITY ORE

[Signed] O. B. Nye (Water Well Contractor)

Contractor's License No. 151 Date 6/23, 1969