

STATE OF OREGON
WATER SUPPLY WELL REPORT

LANE 80627

WELL I.D. LABEL# L 159627

START CARD # 1081705

ORIGINAL LOG #

(as required by ORS 537.545 & 537.765 and OAR 690-205-0210)

5/9/2026

(1) LAND OWNER

Owner Well I.D. 1

First Name STAN Last Name WILLIAMS

Company

Address 1292 HIGH STREET #1232

City EUGENE State OR Zip 97401

(2) TYPE OF WORK☒ New Well ☐ Deepening ☐ Conversion☐ Alteration (complete 2a & 10) ☐ Abandonment (complete 5a)**(2a) PRE-ALTERATION**

Dia + From To Gauge Stl Plstc Wld Thrd

Casing: Material From To Amt sacks/lbs

Seal: Material From To Amt sacks/lbs

(3) DRILL METHOD☒ Rotary Air ☐ Rotary Mud ☐ Cable ☐ Auger☐ Reverse Rotary ☐ Other**(4) PROPOSED USE**☒ Domestic ☐ Irrigation ☐ Community☐ Industrial/ Commercial ☐ Livestock ☐ Dewatering☐ Thermal ☐ Injection ☐ Other**(5) BORE HOLE CONSTRUCTION**Special Standard ☐ (Attach copy)

Depth of Completed Well 180.00 ft.

BORE HOLE

Dia	From	To	Material	SEAL	From	To	Amt	sacks/
10	0	120	Bentonite Chips	0	120	59	S	
6	120	180		Calculated		55.1		
				Calculated				

Seal placement method: ☐ A ☐ B ☐ C ☐ D ☐ E ☒ Other: POURED DRY

Backfill placed from ft. to ft. Material

Filter pack from ft. to ft. Material Size

Explosives used: ☐ Type Amount

Seal Placement Begin Date 4/8/2026 Begin Time 14 00

(5a) ABANDONMENT USING UNHYDRATED BENTONITE

Proposed Amount

Actual Amount

(6) CASING/LINER

C/L	Dia	+	From	To	Gauge	Mat. Type	Wld	Thrd	Shoe	Shoe Location
C	6	☒	1	119	0.250	ST	☒		IN.	119
L	4		6	180	SDR26	PL	☒			

Temp casing ☐ Yes Dia From + To**(7) PERFORATIONS/SCREENS**

Perforations Method drilled holes

Screens Type Material

Perf/ Screen	Casing/ Liner	Screen Dia	From	To	Scrm/slot width	Slot length	# of slots	Tele/ Pipe size
Perf	Liner	4	100	180	.5	0.5	300	

(8) WELL TESTS: Minimum testing time is 1 hour

Type of Test	Yield (gal/min)	Drawdown	Drill Stem/ Pump Depth	Duration (hr)
Air	32		179	1

Temperature 58 °F Lab analysis ☐ Yes ByWater quality concerns? ☐ Yes (describe below) TDS amount 196 ppm

From	To	Description	Amount	Units

(9) LOCATION OF WELL (legal description)

County LANE Twp 17.00 S N/S Range 2.00 W E/W WM

Sec 18 NW 1/4 of the SE 1/4 Tax Lot 601

Tax Map Number Lot

Lat ° ' " or 44.08862665 DMS or DD

Long ° ' " or -122.97520064 DMS or DD

☒ Street address of well ☐ Nearest address

35012 MCKENZIE DR. SPRINGFIELD, OR. 97478

(10) STATIC WATER LEVEL

Date SWL(psi) + SWL(ft)

Existing Well / Pre-Alteration

Completed Well 4/13/2026 42

Flowing Artesian? ☐ Dry Hole? ☐**WATER BEARING ZONES**

Depth water was first found 155.00

SWL Date From To Est Flow SWL(psi) + SWL(ft)

4/13/2026	155	180	32		42

(11) WELL LOG

Ground Elevation 460.58 FT

Material	From	To
Paved driveway	0	1
Clay w/gravel	1	6
Clay broken rock	6	19
Weathered sandstone redish/brown	19	44
Sandstone Light brown W/clay layers brown	44	109
SS cong. medium to hard some quartz white	109	155
Sandstone brown w/quartz hard/fractured	155	180

Construction

Begin Date 4/8/2026 Begin Time 10 00 End Date 4/13/2026

(unbonded) Water Well Constructor Certification

I certify that the work I performed on the construction, deepening, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

License Number Date

Signed

(bonded) Water Well Constructor Certification

I accept responsibility for the construction, deepening, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

License Number 1723 Date 5/9/2026

Signed WILLIAM FIELDER (E-filed)

Drilling Company: Bill Fielder well drilling and pump service

ORIGINAL - WATER RESOURCES DEPARTMENT

THIS REPORT MUST BE SUBMITTED TO THE WATER RESOURCES DEPARTMENT WITHIN 30 DAYS OF COMPLETION OF WORK Form Version:

New exempt use wells must be submitted with a map and recording fee.

Comments/Remarks

STATE OF OREGON WELL LOCATION MAP

This map is supplemental to the WATER SUPPLY WELL REPORT

Oregon Water Resources Department

725 Summer St NE, Salem OR 97301
(503)986-0900



LOCATION OF WELL

Latitude: 44.08862665 Datum: WGS84

Longitude: -122.97520064

Township/Range/Section/Quarter-Quarter Section:

WM 17S 2W 18 NWSE

Address of Well:

35012 MCKENZIE DR. SPRINGFIELD, OR. 97478

Well Label: L159627

Well Log: LANE 80627

Printed: June 8, 2026

DISCLAIMER: This map is intended to represent the approximate location of the exempt use well provided by the land owner. It is not intended to be construed as survey accurate in any manner.

Generated by OWRD

