

STATE OF OREGON
WATER SUPPLY WELL REPORT

LANE 80720

WELL I.D. LABEL# L

162155

START CARD #

1082933

ORIGINAL LOG #

(as required by ORS 537.545 & 537.765 and OAR 690-205-0210)

7/27/2026

(1) LAND OWNER

Owner Well I.D.

First Name BAJWA

Last Name CHARANJEET SINGH

Company

Address 3642 ROCKRESS RD.

City EUGENE

State OR

Zip 97403

(2) TYPE OF WORK☒ New Well ☐ Deepening ☐ Conversion☐ Alteration (complete 2a & 10) ☐ Abandonment (complete 5a)**(2a) PRE-ALTERATION**

Casing: Dia + From To Gauge Stl Plstc Wld Thrd
Material From To Amt sacks/lbs
Seal: Material From To Amt sacks/lbs

(3) DRILL METHOD

☒ Rotary Air ☐ Rotary Mud ☐ Cable ☐ Auger
☐ Reverse Rotary ☐ Other

(4) PROPOSED USE☒ Domestic ☐ Irrigation ☐ Community☒ Industrial/ Commercial ☐ Livestock ☐ Dewatering☐ Thermal ☐ Injection ☐ Other**(5) BORE HOLE CONSTRUCTION**Special Standard ☐ (Attach copy)

Depth of Completed Well 205.00 ft.

BORE HOLE				SEAL			
Dia	From	To	Material	From	To	Amt	sacks/lbs
10	0	38	Bentonite	0	38	22	S
6	38	205			Calculated	17.34	
					Calculated		

Seal placement method: ☐ A ☐ B ☐ C ☐ D ☐ E ☒ Other: POURED AND TAMPED

Backfill placed from ft. to ft. Material

Filter pack from ft. to ft. Material Size

Explosives used: ☐ Type Amount

Seal Placement Begin Date 7/22/2026 Begin Time 11:00

(5a) ABANDONMENT USING UNHYDRATED BENTONITE

Proposed Amount

Actual Amount

(6) CASING/LINER

C/L	Dia	+ From To Gauge	Mat. Type	Wld	Thrd	Shoe Location
C	6	☒ 2 38 0.250	ST	☒		OUT. 38
L	4	☐ 5 205 SDR26	PL	☒		

Temp casing ☐ Yes Dia From + To**(7) PERFORATIONS/SCREENS**

Perforations Method Saw

Screens Type

Material

Perf/ Screen	Casing/ Liner	Screen Dia	From	To	Scrm/slot width	Slot length	# of slots	Tele/ Pipe size
Perf	Liner	4	125	145	.125	1	200	
Perf	Liner	4	185	205	.125	1	200	

(8) WELL TESTS: Minimum testing time is 1 hour

Type of Test	Yield (gal/min)	Drawdown	Drill Stem/ Pump Depth	Duration (hr)
Air	5		204	1

Temperature 51 °F Lab analysis ☐ Yes ByWater quality concerns? ☐ Yes (describe below) TDS amount 177 ppm

From To	Description	Amount	Units

(9) LOCATION OF WELL (legal description)

County LANE Twp 16.00 S N/S Range 6.00 W E/W WM

Sec 7 SE 1/4 of the SE 1/4 Tax Lot 400

Tax Map Number Lot

Lat ° ' " or 44.18950995 DMS or DD

Long ° ' " or -123.45523576 DMS or DD

☒ Street address of well ☐ Nearest address

22505 HWY 36 LOW PASS CHEVRON

(10) STATIC WATER LEVEL

	Date	SWL (psi)	+	SWL (ft)
Existing Well / Pre-Alteration				
Completed Well	7/23/2026			30
Flowing Artesian?	☐	Dry Hole?	☐	

WATER BEARING ZONES

Depth water was first found 50.00

SWL Date	From	To	Est Flow	SWL (psi)	+	SWL (ft)
7/23/2026	50	51	3.5			30
7/23/2026	105	106	1.5			30

(11) WELL LOG

Ground Elevation 627.75 FT

Material	From	To
Top Soil	0	1
Sandy Brown Clay	1	13
Blue Claystone	13	50
Blue Sandstone	50	105
Red Claystone	105	110
Blue Claystone	110	205

Construction

Begin Date 7/22/2026 Begin Time 06:50 End Date 7/23/2026

(unbonded) Water Well Constructor Certification

I certify that the work I performed on the construction, deepening, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

License Number 2002 Date 7/27/2026

Signed MAXWELL JONES (E-filed)

(bonded) Water Well Constructor Certification

I accept responsibility for the construction, deepening, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

License Number 2002 Date 7/27/2026

Signed MAXWELL JONES (E-filed)

Drilling Company: Casey Jones Well Drilling

ORIGINAL - WATER RESOURCES DEPARTMENT

THIS REPORT MUST BE SUBMITTED TO THE WATER RESOURCES DEPARTMENT WITHIN 30 DAYS OF COMPLETION OF WORK Form Version:

New exempt use wells must be submitted with a map and recording fee.

WATER SUPPLY WELL REPORT - Map with location identified must be attached and shall include an approximate scale and north arrow

LANE 80720

7/27/2026

Map of Hole

STATE OF OREGON WELL LOCATION MAP

This map is supplemental to the WATER SUPPLY WELL REPORT

Oregon Water Resources Department

725 Summer St NE, Salem OR 97301
(503)986-0900



LOCATION OF WELL

Latitude: 44.18950995 Datum: WGS84

Longitude: -123.45523576

Township/Range/Section/Quarter-Quarter Section:

WM16.00S6.00W7SESE

Address of Well:

22505 HWY 36 LOW PASS CHEVRON

Well Label: 162155

Printed: July 27, 2026

DISCLAIMER: This map is intended to represent the approximate location the well. It is not intended to be construed as survey accurate in any manner.

Provided by well constructor

