

NOTICE TO WATER WELL CONTRACTOR

The original and first copy of this report are to be filed with the

STATE ENGINEER, SALEM, OREGON 97310 within 30 days from the date of well completion.

RECEIVED
OCT 23 1969
STATE OF OREGON
STATE ENGINEER
SALEM, OREGON

WATER WELL REPORT

(Please type or print)

(Do not write above this line)

LANE
8260

State Well No. 16/4W-380

State Permit No. G 5021

(1) OWNER:

Name Richard Burton

Address 2700 Meadowview Rd Junction City, OR

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☐ Driven ☐
Cable ☒ Jetted ☐
Dug ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☐ Industrial ☐ Municipal ☐
Irrigation ☐ Test Well ☒ Other ☐

CASING INSTALLED:

Threaded ☐ Welded ☒
8" Diam. from GL ft. to 35 ft. Gage 250

" Diam. from _____ ft. to _____ ft. Gage _____

" Diam. from _____ ft. to _____ ft. Gage _____

PERFORATIONS:

Perforated? ☒ Yes ☐ No.

Type of perforator used Torch

Size of perforations 1/4 in. by 6 in.

100 perforations from 18 ft. to 38 ft.

perforations from _____ ft. to _____ ft.

perforations from _____ ft. to _____ ft.

perforations from _____ ft. to _____ ft.

perforations from _____ ft. to _____ ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name _____

Type _____ Model No. _____

Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.

Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.

(8) WATER LEVEL: Completed well.

Static level 4 ft. below land surface Date 10/10/67

Artesian pressure _____ lbs. per square inch Date _____

(9) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? ☐ Yes ☒ No If yes, by whom?

Yield: _____ gal./min. with _____ ft. drawdown after _____ hrs.

" " " " "

" " " " "

Bailer test 100 gal./min. with 11 ft. drawdown after 1 hrs.

Artesian flow _____ g.p.m. Date _____

Temperature of water _____ Was a chemical analysis made? ☐ Yes ☒ No

(10) CONSTRUCTION:

Well seal—Material used Cement

Depth of seal 18 ft.

Diameter of well bore to bottom of seal 10 in.

Were any loose strata cemented off? ☐ Yes ☒ No Depth _____

Was a drive shoe used? ☒ Yes ☐ No

Did any strata contain unusable water? ☐ Yes ☒ No

Type of water? _____ depth of strata _____

Method of sealing strata off _____

Was well gravel packed? ☐ Yes ☒ No Size of gravel: _____

Gravel placed from _____ ft. to _____ ft.

(11) LOCATION OF WELL:

County Lane Driller's well number _____

Bearing and distance from section or subdivision corner _____

(12) WELL LOG:

Diameter of well below casing 8

Depth drilled 38 ft. Depth of completed well 38 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level as drilling proceeds. Note drilling rates.

MATERIAL	From	To	SWL
Clay	0	12	
Clay sand gravel	12	18	
Sand & gravel	18	22	10'
Sand gravel & clay	22	25	
Sand & small gravel	25	38	4'

Work started 10/7 1967 Completed 10/10 1967

Date well drilling machine moved off of well 10/10 1967

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] R. D. Johnson Date 24, 1967
(Drilling Machine Operator)

Drilling Machine Operator's License No. 24

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

NAME W. H. Drilling & Pump Ser
(Person, firm or corporation) (Type or print)

Address 2320 MAIN - Springfield, OR

[Signed] Walt Johnson
(Water Well Contractor)

Contractor's License No. 268 Date 10/21, 1968