

RECEIVED

WATER WELL REPORT  
STATE OF OREGON

LANE 8306  
8306  
774

AUG 5 1981

State Well No. 165/40-34AA

WATER RESOURCES DEPT  
SALEM, OREGON

(1) OWNER:

Name GARY JONES  
Address 9154 RIVER ROAD  
City JUNCTION CITY State OR

(2) TYPE OF WORK (check):

New Well  Deepening  Reconditioning  Abandon   
If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary Air  Driven   
Rotary Mud  Dug   
 Bored

(4) PROPOSED USE (check):

Domestic  Industrial  Municipal   
Irrigation  Test Well  Other   
Thermal: Withdrawal  Reinjection

(5) CASING INSTALLED:

Steel  Plastic   
Threaded  Welded   
8" Diam. from +1 1/2 ft. to 2 1/2 ft. Gauge 2.50

LINER INSTALLED:

" Diam. from ..... ft. to ..... ft. Gauge .....

(6) PERFORATIONS:

Perforated?  Yes  No  
Type of perforator used HOLTE  
Size of perforations 1/4 in. by 1/4 in.  
120 perforations from 61 ft. to 71 ft.

(7) SCREENS:

Well screen installed?  Yes  No  
Manufacturer's Name .....  
Type ..... Model No. ....  
Diam. .... Slot Size ..... Set from ..... ft. to ..... ft.

(8) WELL TESTS:

Drawdown is amount water level is lowered below static level  
Was a pump test made?  Yes  No If yes, by whom?  
" " " " " "  
Air test 70 gal./min. with drill stem at 75 ft. 2 hrs.  
Bailer test ..... gal./min. with ..... ft. drawdown after ..... hrs.  
Artesian flow ..... g.p.m.  
Temperature of water ..... Depth artesian flow encountered ..... ft.

(9) CONSTRUCTION:

Special standards: Yes  No   
Well seal—Material used CEMENT  
Well sealed from land surface to 18' ft.  
Diameter of well bore to bottom of seal 12 in.  
Diameter of well bore below seal 6 in.  
Number of sacks of cement used in well seal 11 sacks  
How was cement grout placed? PRESSURE GROUT

Was pump installed? YES Type SUB HP 3 Depth 65 ft.  
Was a drive shoe used?  Yes  No Plugs ..... Size: location ..... ft.  
Did any strata contain unusable water?  Yes  No  
Type of Water? ..... depth of strata .....  
Method of sealing strata off .....  
Was well gravel packed?  Yes  No Size of gravel: .....  
Gravel placed from ..... ft. to ..... ft.

(10) LOCATION OF WELL:

County LANE Driller's well number .....  
NE 1/4 NE 1/4 Section 34 T. 16S R. 4W W.M.  
Tax Lot # 400 Lot Blk Subdivision .....  
Address at well location: (1) OWNERS

(11) WATER LEVEL: Completed well.

Depth at which water was first found 18' ft.  
Static level 15' ft. below land surface. Date .....  
Artesian pressure ..... lbs. per square inch. Date .....

(12) WELL LOG:

Diameter of well below casing 6 .....  
Depth drilled 82' ft. Depth of completed well 73 ft.  
Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
RIVER LOAM	0	14	
SANDY GRAVEL 3/4 MINUS	14	33	15
SDY GRAVEL	33	45	"
CEMENTED GRAVEL	45	62	"
SANDY GRAVEL (water bearing)	62	82	"

Work started 13 JULY 1981 Completed 14 JULY 1981  
Date well drilling machine moved off of well 14 JULY 1981

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.  
[Signed] Walter N. White Date 30 JULY 81  
(Drilling Machine Operator)  
Drilling Machine Operator's License No. 1086

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.  
Name Walter N. White Drilling  
(Person, firm or corporation) (Type or print)  
Address 91769 PRAIRIE RD JUNCTION CITY  
[Signed] Walter N. White  
(Water Well Contractor)  
Contractor's License No. 638 Date 30 JULY 1981

NOTICE TO WATER WELL CONTRACTOR  
The original and first copy of this report are to be filed with the

WATER RESOURCES DEPARTMENT,  
SALEM, OREGON 97310  
within 30 days from the date of well completion.

SP\*12658-690

LANE 8306  
WELL IDENTIFICATION FORM

CURRENT WELL OWNER:

Owner's Well Number: 2

Name: GARY & INEZ JONES

Mailing Address: 91154 RIVER RD.

City: JUNCTION CITY State: OR Zip: 97478

*If a well report is available for this well, please attach a copy of it to this form and return. It is not necessary for you to complete the remainder of the form if the well report is attached. If a well report is not available, please complete the remainder of the form to the best of your ability.*

WELL LOCATION:

LANE 8306

**RECEIVED**

County: LANE Latitude: \_\_\_\_\_ Longitude: DEC 16 1999

Township: \_\_\_\_\_ N or S, Range: \_\_\_\_\_ E or W Section: \_\_\_\_\_

WATER RESOURCES DEPT.  
1/4 SALEM, OREGON 4

Tax Lot Number: 1604340000402

Street Address of Well (if different from above): \_\_\_\_\_

WELL INFORMATION:

Start Card Number: 2 Approx. Construction Date: 1980

Well Constructor: UNKNOWN

Name of Owner at Time of Construction: GARY D. JONES

Well Depth (in feet): 60' Static Water Level (in feet): UNKNOWN

Diameter of Exposed Well Casing (in inches): 8"

Does this well have a formal water right associated with it? Yes: \_\_\_\_\_ No:  If yes:

Application #: \_\_\_\_\_ Permit #: \_\_\_\_\_ Certificate #: \_\_\_\_\_

Please Return Completed Form to: Oregon Water Resources Department  
158 12th Street NE  
Salem, OR 97310

(Office use only)

Well Identification Number: 39009