

WATER WELL REPORT
STATE OF OREGON

001448

LINE

RECEIVED

State Well No.

13510W-32

AUG 21 1981

State Permit No.

WATER RESOURCES DEPT
SALEM, OREGON

(1) OWNER:

Name Kent Campazzi
Address P.O. Box 794
City Tidewater State OREGON

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary Air ☒ Driven ☐
Rotary Mud ☐ Dug ☐
☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐
Irrigation ☐ Test Well ☐ Other ☐
Thermal: Withdrawal ☐ Reinjection ☐

(5) CASING INSTALLED:

Steel ☒ Plastic ☐
Threaded ☐ Welded ☒
6" Diam. from +1 ft. to 54 ft. Gauge 250
" Diam. from ft. to ft. Gauge

LINER INSTALLED:

" Diam. from ft. to ft. Gauge

(6) PERFORATIONS:

Perforated? ☐ Yes ☒ No

Type of perforator used

Size of perforations in. by in.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name

Type Model No.

Diam. Slot Size Set from ft. to ft.

Diam. Slot Size Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? ☐ Yes ☒ No If yes, by whom?

Field: gal./min. with ft. drawdown after hrs.

" " " " "

Air test 5 gal./min. with drill stem at 215 ft. 1 hrs.

Bailer test gal./min. with ft. drawdown after hrs.

Artesian flow g.p.m.

Temperature of water Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Special standards: Yes ☐ No ☒

Well seal—Material used Cement Grout

Well sealed from land surface to 58 ft.

Diameter of well bore to bottom of seal 10 in.

Diameter of well bore below seal 6 in.

Number of sacks of cement used in well seal 38 sacks

How was cement grout placed? Pressure pumped from Bottom of well seal

Was pump installed? yes Type Sub HP 3/4 Depth 300 ft.

Was a drive shoe used? ☐ Yes ☒ No Plugs Size: location ft.

Did any strata contain unusable water? ☐ Yes ☒ No

Type of Water? depth of strata

Method of sealing strata off

Was well gravel packed? ☐ Yes ☒ No Size of gravel: ft.

Gravel placed from ft. to ft.

(10) LOCATION OF WELL:

County Lincoln Driller's well number 3381
Tax Lot # Section 32 T. 13 S R. 10 W W.M.
Lot Blk Subdivision

Address at well location:

(11) WATER LEVEL: Completed well.

Depth at which water was first found 190 ft.

Static level 97 ft. below land surface. Date 7-23-81

Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing 6

Depth drilled 215 ft. Depth of completed well 215 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
Clay yellow	0	16	
Broken Sandrock, yellow	16	30	
Clay			
Sandrock Brown hard	30	70	
Sandrock hard hard	70	190	
Sandrock Broken w/yr	190	192	97'
Sandrock Grey	192	215	
water strata		190'	

Work started 7-20 1981 Completed 7-23 1981
Date well drilling machine moved off of well 7-23 1981

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] Ferry W. Mutschler Date 7-30, 1981
(Drilling Machine Operator)

Drilling Machine Operator's License No. 80

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

Name M-H well Drilling Inc
(Person, firm or corporation) (Type or print)

Address 4051 N.E. Holly Acres Cir. Ore

[Signed] Ferry W. Mutschler
(Water Well Contractor)

Contractor's License No. 237 Date July 30, 1981

NOTICE TO WATER WELL CONTRACTOR
The original and first copy of this report
are to be filed with the

WATER RESOURCES DEPARTMENT,
SALEM, OREGON 97310
within 30 days from the date of well completion.

SP*12658-690