

STATE OF OREGON
WATER SUPPLY WELL REPORT

LINC 54965

WELL I.D. LABEL# L

Page 1 of 3

(as required by ORS 537.545 & 537.765 and OAR 690-205-0210)

9/4/2026

START CARD #
ORIGINAL LOG #

162113
1083323

(1) LAND OWNER

Owner Well I.D.

First Name SAM Last Name SCHEINBERG
Company
Address 5590 E DEVILS LAKE RD
City OTIS State OR Zip 97368

(2) TYPE OF WORK

☒ New Well ☐ Deepening ☐ Conversion

☐ Alteration (complete 2a & 10) ☐ Abandonment (complete 5a)

(2a) PRE-ALTERATION

Casing: Dia + From To Gauge Std Plstc Wld Thrd
Material From To Amt sacks/lbs
Seal: Material From To Amt sacks/lbs

(3) DRILL METHOD

☒ Rotary Air ☐ Rotary Mud ☐ Cable ☐ Auger
☐ Reverse Rotary ☐ Other

(4) PROPOSED USE

☒ Domestic ☐ Irrigation ☐ Community
☐ Industrial/ Commercial ☐ Livestock ☐ Dewatering
☐ Thermal ☐ Injection ☐ Other

(5) BORE HOLE CONSTRUCTION

Special Standard ☐ (Attach copy)

Depth of Completed Well 120.00 ft.

BORE HOLE			SEAL			Amt	sacks/ lbs
Dia	From	To	Material	From	To		
10	0	38.5	Bentonite Chips	0	38.5	18	S
6.75	38.5	123			Calculated	17	
					Calculated		

Seal placement method: ☐ A ☐ B ☐ C ☐ D ☐ E ☒ Other: POURED AND PROBED

Backfill placed from 120 ft. to 123 ft. Material SLUFF GRAVEL

Filter pack from ft. to ft. Material Size

Explosives used: ☐ Type Amount

Seal Placement Begin Date 8/31/2026 Begin Time 14 00

(5a) ABANDONMENT USING UNHYDRATED BENTONITE

Proposed Amount Actual Amount

(6) CASING/LINER

C/L	Dia	+ From To Gauge	Mat. Type	Wld	Thrd	Shoe	Location
C	6	☒ 1.5 38.5 0.250	ST	☒		OUT.	38.5
L	4	☐ 0 120 Sch40	PL		☒		

Temp casing ☒ Yes Dia 10 From + 0 To 5

(7) PERFORATIONS/SCREENS

Perforations Method Electric saw

Screens Type Material

Perf/ Screen	Casing/ Liner	Screen Dia	From	To	Scrn/slot width	Slot length	# of slots	Tele/ Pipe size
Perf	Liner	4	80	120	.125	6	60	

(8) WELL TESTS: Minimum testing time is 1 hour

Type of Test	Yield (gal/min)	Drawdown	Drill Stem/ Pump Depth	Duration (hr)
Air	75		120	1
Pump	20	10	80	1.3

Temperature 54 °F Lab analysis ☐ Yes By

Water quality concerns? ☐ Yes (describe below) TDS amount 163 ppm
From To Description Amount Units

(9) LOCATION OF WELL (legal description)

County LINCOLN Twp 6.00 S N/S Range 11.00 W E/W WM

Sec 36 NW 1/4 of the SE 1/4 Tax Lot 900

Tax Map Number Lot

Lat ° ' " or 45.00685438 DMS or DD

Long ° ' " or -123.97634301 DMS or DD

☒ Street address of well ☐ Nearest address

5590 E DEVILS LAKE RD, OTIS, OR 97368

(10) STATIC WATER LEVEL

	Date	SWL (psi)	+	SWL (ft)
Existing Well / Pre-Alteration				
Completed Well	9/1/2026			38
Flowing Artesian?	☐	Dry Hole?	☐	

WATER BEARING ZONES

Depth water was first found 38.00

SWL Date From To Est Flow SWL (psi) + SWL (ft)

9/1/2026	38	105	75		38

(11) WELL LOG

Ground Elevation 176.87 FT

Material	From	To
Topsoil	0	2
Clay Brown	2	10
Claystone Tan	10	23
Claystone Grey	23	55
Claystone Grey & Brown Conglomerate w/ White Frac	55	107
Claystone Grey and Brown Conglomerate	107	123

Construction

Begin Date 8/31/2026 Begin Time 08 00 End Date 9/1/2026

(unbonded) Water Well Constructor Certification

I certify that the work I performed on the construction, deepening, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

License Number 2090 Date 9/1/2026

Signed JACK BOLLER (E-filed)

(bonded) Water Well Constructor Certification

I accept responsibility for the construction, deepening, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

License Number 1394 Date 9/4/2026

Signed EUGENE MACK (E-filed)

Drilling Company: Mack Drilling Company Inc.

ORIGINAL - WATER RESOURCES DEPARTMENT

THIS REPORT MUST BE SUBMITTED TO THE WATER RESOURCES DEPARTMENT WITHIN 30 DAYS OF COMPLETION OF WORK Form Version:

New exempt use wells must be submitted with a map and recording fee.

Comments/Remarks

WATER SUPPLY WELL REPORT - Map with location identified must be attached and shall include an approximate scale and north arrow

LINC 54965

9/4/2026

Map of Hole

STATE OF OREGON WELL LOCATION MAP

This map is supplemental to the WATER SUPPLY WELL REPORT

Oregon Water Resources Department

725 Summer St NE, Salem OR 97301
(503)986-0900



LOCATION OF WELL

Latitude: 45.00685438 Datum: WGS84

Longitude: -123.97634301

Township/Range/Section/Quarter-Quarter Section:
WM6.00S11.00W36NWSE

Address of Well:

5590 E DEVILS LAKE RD, OTIS, OR 97368

Well Label: 162113

Printed: September 1, 2026

DISCLAIMER: This map is intended to represent the approximate location the well. It is not intended to be construed as survey accurate in any manner.

Provided by well constructor

