

WATER WELL REPORT
STATE OF OREGON

LINN
109.28

RECEIVED

FEB 25 1983

State Well No. 12525-2.664

State Permit No.

PLEASE TYPE IN BLOCK LETTERS
WATER RESOURCES DEPT.
SALEM, OREGON

(1) OWNER:

Name Paul Willetts (Crown-Zellerbach)
Address Containerboard Div. One Bush Street
City San Francisco, California State 94104

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary Air ☐ Driven ☐ Domestic ☒ Industrial ☐ Municipal ☐
Rotary Mud ☒ Dug ☐ Irrigation ☒ Test Well ☐ Other ☐
☐ Bored ☐ Thermal ☐ Withdrawal ☐ Reinjection ☐

(4) PROPOSED USE (check):

(5) CASING INSTALLED:

Steel ☐ Plastic ☒
Threaded ☐ Welded ☒

6" Diam. from 1 ft. to 100 ft. Gauge PVC200
" Diam. from ft. to ft. Gauge

(6) LINER INSTALLED:

" Diam. from ft. to ft. Gauge

(6) PERFORATIONS:

Perforated? ☒ Yes ☐ No

Type of perforator used SAW
Size of perforations 1/8 in. by 12 in.
20 perforations from 95 ft. to 100 ft.
perforations from ft. to ft.
perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name
Type Model No.
Diam. Slot Size Set from ft. to ft.
Diam. Slot Size Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? ☐ Yes ☒ No If yes, by whom?
Lift 60 gal./min. with 70 ft. drawdown after 2 hrs.
" 25 " 30 " "
Air test gal./min. with drill stem at ft. hrs.
Bailer test gal./min. with ft. drawdown after hrs.
Artesian flow g.p.m.
Temperature of water 13° C Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Special standards: Yes ☒ No ☐

Well seal—Material used Cement grout + gel
Well sealed from land surface to 80 ft.
Diameter of well bore to bottom of seal 10 in.
Diameter of well bore below seal 8 in.
Number of sacks of cement used in well seal 18 sacks
How was cement grout placed? Pumped in place @ 80' to ground level

Was pump installed? Yes Type Meyer's 1/3 Depth 35 ft.
Was a drive shoe used? ☐ Yes ☒ No Plugs Size: location ft.
Did any strata contain unusable water? ☒ Yes ☐ No
Type of Water? acid & mineral Depth of strata 15' to 35'
Method of sealing strata off cased and grouted
Was well gravel packed? ☐ Yes ☒ No Size of gravel: ft.
Gravel placed from ft. to ft.

(10) LOCATION OF WELL:

County Linn Driller's well number
1/4 1/4 Section 2BBD T.12 S R. 2 E/ W.M.
Tax Lot # Lot Blk Subdivision
Address at well location:

(11) WATER LEVEL: Completed well.

Depth at which water was first found 15 ft.
Static level 10 ft. below land surface. Date 2/18/83
Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing 0

Depth drilled 108 ft. Depth of completed well 100 ft.
Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
Brown silty-sandy loam	0	12	
Brown silty sand & gravel== compact	12	23	10'
Brown compact sand & medium gravel--occ. cobbles--occ. loose	23	31	10'
Brown sand & gravel (cement w/ silty clay	31	33	
Gray-brown silty clay-occ. gravel	33	38	
Dark blue silty clay--occ. peagravel	38	41	
Gray silty clay-occ. peagravel			
occ. wood	41	60	
Gray silty claystone	60	78	
Blue gritty clay-occ. sandstone	78	93	
Blue semi-cemented sand and gravel	93	105	10'
Gray clay w/wood	105	108	

Work started 2/14/83 19 Completed 2/18/83 19
Date well drilling machine moved off of well 2/18/83 19

(unbonded) Water Well Constructor Certification (if applicable):

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] Date, 19

Bonded Water Well Constructor Certification:

Bond Issued by: GREAT AMERICAN INS. Surety Company Name

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

Name A. M. JANNSEN WELL DRILLING CO., INC. (Type or print)

Address 21075 SW Tualatin Valley Hwy. Aloha, O.

[Signed] Date, 19

NOTICE TO WATER WELL CONSTRUCTOR
The original and first copy of this report are to be filed with the

WATER RESOURCES DEPARTMENT,
SALEM, OREGON 97310
within 30 days from the date of well completion.

SP*45292-690