

NOTICE TO WATER WELL CONTRACTOR

The original and first copy of this report are to be filed with the

STATE ENGINEER, SALEM, OREGON 97310

within 30 days from the date of well completion.

RECEIVED

WATER WELL REPORT

NOV 1 1968

STATE OF OREGON

STATE ENGINEER (Please type or print)

SALEM, OREGON (Do not write above this line)

4 INN
10986

State Well No. 13/1w-5 4abb

State Permit No. G-4720

(1) OWNER:

Name Bauman Lumber Co.Address Lebanon, Oregon

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☐ Driven ☐
Cable ☒ Jetted ☐
Dug ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☐ Industrial ☐ Municipal ☒
Irrigation ☐ Test Well ☐ Other ☐

CASING INSTALLED:

10" Diam. from + 1 1/2 ft. to 120 1/2 ft. Gage 250 Wall
" Diam. from ft. to ft. Gage
" Diam. from ft. to ft. Gage

PERFORATIONS:

Perforated? ☒ Yes ☐ No.Type of perforator used Acetylene Torch

Size of perforations 3/8 in. by 12 in.
64 perforations from 120 ft. to 106 ft.
perforations from ft. to ft.
1/2" x 3" With Nials Perforator ft. to ft.
88 perforations from 47 ft. to 25 ft.
perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name

Type Model No.

Diam. Slot size Set from ft. to ft.

Diam. Slot size Set from ft. to ft.

(8) WATER LEVEL: Completed well.

Static level 11'06" ft. below land surface Date 9-26-68

Artesian pressure lbs. per square inch Date

(9) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? ☐ Yes ☒ No If yes, by whom?

Yield: gal./min. with ft. drawdown after hrs.

" " " "

" " " "

Ball test 100 gal./min. with 25 ft. drawdown after 1 1/2 hrs.

Artesian flow g.p.m. Date

Temperature of water Was a chemical analysis made? ☐ Yes ☒ No

(10) CONSTRUCTION:

Well seal—Material used BentoniteDepth of seal 18 ft.Diameter of well bore to bottom of seal 14 in.Were any loose strata cemented off? ☐ Yes ☒ No DepthWas a drive shoe used? ☒ Yes ☐ NoDid any strata contain unusable water? ☐ Yes ☒ No

Type of water? depth of strata

Method of sealing strata off

Was well gravel packed? ☐ Yes ☒ No Size of gravel:

Gravel placed from ft. to ft.

(11) LOCATION OF WELL:

County Linn

Driller's well number

1/4 1/4 Section 15 T. 13S R. 1W W.M.

Bearing and distance from section or subdivision corner

(12) WELL LOG:

Diameter of well below casing 10"Depth drilled 150 ft. Depth of completed well 150 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level as drilling proceeds. Note drilling rates.

MATERIAL	From	To	SWL
Top Soil	0	2	
Yellow Clay & Gravel	2	24	
Coarse Gravel	24	29	
Dirty Gravel	29	38	
Clay & Gravel	38	42	
Yellow Clay & Gravel	42	103	
Gravel	103	117	
Blue Clay	117	132	
Brown Clay	132	139	
Red Rock & Clay	139	150	

Work started 9-17 19 68 Completed 9-26 1968Date well drilling machine moved off of well 9-26 1968

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] Merle Warren Date 10/10, 1968
(Drilling Machine Operator)

Drilling Machine Operator's License No. 436

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

NAME Merle Warren Well Drilling
(Person, firm or corporation) (Type or print)

Address Rt. 1, Box 85, Tangent, Ore. 97389

[Signed] Merle Warren
(Water Well Contractor)

Contractor's License No. 182 Date 10-10, 1968