

NOTICE TO WATER WELL CONTRACTOR

The original and first copy
of this report are to be
filed with the

STATE ENGINEER, SALEM, OREGON
within 30 days from the date
of well completion.

RECEIVED
MAR 2 1970
STATE OF OREGON
STATE ENGINEER
SALEM, OREGON

(Please type or print)

(Write above this line)

State Well No. 13/1W-10State Permit No. well #1

(1) OWNER:

Name Boise Cascade Co, P.O. Box 127Address Independence, Oregon

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☐ Driven ☐
Cable ☒ Jetted ☐
Dug ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☐ Industrial ☐ Municipal ☐
Irrigation ☐ Test Well ☒ Other ☐

CASING INSTALLED:

Threaded ☐ Welded ☒

8" Diam. from 0 ft. to 126 ft. Gage .250

" Diam. from ft. to ft. Gage

" Diam. from ft. to ft. Gage

PERFORATIONS:

Perforated? ☒ Yes ☐ No.Type of perforator used Mills MillsSize of perforations 3/8 in. by 4 in.

384 perforations from 29 ft. to 125 ft.

perforations from ft. to ft.

perforations from ft. to ft.

perforations from ft. to ft.

perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name

Type Model No.

Diam. Slot size Set from ft. to ft.

Diam. Slot size Set from ft. to ft.

(8) WATER LEVEL: Completed well.

Static level 25 ft. below land surface Date 2-23-70

Artesian pressure lbs. per square inch Date

(9) WELL TESTS:

Drawdown is amount water level is
lowered below static levelWas a pump test made? ☒ Yes ☐ No If yes, by whom?

Yield: gal./min. with ft. drawdown after hrs.

" " " "

" " " "

Bailer test 30 gal./min. with 145 ft. drawdown after 1 hrs.

Artesian flow g.p.m. Date

Temperature of water Was a chemical analysis made? ☐ Yes ☒ No

(10) CONSTRUCTION:

Well seal—Material used Cement & Puddled ClayDepth of seal 26 ft.Diameter of well bore to bottom of seal 12 in.Were any loose strata cemented off? ☐ Yes ☒ No DepthWas a drive shoe used? ☒ Yes ☐ NoDid any strata contain unusable water? ☐ Yes ☒ No

Type of water? depth of strata

Method of sealing strata off

Was well gravel packed? ☐ Yes ☒ No Size of gravel:

Gravel placed from ft. to ft.

(11) LOCATION OF WELL:

County Linn

Driller's well number

1/4 1/4 Section 10 T. 13S R. 1W W.M.

Bearing and distance from section or subdivision corner

(12) WELL LOG:

Diameter of well below casing 8Depth drilled 175 ft. Depth of completed well 175 ft.

Formation: Describe color, texture, grain size and structure of materials;
and show thickness and nature of each stratum and aquifer penetrated,
with at least one entry for each change of formation. Report each change
in position of Static Water Level as drilling proceeds. Note drilling rates.

MATERIAL	From	To	SWL
Little Boulders	0	7	
Big Boulders	7	14	
Coarse Black Gravel	14	18	
Fine Black Sand	18	20	
Coarse White Sand	20	25	
Mud & Gravel	25	57	
Fine White Sand	57	63	
Yellow Clay	63	75	
Coarse Black Sand	75	77	
Blue Sandy Clay	77	100	
Black Sand	100	102	
Blue Sand Clay	102	128	
Soft Claystone Chocolate	128	147	
Black Sand	147	160	
Soft Claystone Chocolate	160	175	

Work started 1-28-70 19 Completed 2-23-70 19Date well drilling machine moved off of well 2-23-70 19

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Mate-
rials used and information reported above are true to my best
knowledge and belief.

[Signed] Alvin H. Hester Date 2-25-70, 19

(Drilling Machine Operator)

Drilling Machine Operator's License No. 652

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is
true to the best of my knowledge and belief.

NAME Casey Jones Well Drilling Co Inc

(Person, firm or corporation)

(Type or print)

Address R-8 Box 695 Pleasant Hill, Oregon[Signed] Robert H. Jones

(Water Well Contractor)

Contractor's License No. 103 Date 2-25-70, 19