

NOTICE TO WATER WELL CONTRACTOR

The original and first copy
of this report are to be
filed with the

STATE ENGINEER, SALEM, OREGON 97301
within 30 days from the date
of well completion.

RECEIVED
JUL 8 1964
STATE ENGINEER OF OREGON
SALEM, OREGON

WATER WELL REPORT

(Please type or print)

State Well No. 13/34-18

State Permit No. _____

(1) OWNER:

Name John Pugh & Son
Address Box #190, Shedd, Ore.

(2) LOCATION OF WELL:

County Linn Driller's well number 55
NW 1/4 NW 1/4 Section 18 T. 13S R. 3W W.M.
Bearing and distance from section or subdivision corner

(3) TYPE OF WORK (check):

Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐
In abandonment, describe material and procedure in Item 12.

(4) PROPOSED USE (check):

Domestic ☐ Industrial ☐ Municipal ☐
Irrigation ☒ Test Well ☐ Other ☐

(5) TYPE OF WELL:

Rotary ☐ Driven ☐
Cable ☒ Jetted ☐
Dug ☐ Bored ☐

(6) CASING INSTALLED:

Threaded ☐ Welded ☒

8" Diam. from 0 ft. to 80 ft. Gage 250
" Diam. from " ft. to " ft. Gage
" Diam. from " ft. to " ft. Gage

(7) PERFORATIONS:

Perforated? ☒ Yes ☐ NoType of perforator used Mills

Size of perforations 1/4 in. by 2 in.
600 perforations from 25 ft. to 80 ft.
perforations from " ft. to " ft.
perforations from " ft. to " ft.
perforations from " ft. to " ft.
perforations from " ft. to " ft.

(8) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name _____ Model No. _____
Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.
Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.

(9) CONSTRUCTION:

Well seal—Material used in seal Bentonite
Depth of seal 20 ft. Was a packer used? yes
Diameter of well bore to bottom of seal 8 in.
Were any loose strata cemented off? ☐ Yes ☒ No Depth _____
Was a drive shoe used? ☒ Yes ☐ No
Was well gravel packed? ☐ Yes ☒ No Size of gravel: _____
Gravel placed from _____ ft. to _____ ft.
Did any strata contain unusable water? ☐ Yes ☒ No
Type of water? _____ depth of strata _____
Method of sealing strata off _____

(10) WATER LEVELS:

Static level 8 ft. below land surface Date 5/15/64
Artesian pressure _____ lbs. per square inch Date _____

(11) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? ☒ Yes ☐ No If yes, by whom? Becker Equip.Yield: 280 gal./min. with 55 ft. drawdown after 2 hrs.

" " " "

" " " "

Ballor test gal./min. with " ft. drawdown after " hrs.

Artesian flow g.p.m. Date

Temperature of water 53 Was a chemical analysis made? ☐ Yes ☒ No

(12) WELL LOG:

Diameter of well below casing 8Depth drilled 105 ft. Depth of completed well 105 ft.

Formation: Describe by color, character, size of material and structure, and show thickness of aquifers and the kind and nature of the material in each stratum penetrated, with at least one entry for each change of formation.

MATERIAL	FROM	TO
Dark topsoil	0'	1'
Brown clay	1'	15'
Blue clay	15'	25'
Med. Gravel & sand	25'	26'
Med. sand & fine gravel	26'	35'
Fine sand - Fine gravel (hard packed)	35'	50'
Cemented gravel	50'	56'
Hard packed sand (med.)	56'	68'
Course sand - fine gravel	68'	80'
Blue clay-black sand	80'	82'
Firm grey clay	82'	105'

Work started 6/10/64 19 Completed 8/15/64 19Date well drilling machine moved off of well 6/15/64 19

(13) PUMP:

Manufacturer's Name _____ Type: _____ H.P. _____

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

NAME Pete Tolmasoff Well Drilling
(Person, firm or corporation) (Type or print)

Address Turner, Ore.Drilling Machine Operator's License No. 320

[Signed] Pete Tolmasoff
(Water Well Contractor)

Contractor's License No. 410 Date 7/1/64 19