

2

RECEIVED

NOV 22 1991 125/3W-2766  
WATER RESOURCES DEPT (START CARD) # 33499

STATE OF OREGON  
WATER WELL REPORT  
(as required by ORS 537.765)

Linn  
1363

LINN 1363

NOV 12 1991

(1) OWNER: Well Number: **WATER RESOURCES DEPT**  
Name Larry Ruckert  
Address 33660 Ridge Dr.  
City Tangent State OR Zip 97389

(9) LOCATION OF WELL by legal description:  
County Linn Latitude \_\_\_\_\_ Longitude \_\_\_\_\_  
Township 12 S N or S. Range 3 W E or W. WM.  
Section 27 NW 1/4 NW 1/4  
Tax Lot 00200 Lot \_\_\_\_\_ Block \_\_\_\_\_ Subdivision \_\_\_\_\_  
Street Address of Well (or nearest address) same

(2) TYPE OF WORK:  
 New Well  Deepen  Recondition  Abandon

(3) DRILL METHOD  
 Rotary Air  Rotary Mud  Cable  
 Other \_\_\_\_\_

(4) PROPOSED USE:  
 Domestic  Community  Industrial  Irrigation  
 Thermal  Injection  Other \_\_\_\_\_

(5) BORE HOLE CONSTRUCTION:  
Special Construction approval Yes  No  Depth of Completed Well 150 ft.  
Explosives used Yes  No  Type \_\_\_\_\_ Amount \_\_\_\_\_

HOLE			SEAL			Amount sacks or pounds
Diameter	From	To	Material	From	To	
14"	0	18'	cement	0	18"	10 1/2 sacks
10"	18'	150'				

How was seal placed: Method  A  B  C  D  E  
 Other \_\_\_\_\_  
Backfill placed from \_\_\_\_\_ ft. to \_\_\_\_\_ ft. Material \_\_\_\_\_  
Gravel placed from \_\_\_\_\_ ft. to \_\_\_\_\_ ft. Size of gravel \_\_\_\_\_

(6) CASING/LINER:

Casing:	Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
					<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
	10"	+15"	123'	.250	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
			05"		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

Liner: \_\_\_\_\_

Final location of shoets) 123'05"

(7) PERFORATIONS/SCREENS:

Perforations Method Acetylene torch  
 Screens Type \_\_\_\_\_ Material \_\_\_\_\_

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
113'01"	123'	3/8"	80	10"		<input checked="" type="checkbox"/>	<input type="checkbox"/>
	05"	x12"				<input type="checkbox"/>	<input type="checkbox"/>

(8) WELL TESTS: Minimum testing time is 1 hour  
 Pump  Bailer  Air  Flowing Artesian  
Yield gal/min 60 gpm Drawdown 50' Drill stem at \_\_\_\_\_ Time 1 hr.

Temperature of water 54 Depth Artesian Flow Found \_\_\_\_\_  
Was a water analysis done?  Yes By whom \_\_\_\_\_  
Did any strata contain water not suitable for intended use?  Too little  
 Salty  Muddy  Odor  Colored  Other \_\_\_\_\_  
Depth of strata: \_\_\_\_\_

(10) STATIC WATER LEVEL:  
12'06" ft. below land surface. Date 11-4-91  
Artesian pressure \_\_\_\_\_ lb. per square inch. Date \_\_\_\_\_

(11) WATER BEARING ZONES:

Depth at which water was first found 25

From	To	Estimated Flow Rate	SWL
25'	44'	60 gpm	12'6"

(12) WELL LOG: - Ground elevation \_\_\_\_\_

Material	From	To	SWL
Top soil	0	2	
Brown clay	2	12	
Brown clay & gravel	12	25	
Dirty brown sand & gravel	25	44	12'6"
Brown sandy clay	44	55	
Brown clay & gravel	55	76	
Blue clay & gravel	76	88	
Gray sandy clay & gravel	88	93	
Dark gray clay	93	105	
Blue clay	105	115	
Brown clay	115	120	
Black clay	120	128	
Brown clay	128	133	
Dark gray silty clay	133	140	
Black sandy clay	140	150	

Date started 10-18-91 Completed 11-4-91

(unbonded) Water Well Constructor Certification:  
I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon well construction standards. Materials used and information reported above are true to my best knowledge and belief.  
Signed \_\_\_\_\_ WWC Number \_\_\_\_\_ Date \_\_\_\_\_

(bonded) Water Well Constructor Certification:  
I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. all work performed during this time is in compliance with Oregon well construction standards. This report is true to the best of my knowledge and belief.  
Signed [Signature] WWC Number 1378 Date 11-8-91



Oregon Water Resources Department  
725 Summer Street NE, Suite A  
Salem Oregon 97301  
(503) 986-0900  
www.wrd.state.or.us

# Application for Well ID Number

RECEIVED BY OWRD

OCT 13 2015

SALEM, OR

Do not complete if the well already has a Well Identification Number.

### I. OWNER INFORMATION

Current Owner Name (please print): Larry Ruckert  
Mailing Address: 33660 Ridge Dr.  
City, State, Zip: Tangent, Or 97389  
Mail Well ID Tag to:  SAME AS ABOVE  In Care Of (C/O)  
Name & Address: \_\_\_\_\_  
City, State, Zip: \_\_\_\_\_

### II. WELL LOCATION INFORMATION (Please fill out as completely as possible)

Township: 12 (North / South) Range: 3 (East / West) Section: 27  
Tax Lot: 200 County Linn 1/4 \_\_\_\_\_ 1/4 \_\_\_\_\_  
GPS Coordinates: \_\_\_\_\_

Street Address of Well, City: 33660 Ridge Dr. Tangent, Or 97389  
If the property had a different street address in the past: Rt 1, Box 201 Tangent, Or 97389

### III. GENERAL WELL INFORMATION (Please fill out as completely as possible)

Use of Well (domestic, irrigation, commercial, industrial, monitoring): irrigation  
Date Well Constructed (or property built): \_\_\_\_\_ Total Well Depth: \_\_\_\_\_ Casing Diameter: \_\_\_\_\_  
Owner at time the well was constructed (if known): \_\_\_\_\_  
Other Information: \_\_\_\_\_

SUBMITTED BY (please print): Larry Ruckert  
PHONE: (541) 979-4121 EMAIL &/or FAX: larry.ruckert@yq600.com  
fax (541) 928-7966 (call first)

Send application to: Oregon Water Resources Department 725 Summer St NE, Suite A, Salem, Oregon 97301; or fax to (503) 986-0902. Applications are processed in the order they are received, and Well ID Numbers are mailed within 4-5 business days.

For Official Use Only by the Oregon Water Resources Department.

Received Date:  
10-13-15

Well Log Number:  
LINN 1363

Well Identification #:  
L-120421