

STATE OF OREGON  
WATER WELL REPORT  
(as required by ORS 537.765)

RECEIVED  
Linn 1856  
FEB 16 1993

(START CARD) # 48055

10s/4w/1Zab

(1) OWNER: Well Number SALEM, OREGON  
Name Cook Family Farms, Inc.  
Address 32073 Dever Conner Dr. NE  
City Albany State OR Zip 97321

(2) TYPE OF WORK:  
 New Well  Deepen  Recondition  Abandon

(3) DRILL METHOD:  
 Rotary Air  Rotary Mud  Cable  
 Other

(4) PROPOSED USE:  
 Domestic  Community  Industrial  Irrigation  
 Thermal  Injection  Other

(5) BORE HOLE CONSTRUCTION:  
Special Construction approval  Yes  No Depth of Completed Well 40 ft.  
Explosives used  Yes  No Type Amount

HOLE			SEAL			Amount sacks or pounds
Diameter	From	To	Material	From	To	
16"	0	18'	cement	0	18'	11 sacks
12"	18'	40'				

How was seal placed: Method  A  B  C  D  E  
 Other

Backfill placed from \_\_\_\_\_ ft. to \_\_\_\_\_ ft. Material \_\_\_\_\_  
Gravel placed from \_\_\_\_\_ ft. to \_\_\_\_\_ ft. Size of gravel \_\_\_\_\_

(6) CASING/LINER:

Diameter	From	To	Gauge	Seal			
				Steel	Plastic	Welded	Threaded
Casing: 12"	+12"	37'	.250	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
		01"		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Liner:				<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

Final location of shoe(s) 37'01"

(7) PERFORATIONS/SCREENS:  
 Perforations Method Acetylene torch  
 Screens Type Material

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
26'01"	37'	1/2"	100	12"		<input checked="" type="checkbox"/>	<input type="checkbox"/>
		01" x 12"				<input type="checkbox"/>	<input type="checkbox"/>

(8) WELL TESTS: Minimum testing time is 1 hour

Pump  Bailer  Air  Flowing Artesian

Yield gal/min	Drawdown	Drill stem at	Time
110 gpm	3'		1 hr.

Temperature of Water 53 Depth Artesian Flow Found \_\_\_\_\_  
Was a water analysis done?  Yes By whom \_\_\_\_\_  
Did any strata contain water not suitable for intended use?  Too little  
 Salty  Muddy  Odor  Colored  Other \_\_\_\_\_  
Depth of strata: \_\_\_\_\_

(9) LOCATION OF WELL by legal description:  
County Linn Latitude Longitude  
Township 10 S N or S. Range 4 W E or W. WM.  
Section 12 NW NE  
Tax Lot 201 Lot Block Subdivision  
Street Address of Well (or nearest address)

(10) STATIC WATER LEVEL:  
11' ft. below land surface. Date 2-2-93  
Artesian pressure lb. per square inch. Date

(11) WATER BEARING ZONES:  
Depth at which water was first found 24'

From	To	Estimated Flow Rate	SWL
24'	36'	110 gpm	11'

(12) WELL LOG:  
Ground elevation \_\_\_\_\_

Material	From	To	SWL
Top soil & gravel	0	4	
Brown clay & gravel	4	24	
Brown sand & gravel	24	36	11
Gray clay	36	40	

Date started 1-29-93 Completed 2-2-93

(unbonded) Water Well Constructor Certification:  
I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon well construction standards. Materials used and information reported above are true to my best knowledge and belief.

WWC Number \_\_\_\_\_  
Signed \_\_\_\_\_ Date \_\_\_\_\_

(bonded) Water Well Constructor Certification:  
I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon well construction standards. This report is true to the best of my knowledge and belief.

WWC Number 1378  
Signed \_\_\_\_\_ Date 2-5-93