

RECEIVED

STATE OF OREGON WATER WELL REPORT (as required by ORS 537.765)

MAY 23 1994

LINN 2181

12s/1w/33ba

(START CARD) # 60836

Instructions for completing this report are on the last page of this form.

(1) OWNER: Well Number Name Linn County Parks & Res. Address 3010 Ferry St. SW City Albany State OR Zip 97321

(2) TYPE OF WORK [X] New Well [] Deepening [] Alteration (repair/recondition) [] Abandonment

(3) DRILL METHOD: [] Rotary Air [] Rotary Mud [X] Cable [] Auger [] Other

(4) PROPOSED USE: [X] Domestic [] Community [] Industrial [] Irrigation [] Thermal [] Injection [] Livestock [] Other

(5) BORE HOLE CONSTRUCTION: Special Construction approval [] Yes [X] No Depth of Completed Well 75 ft. Explosives used [] Yes [X] No Type Amount

Table with columns: HOLE Diameter, From, To, SEAL Material, From, To, Sacks or pounds. Row 1: 10", 0, 18', cement, 0, 18', 12 sacks. Row 2: 6", 18', 75'

How was seal placed: Method [] A [] B [X] C [] D [] E [] Other Backfill placed from ft. to ft. Material Gravel placed from ft. to ft. Size of gravel

(6) CASING/LINER: Table with columns: Diameter, From, To, Gauge, Steel, Plastic, Welded, Threaded. Casing: 6", +20", 71', .250, [X], [], [X], []. Liner: [], [], [], [], [], [], [], [].

Final location of shoe(s) 71'09"

(7) PERFORATIONS/SCREENS: [X] Perforations Method Acetylene torch [] Screens Type Material. Table with columns: From, To, Slot size, Number, Diameter, Tele/pipe size, Casing, Liner. Row 1: 63', 71', 3/8", 44, 6", [], [X], []. Row 2: 09", 09", x12", [], [], [], [].

(8) WELL TESTS: Minimum testing time is 1 hour [] Pump [X] Bailer [] Air [] Flowing Artesian. Yield gal/min 35 gpm Drawdown 5'7" Drill stem at Time 1 hr.

Temperature of water 52 Depth Artesian Flow Found Was a water analysis done? [] Yes By whom Did any strata contain water not suitable for intended use? [] Too little [] Salty [] Muddy [] Odor [] Colored [] Other Depth of strata:

(9) LOCATION OF WELL by legal description: County Linn Latitude Longitude Township 12 S N or S Range 1 W E or W. WM. Section 33B NE 1/4 NW 1/4 Tax Lot 100 Lot Block Subdivision Street Address of Well (or nearest address) Waterloo Park Santiam Addition

(10) STATIC WATER LEVEL: 5'06" ft. below land surface. Date 5-14-94 Artesian pressure lb. per square inch. Date

(11) WATER BEARING ZONES: Depth at which water was first found 30'

Table with columns: From, To, Estimated Flow Rate, SWL. Row 1: 30', 40', 6 gpm, 18'. Row 2: 66', 70', 35 gpm, 5'06".

(12) WELL LOG: Ground Elevation

Table with columns: Material, From, To, SWL. Row 1: Top soil, 0, 5. Row 2: Brown sandy clay & gravel, 5, 16. Row 3: Gray clay & gravel, 16, 30. Row 4: Gray sandy clay & gravel, 30, 40, 10'. Row 5: Gray clay, 40, 44. Row 6: Gray clay & gravel, 44, 53. Row 7: Blue clay & gravel, 53, 62. Row 8: Gray clay & gravel, 62, 66. Row 9: Gray sand & gravel, 66, 70, 5'06". Row 10: Gray clay & gravel, 70, 75.

Date started 5-9-94 Completed 5-14-94

(unbonded) Water Well Constructor Certification: I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

Signed WWC Number Date

(bonded) Water Well Constructor Certification: I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

Signed WWC Number 1378 Date 5-17-94