

WATER WELL REPORT
STATE OF OREGON

RECEIVED

JAN 27 1984

WATER RESOURCES DEPT.
SALEM, OREGON

State Well No. 95/1W-15

State Permit No.

Linn
246

(1) OWNER:

Name Arnold Lee
Address 40653 Forrest Way
City Stayton State OR

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary Air ☐ Driven ☐ Domestic ☒ Industrial ☐ Municipal ☐
Rotary Mud ☐ Dug ☐ Irrigation ☐ Test Well ☐ Other ☐
☒ Bored ☐ Thermal ☐ Withdrawal ☐ Reinjection ☐

(4) PROPOSED USE (check):

(5) CASING INSTALLED:

Steel ☒ Plastic ☐
Threaded ☐ Welded ☒

6" Diam. from 11 ft. to 49 ft. Gauge 2.52
" Diam. from ft. to ft. Gauge

LINER INSTALLED:

" Diam. from ft. to ft. Gauge

(6) PERFORATIONS:

Perforated? ☐ Yes ☒ No

Type of perforator used

Size of perforations in. by in.

perforations from ft. to ft.

perforations from ft. to ft.

perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name

Type Model No.

Diam. Slot Size Set from ft. to ft.

Diam. Slot Size Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is lowered below static level

Is a pump test made? ☐ Yes ☒ No If yes, by whom?

Field: gal./min. with ft. drawdown after hrs.

Air test gal./min. with drill stem at ft. hrs.

Bailer test 18 gal./min. with 12 ft. drawdown after 2 hrs.

Artesian flow g.p.m.

Temperature of water Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Special standards: Yes ☒ No ☐

Well seal—Material used bentonite

Well sealed from land surface to 20 ft.

Diameter of well bore to bottom of seal 10 in.

Diameter of well bore below seal 6 in.

Number of sacks of cement used in well seal 4-5 c16 slurry sacks

How was cement grout placed? 1.5 placed & kept filled during drilling

Was pump installed? no Type HP Depth ft.

Was a drive shoe used? ☒ Yes ☐ No Plugs Size: location ft.

Did any strata contain unusable water? ☐ Yes ☒ No

Type of Water? depth of strata

Method of sealing strata off

Was well gravel packed? ☐ Yes ☒ No Size of gravel:

Gravel placed from ft. to ft.

(10) LOCATION OF WELL:

County Linn Driller's well number
1/4 1/4 Section 15 T. 9S R. 1W W.M.

Tax Lot # Lot Blk Subdivision

Address at well location: 40653 Forrest Way

Stayton Oregon

(11) WATER LEVEL: Completed well.

Depth at which water was first found 45 ft.

Static level 23 ft. below land surface. Date 11/20/83

Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing 0

Depth drilled 49 ft. Depth of completed well 49 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
brown clay silt	0'	4'	
cobble sand clay	4'	15'	
cemented gravels	15'	23'	
light gravels sand	23'	34'	
cobbles sand clay	34'	42'	
cemented gravels	42'	45'	
gravels small brown sand	45'	49'	23

Work started 11-15 19 83 Completed 11-20 19 83

Date well drilling machine moved off of well 11-21 19 83

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] Thomas J. Pear Date 11-21 19 83
(Drilling Machine Operator)

Drilling Machine Operator's License No. 924

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

Name George Robinson Drilling
(Person, firm or corporation) (Type or print)

Address 1050 Crescent Dr NW Salem

[Signed] George Robinson
(Water Well Contractor)

Contractor's License No. 13 Date 12-30 19 83

NOTICE TO WATER WELL CONTRACTOR
The original and first copy of this report
are to be filed with the

WATER RESOURCES DEPARTMENT,
SALEM, OREGON 97310
within 30 days from the date of well completion.

SP*12658-690