

RECEIVED

WATER WELL REPORT

WATER RESOURCES DEPARTMENT
SALEM, OREGON 97310
within 30 days from the date
of well completion

AUG 7 - 1979

STATE OF OREGON
(Please type or print)

WATER RESOURCES DEPARTMENT write above this line)

SALEM, OREGON

State Well No. 95/1w-24ac

State Permit No. G-8689

(1) OWNER:

Name Mr. & Mrs. Marion Bockelman
Address 41343 Manitau Dr., Stayton 97383

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☒ Driven ☐
Cable ☐ Jetted ☐
Dug ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐
Irrigation ☒ Test Well ☐ Other ☐

CASING INSTALLED:

6" Diam. from 0 ft. to 23 ft. Gage 250
" Diam. from ft. to ft. Gage
" Diam. from ft. to ft. Gage

PERFORATIONS:

Perforated? ☐ Yes ☒ No.

Type of perforator used

Size of perforations in. by in.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name
Type Model No.
Diam. Slot size Set from ft. to ft.
Diam. Slot size Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is
lowered below static level

Was a pump test made? ☒ Yes ☐ No If yes, by whom? Stehler

Yield: 60 gal./min. with 0 ft. drawdown after 3 hrs.

Air lift 18 gpm from 200 ft. after 1 hr.

Ball test gal./min. with ft. drawdown after hrs.

Artesian flow g.p.m.

Temperature of water Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Well seal—Material used Cement

Well sealed from land surface to 23 ft.

Diameter of well bore to bottom of seal 8 in.

Diameter of well bore below seal 6 in.

Number of sacks of cement used in well seal 5 sacks

How was cement grout placed? Method B.

Was a drive shoe used? ☐ Yes ☒ No Plugs Size: location ft.

Did any strata contain unusable water? ☐ Yes ☒ No

Type of water? depth of strata

Method of sealing strata off

Was well gravel packed? ☐ Yes ☒ No Size of gravel:

Gravel placed from ft. to ft.

(10) LOCATION OF WELL:

County Linn Driller's well number 1034
SW 1/4 NE 1/4 Section 24 T. 9S R. 1W W.M.

Bearing and distance from section or subdivision corner

(11) WATER LEVEL: Completed well.

Depth at which water was first found 198 ft.

Static level 156 ft. below land surface. Date 7/19/79

Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing 6"

Depth drilled 360 ft. Depth of completed well 360 ft.

Formation: Describe color, texture, grain size and structure of materials;
and show thickness and nature of each stratum and aquifer penetrated,
with at least one entry for each change of formation. Report each change in
position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
Top soil	0'	1'	
Clay (dark)	1'	9'	
Basalt (weathered)	9'	18'	
Basalt (hard black)	18'	34'	
Basalt (grey tuff streaks)	34'	37'	
Basalt (vesicular black)	37'	85'	
Basalt (hard black)	85'	185'	
Basalt (hard grey)	185'	198'	
Basalt (creviced black)	198'	200'	
Basalt (tuff grey blue green)	200'	218'	
Shale (brown)	218'	219'	
Basalt (Igneous creviced)	219'	240'	
Basalt (hard black)	240'	280'	
Basalt (creviced)	280'	300'	
Basalt (hard black)	300'	307'	
Basalt (hard grey black)	307'	329'	
Basalt (hard black)	329'	330'	
Basalt (Igneous) (shaley)	330'	334'	
Basalt (creviced black)	334'	360'	156'

Work started 7/16/79 19 Completed 7/19/79 19

Date well drilling machine moved off of well 7/19/79 19

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision.
Materials used and information reported above are true to my
best knowledge and belief.

[Signed] Pete Tolmasoff Date 7/28, 1979.

(Drilling Machine Operator)

Drilling Machine Operator's License No. 320

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is
true to the best of my knowledge and belief.

Name Pete Tolmasoff Well Drilling

(Person, firm or corporation)

(Type or print)

Address 7332 Mac Robbins Lane, Turner

[Signed] Pete Tolmasoff

(Water Well Contractor)

Contractor's License No. 410 Date 7/28/79, 19