

NOTICE TO WATER WELL CONTRACTOR

The original and first copy of this report are to be filed with the

STATE ENGINEER, SALEM 10, OREGON within 30 days from the date of well completion.

RECEIVED JUL 3 1962 STATE ENGINEER SALEM, OREGON

WATER WELL REPORT

STATE OF OREGON (Please type or print)

G-3910 G-2538

State Well No. 9/2-36C State Permit No.

(1) OWNER:

Name North Santiam Plywood Co. Address P.O. Box 377 Mill City, Ore.

(2) LOCATION OF WELL:

County Linn Driller's well number 9/2-36A Bearing and distance from section or subdivision corner

(3) TYPE OF WORK (check):

Well [X] Deepening [] Reconditioning [] Abandon []

(4) PROPOSED USE (check):

Domestic [] Industrial [X] Municipal [] Irrigation [] Test Well [] Other []

(5) TYPE OF WELL:

Rotary [] Driven [] Cable [X] Jetted [] Dug [] Bored []

(6) CASING INSTALLED:

12 3/4 Diam. from 1+0 ft. to 149 ft. Gage 250

(7) PERFORATIONS:

Perforated? [X] Yes [] No Type of perforator used Mills Size of perforations 38 in. by 2 1/2 in.

(8) SCREENS:

Well screen installed [] Yes [X] No Manufacturer's Name Model No.

(9) CONSTRUCTION:

Well seal—Material used in seal Bentonite Depth of seal 60 ft. Was a packer used? no Diameter of well bore to bottom of seal 13 1/2 in.

(10) WATER LEVELS:

Static level 63 ft. below land surface Date 7/30/62 Artesian pressure lbs. per square inch Date

(11) WELL TESTS:

Drawdown is amount water level is lowered below static level Was a pump test made? [X] Yes [] No Yield: 400 gal./min. with 45 ft. drawdown after 1 1/2 hrs.

(12) WELL LOG:

Diameter of well below casing Depth drilled 149 ft. Depth of completed well 149 ft. Formation: Describe by color, character, size of material and structure, and show thickness of aquifers and the kind and nature of the material in each stratum penetrated, with at least one entry for each change of formation.

Table with columns: MATERIAL, FROM, TO. Rows: Glacial boulders & gravel (0-89), Silt (grey) (89-110), Silt (brown) (110-127), Gravel (127-140), Gravel with clay (140-149)

Work started 6/26 19 62 Completed 7/17/62 19 Date well drilling machine moved off of well 7/17/62 19

(13) PUMP:

Manufacturer's Name Type: H.P.

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

NAME Harry A. Robinson (Person, firm or corporation) (Type or print) Address 2214 Front St NE Salem, Ore. Drilling Machine Operator's License No. 63 [Signed] Harry A. Robinson (Water Well Contractor) Contractor's License No. 22 Date 7/30/62, 19