

WATER WELL REPORT
STATE OF OREGON

RECEIVED

State Well No.

115/1W-25

FEB 7 1984

State Permit No.

WATER RESOURCES DEPT.
SALEM, OREGON

(1) OWNER:

Name Frank Peoples
Address 41475 Lacomp Dr
City Tiburon State Oregon

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rot ☒ Air ☐ Driven ☐ Domestic ☒ Industrial ☐ Municipal ☐
R. Mud ☐ Dug ☐ Irrigation ☐ Test Well ☐ Other ☐
Cable ☒ Bored ☐ Thermal: Withdrawal ☐ ReInjection ☐

(4) PROPOSED USE (check):

(5) CASING INSTALLED: Steel ☒ Plastic ☐
Threaded ☐ Welded ☒
6" Diam. from 1-7 ft. to 90-6" ft. Gauge 250 X
" Diam. from ft. to ft. Gauge

LINER INSTALLED:

" Diam. from ft. to ft. Gauge

(6) PERFORATIONS:

Perforated? ☐ Yes ☒ No

Type of perforator used

Size of perforations in. by in.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name
Type Model No.
Diam. Slot Size Set from ft. to ft.
Diam. Slot Size Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is lowered below static level

a pump test made? ☐ Yes ☒ No If yes, by whom?
Yield: gal./min. with ft. drawdown after hrs.
" " " "
Air test gal./min. with drill stem at ft. hrs.
Packer test 15 gal./min. with 55 ft. drawdown after 1 hrs.
Artesian flow g.p.m.

Temperature of water 54 Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Special standards: Yes ☐ No ☒

Well seal—Material used Cement
Well sealed from land surface to 20 ft.
Diameter of well bore to bottom of seal 10 in.
Diameter of well bore below seal 6 in.
Number of sacks of cement used in well seal 19 sacks
How was cement grout placed? Pump

Was pump installed? Type HP Depth ft.

Was a drive shoe used? ☒ Yes ☐ No Plugs Size: location ft.

Did any strata contain unusable water? ☐ Yes ☒ No

Type of Water? depth of strata

Method of sealing strata off

Was well gravel packed? ☐ Yes ☒ No Size of gravel: ft.

Gravel placed from ft. to ft.

(10) LOCATION OF WELL:

County LINN Driller's well number
1/4 1/4 Section T. R. W.M.
Tax Lot # Lot Blk Subdivision
Address at well location: 25-11-12W

(11) WATER LEVEL: Completed well.

Depth at which water was first found 38 ft.
Static level 35 ft. below land surface. Date 1-15-84
Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing 6

Depth drilled 125 ft. Depth of completed well 125 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
Top soil red	0	4	
clay yellow	4	38	
Sand yellow	38	39	
clay yellow & sand	39	55	
clay yellow	55	60	
clay sand & gravel	60	90	
hard	90	125	
Black Sand Rock			
not to hard			

Work started 11-19 1983 Completed 1-15 1984
Date well drilling machine moved off of well 1-16 1984

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] Robert E. White Date 1-25-84
(Drilling Machine Operator)

Drilling Machine Operator's License No. 210

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

Name BOBS. WELL DRILLING INC
(Person, firm or corporation) (Type or print)

Address 465 Wagon Wheel Dr Tiburon

[Signed] Robert E. White
(Water Well Contractor)

Contractor's License No. 121 Date 1-25 1984

NOTICE TO WATER WELL CONTRACTOR
The original and first copy of this report
are to be filed with the

WATER RESOURCES DEPARTMENT,
SALEM, OREGON 97310
within 30 days from the date of well completion.

SP*12658-690