

RECEIVED

NOTICE TO WATER WELL CONTRACTOR

The original and first copy of this report are to be filed with the

STATE ENGINEER, SALEM 10, OREGON within 30 days from the date of well completion.

WATER WELL REPORT

STATE OF OREGON (Please type or print)

State Well No. 10/3W-33Q

State Permit No.

(1) OWNER:

Name Lois M. Bennett
Address 1197 North Pacific Highway
Albany Oregon

(2) LOCATION OF WELL:

County Linn Driller's well number
SW 1/4 SE 1/4 Section 33 T. 10-S R. 3W W.M.
Bearing and distance from section or subdivision corner

(3) TYPE OF WORK (check):

Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐
abandonment, describe material and procedure in Item 12.

(4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐
Irrigation ☐ Test Well ☐ Other ☐

(5) TYPE OF WELL:

Rotary ☐ Driven ☐
Cable ☒ Jetted ☐
Dug ☐ Bored ☐

(6) CASING INSTALLED:

Threaded ☐ Welded ☒

6" Diam. from 1 ft. to 52 ft. Gage 250
" Diam. from ft. to ft. Gage
" Diam. from ft. to ft. Gage

(7) PERFORATIONS:

Perforated? ☒ Yes ☐ No

Type of perforator used
Size of perforations 3/8 in. by 5-8 ft. to 62 ft.
15 perforations from 5-8 ft. to 62 ft.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.

(8) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name X Model No. X
Diam. X Slot size X Set from ft. to X ft.
Diam. X Slot size X Set from X ft. to X ft.

(9) CONSTRUCTION:

Well seal—Material used in seal Puddled Clay
Depth of seal 17 ft. Was a packer used? No
Diameter of well bore to bottom of seal 9 in.
Were any loose strata cemented off? ☐ Yes ☐ No Depth
Was a drive shoe used? ☐ Yes ☒ No
Was well gravel packed? ☐ Yes ☒ No Size of gravel:
Gravel placed from ft. to ft.
Did any strata contain unusable water? ☐ Yes ☒ No
Type of water? M.H. Depth of strata 57-61
Method of sealing strata off

(10) WATER LEVELS:

Static level 17 ft. below land surface Date 4-1-64
Artesian pressure lbs. per square inch Date

(11) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? ☒ Yes ☐ No If yes, by whom?

Yield: 20 gal./min. with 6 ft. drawdown after 3 hrs.

" " " "

" " " "

Bailer test gal./min. with ft. drawdown after hrs.

Artesian flow g.p.m. Date

Temperature of water 54 Was a chemical analysis made? ☐ Yes ☒ No

(12) WELL LOG:

Diameter of well below casing None

Depth drilled 52 ft. Depth of completed well 52 ft.

Formation: Describe by color, character, size of material and structure, and show thickness of aquifers and the kind and nature of the material in each stratum penetrated, with at least one entry for each change of formation.

MATERIAL	FROM	TO
Surf. Soil - Clay	0	17
Gravel - 11"	17	35
" + Sand + Brown	35	41
1" Clay - "	41	57
" + Sand "	57	62

Work started 3-30 1964 completed 3-31 1964
Date well drilling machine moved off of well 4-1 1964

(13) PUMP:

Manufacturer's Name
Type: H.P.

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

NAME Alie Drilling Co.
(Person, firm or corporation) (Type or print)

Address Albany Oregon

Drilling Machine Operator's License No. 852

[Signed] Bill Hamilton
(Water Well Contractor)

Contractor's License No. 52 Date 4-4 1964