

RECEIVED

LINN 55013

29400 SANTIAM HWY
LEBANON, OREGON 97355
541-367-2560

STATE OF OREGON

WATER SUPPLY WELL REPORT

(as required by ORS 537.765)

WATER RESOURCES DEPT.
SALEM, OREGON

WELL I.D. # L 56541

START CARD # 147966

Instructions for completing this report are on the back of this form.

(1) LAND OWNER

Name Robert Leach
Address 33648 Berry Dr. NE
City Albany State OR Zip 97321

(2) TYPE OF WORK

New Well Deepening Alteration (repair/recondition) Abandonment

(3) DRILL METHOD:

Rotary Air Rotary Mud Cable Auger
 Other

(4) PROPOSED USE:

Domestic Community Industrial Irrigation
 Thermal Injection Livestock Other

(5) BORE HOLE CONSTRUCTION:

Special Construction approval Yes No Depth of Completed Well 150 ft.
Explosives used Yes No Type _____ Amount _____

HOLE			SEAL			Sacks or pounds
Diameter	From	To	Material	From	To	
10	0	20	Hole Plug	0	20	9-50lb
6	20	150				

How was seal placed: Method A B C D E
 Other Poured & probed

Backfill placed from _____ ft. to _____ ft. Material _____
Gravel placed from 20 ft. to 23 ft. Size of gravel 3/4"

(6) CASING/LINER:

Casing/Liner	Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing	6	0	79	250	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Liner					<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

Drive Shoe used Inside Outside None
Final location of shoe(s) 79"

(7) PERFORATIONS/SCREENS:

Perforations Method Air - Holte
 Screens Type _____ Material _____

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
23	28	1/4 x 1/2	108	1 1/4		<input checked="" type="checkbox"/>	<input type="checkbox"/>

(8) WELL TESTS: Minimum testing time is 1 hour

Yield gal/min	Drawdown	Drill stem at	Flowing Time
7		40	1 hr.

Temperature of water 56° Depth Artesian Flow Found _____

Was a water analysis done? Yes By whom _____

Did any strata contain water not suitable for intended use? Too little

Salty Muddy Odor Colored Other _____

Depth of strata: _____

(9) LOCATION OF WELL by legal description:

County Linn Latitude _____ Longitude _____
Township 10 N or S Range 3 E or W. W.M.
Section 21 SE 1/4 SE 1/4
Tax Lot 4900 Lot _____ Block _____ Subdivision _____
Street Address of Well (or nearest address) 33648 Berry Dr. NE - Albany, OR 97321

(10) STATIC WATER LEVEL:

16 ft. below land surface. Date 7-31-02
Artesian pressure _____ lb. per square inch Date _____

(11) WATER BEARING ZONES:

Depth at which water was first found 23

From	To	Estimated Flow Rate	SWL
23	28	7 gpm	16

(12) WELL LOG:

Ground Elevation _____

Material	From	To	SWL
Topsoil	0	2	
Clay Brown firm	2	18	
Clay green sticky firm	18	23	
Gravel small multi color w/ clay brown silty	23	—	
Clay grey sandy & sticky	28	40	16
Clay grey & blue firm	40	60	
Clay dark grey firm & sticky	60	67	
Siltstone dark grey firm	67	150	

JONES DRILLING CO., INC.
29400 SANTIAM HWY
LEBANON, OREGON 97355
541-367-2560

Date started 7-31-02 Completed 7-31-02

(unbonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

Signed Douglas Reynolds WWC Number 1725
Date 7-7-02

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

Signed [Signature] WWC Number 16841
Date 8-06-02