

STATE OF OREGON
WATER SUPPLY WELL REPORT
(as required by ORS 537.765)

Instructions for completing this report are on the last page of this form.

(WELL I.D.# L 62589

(START CARD) # 161506

(1) OWNER:

Well Number 3881

Name Matthew Powell

Address 41210 Upper Calapooia Dr.

City Sweet Home State Oregon Zip 97386

(2) TYPE OF WORK

☒ New Well ☐ Deepening ☐ Alteration (repair/recondition) ☐ Abandonment

(3) DRILL METHOD:

☒ Rotary Air ☐ Rotary Mud ☐ Cable ☐ Auger
☐ Other

(4) PROPOSED USE:

☒ Domestic ☐ Community ☐ Industrial ☐ Irrigation
☐ Thermal ☐ Injection ☐ Livestock ☐ Other

(5) BORE HOLE CONSTRUCTION:

Special Construction approval ☐ Yes ☒ No Depth of Completed Well 93 ft.

Explosives used ☐ Yes ☒ No Type Amount

HOLE

SEAL

Diameter	From	To	Material	From	To	Sacks or pounds
10	0	19	Bentonite	0	19	9 sacks
6	19	93				

How was seal placed: Method ☐ A ☐ B ☐ C ☐ D ☐ E

☒ Other Poured dry

Backfill placed from ft. to ft. Material

Gravel placed from ft. to ft. Size of gravel

(6) CASING/LINER:

Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing: 6"	+1	19	250	☒	☐	☐	☐
Liner: 4-1/2"	0	93	160	☐	☒	☐	☐

Final location of shoe(s)

(7) PERFORATIONS/SCREENS:

☒ Perforations Method Drilled

☐ Screens

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
33	93		1000	1/4"		☐	☒

(8) WELL TESTS: Minimum testing time is 1 hour

Yield gal/min	Drawdown	Drill stem at	Time
60		93	1 hr.

Temperature of water 52 Depth Artesian Flow Found

Was a water analysis done? ☐ Yes By whom

Did any strata contain water not suitable for intended use? ☐ Too little

☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other

Depth of strata:

(9) LOCATION OF WELL by legal description:

County Linn Latitude Longitude
Township 14 S Range 1 W WM.
Section 25 NW 1/4 NE 1/4
Tax Lot 500 Lot Block Subdivision
Street Address of Well (or nearest address) 41210 Upper Calapooia Dr.
Sweet Home, OR 97386

(10) STATIC WATER LEVEL:

13 ft. below land surface. Date 10/23/2003
Artesian pressure lb. per square inch. Date

(11) WATER BEARING ZONES:

Depth at which water was first found 60'

From	To	Estimated Flow Rate	SWL
60	80	60 gpm	13

(12) WELL LOG:

Ground Elevation

Material	From	To	SWL
Gravel fill	0	1	
Brown clay	1	10	
Broken brown sandstone	10	12	
Blue grey sandstone	12	93	

RECEIVED

OCT 31 2003

WATER RESOURCES DEPT.
SALEM, OREGON

JONES DRILLING CO., INC.

29400 SANTIAM HWY.

LEBANON, OR 97355

541-367-2560 541-451-2686

1-800-915-8388

Date started 10/22/2003 Completed 10/22/2003

(unbonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

Signed *K. D. M.* WWC Number 1411 Date 10/24/2003

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

Signed *B. J. M.* WWC Number 1684 Date 10/24/2003

ORIGINAL & FIRST COPY-WATER RESOURCES DEPARTMENT SECOND COPY-CONSTRUCTOR THIRD COPY-CUSTOMER