

STATE OF OREGON
WATER SUPPLY WELL REPORT
(as required by ORS 537.765)

Instructions for completing this report are on the last page of this form.

(WELL I.D.)# L 87028

(START CARD) # 191135

(1) OWNER:

Well Number 4793

Name Roy Holcomb

Address P.O. Box 680

City Foster

State OR

Zip 97345

(2) TYPE OF WORK

☒ New Well ☐ Deepening ☐ Alteration (repair/recondition) ☐ Abandonment

(3) DRILL METHOD:

☒ Rotary Air ☐ Rotary Mud ☐ Cable ☐ Auger
☐ Other

(4) PROPOSED USE:

☒ Domestic ☐ Community ☐ Industrial ☐ Irrigation
☐ Thermal ☐ Injection ☐ Livestock ☐ Other

(5) BORE HOLE CONSTRUCTION:

Special Construction approval ☐ Yes ☒ No Depth of Completed Well 445 ft.
Explosives used ☐ Yes ☒ No Type Amount

HOLE			SEAL				
Diameter	From	To	Material	From	To	Sacks or pounds	
10	0	39	Bentonite	0	39	16 sacks	
6	39	445					

How was seal placed: Method ☐ A ☐ B ☐ C ☐ D ☐ E

☒ Other poured dry

Backfill placed from ft. to ft. Material

Gravel placed from ft. to ft. Size of gravel

(6) CASING/LINER:

Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing: 6"	+1	39	250	☒	☐	☒	☐
Liner:				☐	☐	☐	☐

Final location of shoe(s) 39'

(7) PERFORATIONS/SCREENS:

		Method		Material	
		Type		Tele/pipe size	Casing
From	To	Slot size	Number	Diameter	Liner
NONE					

(8) WELL TESTS: Minimum testing time is 1 hour

	Pump	Bailer	Air	Flowing
Yield gal/min	Drawdown	Drill stem at	Time	
4		445	1 hr.	

Temperature of water 55 Depth Artesian Flow Found

Was a water analysis done? ☐ Yes By whom

Did any strata contain water not suitable for intended use? ☐ Too little

☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other

Depth of strata:

(9) LOCATION OF WELL by legal description:

County Linn Latitude Longitude
Township 13 S Range 1 E WM.
Section 26 NE 1/4 SE 1/4
Tax Lot 804 Lot Block Subdivision
Street Address of Well (or nearest address) 28043 Riggs Hill Rd.
Foster, OR 97345

(10) STATIC WATER LEVEL:

75 ft. below land surface. Date 2/20/07
Artesian pressure lb. per square inch. Date

(11) WATER BEARING ZONES:

Depth at which water was first found 150

From	To	Estimated Flow Rate	SWL
150	151	2-1/2	75
340	341	1-1/2	75

(12) WELL LOG:

Ground Elevation

Material	From	To	SWL
Gravel Fill	0	1	
Brown Clay	1	3	
Broken Black Basalt	3	24	
Black Basalt	24	73	
Blue Grey Sand Stone	73	170	75
Dark Grey Sand Stone	170	225	
Turquoise Sand Stone	225	345	75
Blue Grey Sand Stone	345	445	

JONES DRILLING CO., INC.

29400 SANTIAM HWY.

LEBANON, OR 97355

541-367-2560 541-451-2686

1-800-915-8388

RECEIVED

FEB 22 2007

WATER RESOURCES DEPT
SALEM, OREGON

Date started 2/19/07

Completed 2/20/07

(unbonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

Signed

WWC Number 1411

Date 2/22/07

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

Signed

WWC Number 1684

Date 2/22/07