

STATE OF OREGON
WATER SUPPLY WELL REPORT
(as required by ORS 537.765)

(WELL I.D.)# L 89008
(START CARD) # 192209

Instructions for completing this report are on the last page of this form.

(1) OWNER:

Well Number 4841

Name **Khao Chiam Saetern**Address **33427 Seven Mile Ln. SE**City **Albany**State **Oregon**Zip **97322**

(2) TYPE OF WORK

☒ New Well ☐ Deepening ☐ Alteration (repair/recondition) ☐ Abandonment

(3) DRILL METHOD:

☒ Rotary Air ☐ Rotary Mud ☐ Cable ☐ Auger

☐ Other

(4) PROPOSED USE:

☒ Domestic ☐ Community ☐ Industrial ☐ Irrigation

☐ Thermal ☐ Injection ☐ Livestock ☐ Other

(5) BORE HOLE CONSTRUCTION:

Special Construction approval ☐ Yes ☒ No Depth of Completed Well **120** ft.Explosives used ☐ Yes ☒ No Type _____ Amount _____

HOLE			SEAL			Sacks or pounds
Diameter	From	To	Material	From	To	
10	0	20	Bentonite	0	20	13 sacks
6	20	128				

How was seal placed: Method ☐ A ☐ B ☐ C ☐ D ☐ E
☒ Other **Poured dry**

Backfill placed from _____ ft. to _____ ft. Material _____

Gravel placed from _____ ft. to _____ ft. Size of gravel _____

(6) CASING/LINER:

	Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing:	6	+1	119	250	☒	☐	☒	☐
					☐	☐	☐	☐
					☐	☐	☐	☐
					☐	☐	☐	☐
Liner:					☐	☐	☐	☐
					☐	☐	☐	☐

Final location of shoe(s) _____

(7) PERFORATIONS/SCREENS:

☐ Perforations

Method _____

☐ Screens

Type _____

Material _____

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
						☐	☐
						☐	☐
						☐	☐
						☐	☐
						☐	☐

(8) WELL TESTS: Minimum testing time is 1 hour

☐ Pump

☐ Bailer

☒ Air

☐ Flowing

☐ Artesian

Yield gal/min **75** Drawdown **All** Drill stem at **115** Time **1 hr.**

Temperature of water **56** Depth Artesian Flow Found _____Was a water analysis done? ☐ Yes By whom _____Did any strata contain water not suitable for intended use? ☐ Too little
☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other _____

Depth of strata: _____

(9) LOCATION OF WELL by legal description:

County **Linn** Latitude _____ Longitude _____
Township **12** S Range **3** W W.M.
Section **3** NW 1/4 SW 1/4
Tax Lot **400** Lot _____ Block _____ Subdivision _____
Street Address of Well (or nearest address) **33427 Seven Mile Ln. SE**
Albany, OR 97322

(10) STATIC WATER LEVEL:

7 ft. below land surface. Date **6/27/2007**

Artesian pressure _____ lb. per square inch. Date _____

(11) WATER BEARING ZONES:

Depth at which water was first found **30**

From	To	Estimated Flow Rate	SWL
30	105	10	7
105	125	75	7

(12) WELL LOG:

Ground Elevation _____

Material	From	To	SWL
Clay brown	0	16	
Clay w/gravel	16	30	
Cemented sand	30	70	
Cemented sand & gravel	70	105	
Loose gravel	105	128	

Hole caved back to 120'

JONES DRILLING CO., INC.**29400 SANTIAM HWY.****LEBANON, OR 97355****541-367-2560 541-451-2686****1-800-915-8388****RECEIVED****JUL 03 2007**

WATER RESOURCES DEPT.
SALEM, OREGON

Date started **6/26/2007**Completed **6/27/2007**

(unbonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.


WWC Number _____

Signed _____

Date _____

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

WWC Number **1684**Signed Date **6/29/2007**