

STATE OF OREGON  
 WATER SUPPLY WELL REPORT  
 (as required by ORS 537.765 & OAR 690-205-0210)

WELL LABEL # L 112546

START CARD # 1023717

(1) LAND OWNER Owner Well I.D. 5428

First Name Ron Last Name Hess  
 Company \_\_\_\_\_  
 Address 650 Castro Street, #120-292  
 City Mountain View State CA Zip 94041

(2) TYPE OF WORK  New Well  Deepening  Conversion  
 Alteration (repair/recondition)  Abandonment

(3) DRILL METHOD  
 Rotary Air  Rotary Mud  Cable  Auger  Cable Mud  
 Reverse Rotary  Other \_\_\_\_\_

(4) PROPOSED USE  Domestic  Irrigation  Community  
 Industrial/ Commercial  Livestock  Dewatering  
 Thermal  Injection  Other \_\_\_\_\_

(5) BORE HOLE CONSTRUCTION Special Standard  (Attach copy)  
 Depth of Completed Well 180 ft.

BORE HOLE			SEAL				sacks/ lbs	
Dia	From	To	Material	From	To	Amt		
10	0	19	Bentonite	0	19	13	S	
6	19	180						

How was seal placed: Method  A  B  C  D  E

Other Poured dry

Backfill placed from \_\_\_\_\_ ft. to \_\_\_\_\_ ft. Material \_\_\_\_\_

Filter pack from \_\_\_\_\_ ft. to \_\_\_\_\_ ft. Material \_\_\_\_\_ Size \_\_\_\_\_

Explosives used:  Yes Type \_\_\_\_\_ Amount \_\_\_\_\_

(6) CASING/LINER

Casing Liner	Dia	+	From	To	Gauge	Stl	Plstc	Wld	Thrd
<input checked="" type="checkbox"/>	6	<input checked="" type="checkbox"/>	1	179	250	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>

Shoe  Inside  Outside  Other Location of shoe(s) \_\_\_\_\_

Temp casing  Yes Dia 10 From 0 To 19

(7) PERFORATIONS/SCREENS

Perforations Method Holte air perforator

Screens Type \_\_\_\_\_ Material \_\_\_\_\_

Perf	Casing	Screen Dia	From	To	Scr/slot width	Slot length	# of slots	Tele/ pipe size
		6	80	<del>180</del> 178	.375	.5	500	

(8) WELL TESTS: Minimum testing time is 1 hour

Pump  Bailer  Air  Flowing Artesian

Yield gal/min	Drawdown	Drill stem/Pump depth	Duration (hr)
20		179	1

Temperature 53 °F Lab analysis  Yes By \_\_\_\_\_

Water quality contents:  Yes (Describe All)  No

From	To	Description	Amount	Units

(9) LOCATION OF WELL (legal description)

County LINN Twp 14 S N/S Range 1 W E/W WM  
 Sec 18 SE 1/4 of the NE 1/4 Tax Lot 1801  
 Tax Map Number \_\_\_\_\_ Lot \_\_\_\_\_  
 Lat \_\_\_\_\_ " or \_\_\_\_\_ DMS or DD  
 Long \_\_\_\_\_ " or \_\_\_\_\_ DMS or DD  
 Street address of well  Nearest address

38530 Hwy. 228, Sweet Home, OR 97386

(10) STATIC WATER LEVEL

Existing Well / Predeepening	Date	SWL(psi)	+ SWL(ft)
Completed Well	07-23-2014		27

Flowing Artesian?  Dry Hole?

WATER BEARING ZONES

Depth water was first found 80

SWL Date	From	To	Est Flow	SWL(psi)	+ SWL(ft)
07-18-2014	80	100	5		27
07-18-2014	100	125	15		27

(11) WELL LOG

Ground Elevation \_\_\_\_\_

Material	From	To
Topsoil	0	2
Brown clay	2	8
Small sand and gravel	8	15
Cemented sand & gravel	15	45
Gray clay with sand and gravel	45	80
Cemented sand & gravel	80	119
Broken black basalt with gravel	119	125
Broken black basalt w/brown claystone	125	165
Weathered basalt	165	170
Gray sandstone w/brown claystone	170	178
Gray basalt	178	180

**JONES DRILLING CO., INC.**  
**29400 SANTIAM HWY.**  
**LEBANON, OR 97355**  
**541-367-2560 541-451-2686**  
**1-800-915-8388**

Date Started 07-17-2014 Completed 07-18-2014

(unbonded) Water Well Constructor Certification

I certify that the work I performed on the construction, deepening, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

License Number 1888 Date 07-24-2014

Password: (if filing electronically) \_\_\_\_\_  
 Signed [Signature]

(bonded) Water Well Constructor Certification

I accept responsibility for the construction, deepening, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

License Number 1684 Date 07-24-2014

Password: (if filing electronically) \_\_\_\_\_  
 Signed [Signature]  
 Contact Info (optional) jonesdrilling@hotmail.com