

STATE OF OREGON
WATER SUPPLY WELL REPORT
(as required by ORS 537.765 & OAR 690-205-0210)

WELL I.D. LABEL# L 134780
START CARD # 1045572
ORIGINAL LOG #

(1) LAND OWNER Owner Well I.D. 6074
First Name Jimmy Last Name Lee
Company Third Knight Farms
Address 34309 Hwy. 34 SE
City Albany State OR Zip 97322

(2) TYPE OF WORK [X] New Well [] Deepening [] Conversion
[] Alteration (complete 2a & 10) [] Abandonment (complete 5a)

(2a) PRE-ALTERATION
Dia + From To Gauge Stl Plstc Wld Thrd
Casing: [] [] [] [] [] [] [] []
Material From To Amt sacks/lbs
Seal: [] [] [] [] [] [] [] []

(3) DRILL METHOD
[X] Rotary Air [] Rotary Mud [] Cable [] Auger [] Cable Mud
[] Reverse Rotary [] Other

(4) PROPOSED USE [] Domestic [X] Irrigation [] Community
[] Industrial/ Commercial [] Livestock [] Dewatering
[] Thermal [] Injection [] Other

(5) BORE HOLE CONSTRUCTION Special Standard [] (Attach copy)
Depth of Completed Well 240 ft.
BORE HOLE SEAL sacks/lbs
Dia From To Material From To Amt lbs
16 0 44 Cement 0 44 34 S
12 44 240 Calculated 22.3
Calculated

How was seal placed: Method [] A [] B [X] C [] D [] E
[] Other
Backfill placed from ft. to ft. Material
Filter pack from ft. to ft. Material Size
Explosives used: [] Yes Type Amount

(5a) ABANDONMENT USING UNHYDRATED BENTONITE
Proposed Amount Pounds Actual Amount Pounds

(6) CASING/LINER
Casing Liner Dia + From To Gauge Stl Plstc Wld Thrd
[] [] [] [] [] [] [] [] [] []
[] [] [] [] [] [] [] [] [] []
[] [] [] [] [] [] [] [] [] []
[] [] [] [] [] [] [] [] [] []
[] [] [] [] [] [] [] [] [] []
Shoe [] Inside [X] Outside [] Other Location of shoe(s) 137
Temp casing [X] Yes Dia 16 From 0 To 44

(7) PERFORATIONS/SCREENS
Perforations Method
Screens Type Material
Perf/S Casing/ Screen Scrn/slot Slot # of Tele/
reen Liner Dia From To width length slots pipe size

(8) WELL TESTS: Minimum testing time is 1 hour
[] Pump [] Bailer [X] Air [] Flowing Artesian
Yield gal/min Drawdown Drill stem/Pump depth Duration (hr)
800 240 1
Temperature 61 °F Lab analysis [] Yes By
Water quality concerns? [] Yes (describe below) TDS amount 176
From To Description Amount Units

(9) LOCATION OF WELL (legal description)
County LINN Twp 12 S N/S Range 3 W E/W WM
Sec 1 SE 1/4 of the SE 1/4 Tax Lot 1401
Tax Map Number Lot
Lat " or DMS or DD
Long " or DMS or DD
[] Street address of well [] Nearest address
33242 Red Bridge Rd. SE - Albany, OR 97322

(10) STATIC WATER LEVEL
Date SWL(psi) + SWL(ft)
Existing Well / Pre-Alteration
Completed Well 12-03-2019 11
Flowing Artesian? [] Dry Hole? []
WATER BEARING ZONES Depth water was first found 118
SWL Date From To Est Flow SWL(psi) + SWL(ft)
12-03-2019 118 240 1,000 11

(11) WELL LOG
Ground Elevation
Material From To
Gravel fill 0 1.5
Brown clay 1.5 10
Brown cemented gravel RECEIVED 10 78
Black cemented gravel 78 104
Blue clay 104 108
Black cemented gravel DEC 16 2019 108 118
Black gravel & sand 118 190
Blue clay OWRD 190 194
Black sand w/some gravel 194 210
Blue clay 210 213
Black sand w/some gravel 213 240
Do not set pump below 137'. Well not cased
may be unstable
Jones Drilling Co., Inc.
29400 Santiam Hwy.
Lebanon, OR 97355
1-800-915-8388
Date Started 11-18-2019 Completed 12-03-2019

(unbonded) Water Well Constructor Certification
I certify that the work I performed on the construction, deepening, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.
License Number 1888 1411 Date 12-11-2019
Signed [Signature]

(bonded) Water Well Constructor Certification
I accept responsibility for the construction, deepening, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.
License Number 1684 Date 12-11-2019
Signed [Signature]
Contact Info (optional) jonesdrilling@hotmail.com