

STATE OF OREGON
WATER SUPPLY WELL REPORT
(as required by ORS 537.765 & OAR 690-205-0210)

LINN 63135

6/29/2020

WELL I.D. LABEL# L 134336
START CARD # 1047834
ORIGINAL LOG #

(1) LAND OWNER
Owner Well I.D. DR-3467
First Name Last Name
Company PEORIA GARDENS INC.
Address 32355 PEORIA RD.
City ALBANY State OR Zip 97321

(2) TYPE OF WORK
New Well Deepening Conversion
Alteration (complete 2a & 10) Abandonment (complete 5a)

(2a) PRE-ALTERATION
Dia + From To Gauge Stl Plstc Wld Thrd
Casing: Material From To Amt sacks/lbs
Seal: Material From To Amt sacks/lbs

(3) DRILL METHOD
Rotary Air Rotary Mud Cable Auger Cable Mud
Reverse Rotary Other

(4) PROPOSED USE
Domestic Irrigation Community
Industrial/ Commercial Livestock Dewatering
Thermal Injection Other

(5) BORE HOLE CONSTRUCTION
Special Standard (Attach copy)
Depth of Completed Well 88.00 ft.

Table with columns: Dia, From, To, Material, From, To, Amt, lbs. Includes rows for Bentonite and Calculated values.

How was seal placed: Method A B C D E
Other POURED DRY

Backfill placed from ft. to ft. Material

Filter pack from ft. to ft. Material Size

Explosives used: Yes Type Amount

(5a) ABANDONMENT USING UNHYDRATED BENTONITE
Proposed Amount Actual Amount

(6) CASING/LINER
Casing Liner Dia + From To Gauge Stl Plstc Wld Thrd
Shoe Inside Outside Other Location of shoe(s) 87
Temp casing Yes Dia From + To

(7) PERFORATIONS/SCREENS
Perforations Method Holte Air Perforator

Table with columns: Perf/ Screen Liner, Dia, From, To, Scrn/slot width, Slot length, # of slots, Tele/ pipe size. Includes data for a screen with 1 slot and 456 slots.

(8) WELL TESTS: Minimum testing time is 1 hour

Pump Bailer Air Flowing Artesian
Yield gal/min Drawdown Drill stem/Pump depth Duration (hr)
130 82 2

Temperature 53 °F Lab analysis Yes By
Water quality concerns? Yes (describe below) TDS amount 110 ppm
From To Description Amount Units

(9) LOCATION OF WELL (legal description)
County LINN Twp 12.00 S N/S Range 4.00 W E/W WM
Sec 17 SE 1/4 of the SW 1/4 Tax Lot 500
Tax Map Number Lot
Lat " or 44.52031017 DMS or DD
Long " or -123.20615852 DMS or DD
Street address of well Nearest address

32355 PEORIA RD.
ALBANY OR. 97321

(10) STATIC WATER LEVEL
Date SWL(psi) + SWL(ft)
Existing Well / Pre-Alteration
Completed Well 6/25/2020 16
Flowing Artesian? Dry Hole?

Table for WATER BEARING ZONES with columns: SWL Date, From, To, Est Flow, SWL(psi), + SWL(ft). Includes data for 6/25/2020 with values 21, 81, 130, 16.

(11) WELL LOG
Ground Elevation
Material From To
Topsoil 0 1
Clay Gray Sticky 1 6
Clay Gray/Brown Sticky 6 10
Clay Brown 10 19
Gravels w/ Clay Brown 19 21
Gravels w/ Sand Brown 21 32
Sand Brown w/ Gravels 32 46
Gravels Brown w/ Sand 46 64
Gravels Brown w/ Wood 64 66
Sand Brown Course 66 73
Sand Course with Gravels Blue/Brown 73 81
Clay Gray w/ Gravels 81 83
Clay Gray Sticky 83 88

Date Started 6/23/2020 Completed 6/25/2020

(unbonded) Water Well Constructor Certification
I certify that the work I performed on the construction, deepening, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

License Number 1974 Date 6/26/2020
Signed CJ NUGENT (E-filed)

(bonded) Water Well Constructor Certification
I accept responsibility for the construction, deepening, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

License Number 664 Date 6/29/2020
Signed CHARLES NUGENT (E-filed)
Contact Info (optional) Nugent Drilling Co. Lebanon Oregon