

STATE OF OREGON

WATER SUPPLY WELL REPORT

(as required by ORS 537.765 & OAR 690-205-0210)

START CARD # 1054718

ORIGINAL LOG #

(1) LAND OWNER

Owner Well I.D. 6310

First Name Lucas & Elena

Last Name Fortier

Company

Address 33140 Hwy. 34

City Albany

State OR

Zip 97322

(2) TYPE OF WORK

☒ New Well ☐ Deepening ☐ Conversion☐ Alteration (complete 2a & 10) ☐ Abandonment (complete 5a)

(2a) PRE-ALTERATION

Casing: Dia + From To Gauge Std Plstc Wld Thrd

Material From To Amt sacks/lbs

Seal: Dia + From To Gauge Std Plstc Wld Thrd

(3) DRILL METHOD

☒ Rotary Air ☐ Rotary Mud ☐ Cable ☐ Auger ☐ Cable Mud☐ Reverse Rotary ☐ Other

(4) PROPOSED USE

☒ Domestic ☐ Irrigation ☐ Community☐ Industrial/ Commercial ☐ Livestock ☐ Dewatering☐ Thermal ☐ Injection ☐ Other

(5) BORE HOLE CONSTRUCTION

Special Standard ☐ (Attach copy)

Depth of Completed Well 285 ft.

BORE HOLE

Dia	From	To	Material	SEAL	From	To	Amt	sacks/lbs
10	0	80	Bentonite	0	80	40	S	
8	80	99		Calculated		20		
6	99	285	Cement	80	99	3	S	
				Calculated		2		

How was seal placed:

Method ☐ A ☒ B ☐ C ☐ D ☐ E☒ Other Poured dry

Backfill placed from _____ ft. to _____ ft. Material _____

Filter pack from _____ ft. to _____ ft. Material _____ Size _____

Explosives used: ☐ Yes Type _____ Amount _____

(5a) ABANDONMENT USING UNHYDRATED BENTONITE

Proposed Amount Pounds Actual Amount Pounds

(6) CASING/LINER

Casing Liner	Dia	From	To	Gauge	Std	Plstc	Wld	Thrd
☒	6	1	99	250	☒	☐	☒	
☐	4.5	0	285	sch40	☐	☐	☐	

Shoe ☐ Inside ☐ Outside ☐ Other Location of shoe(s) _____Temp casing ☐ Yes Dia _____ From _____ To _____

(7) PERFORATIONS/SCREENS

Perforations Method _____

Screens Type _____

Material _____

Perf/S	Casing/Screen	Dia	From	To	Scr/slot	Slot	# of	Tele/
creen	Liner				width	length	slots	pipe size
Perf	Liner	4.5	205	285	.25	.25	800	

(8) WELL TESTS: Minimum testing time is 1 hour

☐ Pump ☐ Bailer ☒ Air ☐ Flowing Artesian

Yield gal/min Drawdown Drill stem/Pump depth Duration (hr)

100 280

Temperature 64 °F Lab analysis ☐ Yes By _____Water quality concerns? ☐ Yes (describe below) TDS amount 381

From To Description Amount Units

(9) LOCATION OF WELL (legal description)

County LINN Twp 12 S N/S Range 2 W E/W WM

Sec 17 SE 1/4 of the SW 1/4 Tax Lot 200

Tax Map Number Lot

Lat _____ or _____ DMS or DD

Long _____ or _____ DMS or DD

☒ Street address of well ☐ Nearest address

25930 Polly Farm Ln, Lebanon, OR 97355 35930 Polly Farm Ln, Lebanon,

(10) STATIC WATER LEVEL

Date SWL(psi) + SWL(ft)

Existing Well / Pre-Alteration

Completed Well 12-21-2021 68

Flowing Artesian? ☐ Dry Hole? ☐

WATER BEARING ZONES

Depth water was first found 40

SWL Date From To Est Flow SWL(psi) + SWL(ft)

12-17-2021 40 60 5 35

12-20-2021 110 115 1.5 68

12-20-2021 275 285 98.5 68

(11) WELL LOG

Ground Elevation _____

Material	From	To
Topsoil	0	1
Brown clay	1	10
Decomposed rock	10	15
Brown clay w/ some boulders	15	30
Decomposed sandstone w/some boulders	30	37
Grey sandstone	37	40
Blue grey sandstone	40	45
Blue grey sandstone w/wood	45	55
Broken blue sandstone w/wood	55	80
Grey sandstone	80	285

JONES DRILLING CO., INC.

29400 SANTIAM HWY.

LEBANON, OR 97355

541-367-2560 541-451-2686

1-800-915-8388

RECEIVED

JAN 10 2022

OWRD

Date Started 12-17-2021

Completed 12-21-2021

(unbonded) Water Well Constructor Certification

I certify that the work I performed on the construction, deepening, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

License Number 2050

Date 01-06-2022

Signed _____

(bonded) Water Well Constructor Certification

I accept responsibility for the construction, deepening, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

License Number 1684

Date 01-06-2022

Signed _____

Contact Info (optional) jonesdrilling@hotmail.com