

Amended 7/25/2024

LINN 64381

STATE OF OREGON
WATER SUPPLY WELL REPORT

RECEIVED

WELL I.D. LABEL# L 152777

START CARD # 1072148

ORIGINAL LOG #

(as required by ORS 537.545 & 537.765 and OAR 690-205-0210)

DEC 13 2023

(1) LAND OWNER

Owner Well I.D. 6551

First Name Brady

Last Name Moss

Company

Address P.O. Box 287

City Corvallis

State OR

Zip 97339

(2) TYPE OF WORK

☒ New Well ☐ Deepening ☐ Conversion☐ Alteration (complete 2a & 10) ☐ Abandonment (complete 5a)

(2a) PRE-ALTERATION

Casing: Dia + From To Gauge Stil Plstc Wld Thrd

Material From To Amt sacks/lbs

Seal:

(3) DRILL METHOD

☒ Rotary Air ☐ Rotary Mud ☐ Cable ☐ Auger ☐ Cable Mud☐ Reverse Rotary ☐ Other

(4) PROPOSED USE

☒ Domestic ☐ Irrigation ☐ Community☐ Industrial/ Commercial ☐ Livestock ☐ Dewatering☐ Thermal ☐ Injection ☐ Other

(5) BORE HOLE CONSTRUCTION

Special Standard ☐ (Attach copy)

Depth of Completed Well 60 ft.

BORE HOLE

SEAL

sacks/lbs

Dia	From	To	Material	From	To	Amt	S
10	0	19	Bentonite	0	19	10	S
6	19	65				Calculated	10
						Calculated	

How was seal placed:

Method

☐ A☐ B☐ C☐ D☐ E☒ Other Poured dry

Backfill placed from ft. to ft. Material

Filter pack from ft. to ft. Material Size

Seal Placement Begin Date 11/22/2023 Begin Time 13:00

(5a) ABANDONMENT USING UNHYDRATED BENTONITE

Proposed Amount Pounds Actual Amount Pounds

(6) CASING/LINER

Casing	Liner	Dia	From	To	Gauge	Stil	Plstc	Wld	Thrd
☒	☒	6	1	59	.250	☒	☒	☒	☒
☐	☐					☐	☐	☐	☐
☐	☐					☐	☐	☐	☐
☐	☐					☐	☐	☐	☐
☐	☐					☐	☐	☐	☐

Shoe ☐ Inside ☐ Outside ☐ Other Location of shoe(s)Temp casing ☒ Yes Dia 10 From + ☒ 1 To 19

(7) PERFORATIONS/SCREENS

Perforations Method

Screens Type

Material

Perf/S	Casing/Screen	Dia	From	To	Scr/slot width	Slot length	# of slots	Tele/pipe size

(8) WELL TESTS: Minimum testing time is 1 hour

☐ Pump ☐ Bailer ☒ Air ☐ Flowing Artesian

Yield gal/min Drawdown Drill stem/Pump depth Duration (hr)

40		55	1

Temperature 59 °F Lab analysis ☐ Yes ByWater quality concerns? ☐ Yes (describe below) TDS amount 414 ppm

From	To	Description	Amount	Units

(9) LOCATION OF WELL (legal description)

County Linn Twp 12 S N/S Range 4 W E/W WM

Sec 16' NW 1/4 of the SE 1/4 Tax Lot 403

Tax Map Number Lot

Lat " or 44.5259961 DMS or DD

Long " or -123.1767707 DMS or DD

☒ Street address of well ☐ Nearest address

30242 Harvest Dr. - Albany, OR 97321

(10) STATIC WATER LEVEL

Existing Well / Pre-Alteration	Date	SWL (psi)	+ SWL (ft)
Completed Well	11-22-2023		15

Flowing Artesian? ☐ Dry Hole? ☐

WATER BEARING ZONES

Depth water was first found 50

SWL Date From To Est Flow SWL (psi) + SWL (ft)

11-22-2023	50	65	40		15

(11) WELL LOG

Ground Elevation

Material	From	To
Topsoil	0	1
Brown clay	1	17
Grey clay	17	31
Sand & gravel	31	35
Blue clay	35	50
Blue grey sand w/small gravel	50	65
Naturally caved back to 60'		
water rights permit # 618217		
JONES DRILLING CO., INC.		
29400 SANTIAM HWY.		
LEBANON, OR 97355		
541-367-2560 541-451-2686		
1-800-915-8388		

Construction

Begin Date 11-22-2023 Begin Time 09:00 End Date 11-22-2023

(unbonded) Water Well Constructor Certification

I certify that the work I performed on the construction, deepening, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

License Number 2050 Date 12-07-2023

Signed

(bonded) Water Well Constructor Certification

I accept responsibility for the construction, deepening, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

License Number 1684 Date 12-07-2023

Signed

Contact Info (optional) jonesdrilling@hotmail.com

ORIGINAL - WATER RESOURCES DEPARTMENT

THIS REPORT MUST BE SUBMITTED TO THE WATER RESOURCES DEPARTMENT WITHIN 30 DAYS OF COMPLETION OF WORK Form Version: 0.95
New exempt use wells must be submitted with a map and recording fee.

Oregon Water Resources Department
Groundwater Use Recording Mapping Tool

725 Summer St NE, Sale

Step 1: Search for Well

Step 2: Create Well Map

Mark Well Point and
Create Map:

Zoom in closer to the well location, if needed.
Mark the location of the well by either of these two methods:

A. Drawing on the map
using the draw tool

Click on Icon and draw a point on the map

B. Type in the GPS Decimal
Degrees:

GPS Latitude: 44.5259961

GPS Longitude: -123.1767707

Mark Point Clear Point

[Converter](#)

Results:

Latitude: 44.5259961
Longitude: -123.1767707

Complete the form:

Submitted by:

Address of Well:

City:

Special Notes:

Make Map



RECEIVED

DEC 13 2023

OWRD

7N

L 152770