

STATE OF OREGON *Amended 9-30-25*
WATER SUPPLY WELL REPORT
(as required by ORS 537.765 & OAR 690-205-0210)

Received

SEP 08 2025

WELL I.D. LABEL# 156364
START CARD # 217245
ORIGINAL LOG #

(1) LAND OWNER

Owner Well I.D. OWNRD
First Name Linn Benton Community College Last Name
Company Linn Benton Community College
Address 6500 Pacific Boulevard SW
City Albany State OR Zip 97321

(2) TYPE OF WORK

☒ New Well ☐ Deepening ☐ Conversion

☐ Alteration (complete 2a & 10) ☐ Abandonment (complete 5a)

(2a) PRE-ALTERATION

Dia + From To Gauge Stil Plstc Wld Thrd
Casing: ☐ ☐ ☐ ☐ ☐ ☐ ☐ ☐

Material From To Amt sacks/lbs
Seal: ☐ ☐ ☐ ☐

(3) DRILL METHOD

☒ Rotary Air ☐ Rotary Mud ☐ Cable ☐ Auger ☐ Cable Mud
☐ Reverse Rotary ☐ Other

(4) PROPOSED USE

☐ Domestic ☐ Irrigation ☒ Community
☐ Industrial/ Commercial ☐ Livestock ☐ Dewatering
☐ Thermal ☐ Injection ☐ Other

(5) BORE HOLE CONSTRUCTION

Special Standard ☐ (Attach copy)

Depth of Completed Well 140 ft.

BORE HOLE

Dia	From	To	Material	From	To	Amt	sacks/lbs
10"	0	21	Bentonite	21	0	15	Sacks
6"	21	140				Calculated	8.4
						Calculated	

How was seal placed: Method ☐ A ☐ B ☐ C ☐ D ☐ E

☒ Other Bentonite Poured Dry

Backfill placed from _____ ft. to _____ ft. Material _____

Filter pack from _____ ft. to _____ ft. Material _____ Size _____

Explosives used: ☐ Yes Type _____ Amount _____

(5a) ABANDONMENT USING UNHYDRATED BENTONITE

Proposed Amount Pounds Actual Amount Pounds

(6) CASING/LINER

Casing	Liner	Dia	From	To	Gauge	Stil	Plstc	Wld	Thrd
☒	☐	6"	110	135	1/2"	1 1/2"	52	6"	
☐	☐								
☐	☐								
☐	☐								

Shoe ☐ Inside ☐ Outside ☐ Other Location of shoe(s) _____

Temp casing ☐ Yes Dia _____ From _____ To _____

(7) PERFORATIONS/SCREENS

Perforations Method Perforator

Screens Type Ho/te Material _____

Perf/S	Casing/Screen	Dia	From	To	Scrns/slot	Slot	# of	Tele.
green	Liner				width	length	slots	pipe size
Perf Casing		110	135	1/2"	1 1/2"	52	6"	

(8) WELL TESTS: Minimum testing time is 1 hour

☐ Pump ☐ Bailor ☒ Air ☐ Flowing Artesian

Yield gal/min	Drawdown	Drill stem Pump depth	Duration (hr)
100		135'	2 HRS

Temperature 56 F Lab analysis ☐ Yes By _____

Water quality concerns? ☐ Yes (describe below) TDS amount 137 ppm

From	To	Description	Amount	Units

(9) LOCATION OF WELL (legal description)

County Linn Twp 11 S N/S Range 4W E/W WM
Sec 36 SE 1/4 of the SW 1/4 Tax Lot 00300

Tax Map Number _____ Lot _____

Lat 44° 33' 48" or _____ DMS or DD

Long 123° 7' 24" or _____ DMS or DD

☒ Street address of well ☐ Nearest address

Tax Lot 300 Looney Ln. Target, OR 97138

(10) STATIC WATER LEVEL

Date	SWL (psi)	+ SWL (ft)
Existing Well : Pre-Alteration		
Completed Well	7/31/25	21

Flowing Artesian? ☐ Dry Hole? ☐

WATER BEARING ZONES Depth water was first found 67'

SWL Date	From	To	Est Flow	SWL (psi)	+ SWL (ft)
7/30/25	67	91	50		21
7/31/25	102	131	100		21

(11) WELL LOG

Ground Elevation _____

Material	From	To
Topsoil	0	2
Brown/gray clay	2	13
Gray clay	13	17
Gray clay/gravel	17	33
Brown sand/gravel	33	67
Black sand/heaving	67	91
Black sand/small gravel	91	102
Black sand/medium gravel	102	131
Blue gray clay	131	140

Start Date: 7/29/25

Start time: 4:00 PM

Seal Date: 7/29/25

Seal time: 7:00 PM

Helpers: Kevin Fleming, Jeremy Edwards

Date Started 7-29-2025 Completed 7-31-2025

(unbonded) Water Well Constructor Certification

I certify that the work I performed on the construction, deepening, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

License Number _____ Date _____

Signed _____

(bonded) Water Well Constructor Certification

I accept responsibility for the construction, deepening, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

License Number 1562 Date 9/3/25

Signed Sean C. Oldham

Contact Info (optional) _____