

STATE OF OREGON
WATER SUPPLY WELL REPORT

LINN 65223

WELL I.D. LABEL# L

157429

START CARD #

1082937

ORIGINAL LOG #

(as required by ORS 537.545 & 537.765 and OAR 690-205-0210)

8/17/2026

(1) LAND OWNER

Owner Well I.D. DR-3868

First Name _____ Last Name _____
 Company LARRY & MELODY REVOKABLE TRUST.
 Address P. O. BOX 422
 City TANGENT State OR Zip 97389

(2) TYPE OF WORK☒ New Well ☐ Deepening ☐ Conversion☐ Alteration (complete 2a & 10) ☐ Abandonment (complete 5a)**(2a) PRE-ALTERATION**

Casing: Dia + From To Gauge Stl Plstc Wld Thrd
 Material From To Amt sacks/lbs
 Seal: _____

(3) DRILL METHOD

☒ Rotary Air ☐ Rotary Mud ☐ Cable ☐ Auger
☐ Reverse Rotary ☐ Other _____

(4) PROPOSED USE☒ Domestic ☐ Irrigation ☐ Community

☐ Industrial/ Commercial ☐ Livestock ☐ Dewatering
☐ Thermal ☐ Injection ☐ Other _____

(5) BORE HOLE CONSTRUCTIONSpecial Standard ☐ (Attach copy)Depth of Completed Well 94.00 ft.

BORE HOLE				SEAL			
Dia	From	To	Material	From	To	Amt	sacks/lbs
10	0	19	Bentonite	0	19	9	S
6	19	102			Calculated	8.67	
					Calculated		

Seal placement method: ☐ A ☐ B ☐ C ☐ D ☐ E ☒ Other: POURED DRY

Backfill placed from _____ ft. to _____ ft. Material _____

Filter pack from _____ ft. to _____ ft. Material _____ Size _____

Explosives used: ☐ Type _____ Amount _____Seal Placement Begin Date 8/11/2026 Begin Time 15 00**(5a) ABANDONMENT USING UNHYDRATED BENTONITE**

Proposed Amount _____ Actual Amount _____

(6) CASING/LINER

C/L	Dia	+ From To	Gauge	Mat. Type	Wld	Thrd	Shoe	Location
C	6	☒ 1.4 79	0.250	ST	☒		OUT.	79

Temp casing ☐ Yes Dia _____ From + _____ To _____**(7) PERFORATIONS/SCREENS**

Perforations Method _____

Screens Type _____ Material _____

Perf/ Screen	Casing/ Liner	Screen Dia	From	To	Scrn/slot width	Slot length	# of slots	Tele/ Pipe size

(8) WELL TESTS: Minimum testing time is 1 hour

Type of Test	Yield (gal/min)	Drawdown	Drill Stem/ Pump Depth	Duration (hr)
Air	75		75	1

Temperature 53 °F Lab analysis ☐ Yes By _____Water quality concerns? ☐ Yes (describe below) TDS amount 154 ppm

From To	Description	Amount	Units

(9) LOCATION OF WELL (legal description)County LINN Twp 12.00 S N/S Range 3.00 W E/W WMSec 18 SW 1/4 of the NW 1/4 Tax Lot 200

Tax Map Number _____ Lot _____

Lat _____ " or 44.52823309 DMS or DD

Long _____ " or -123.10949220 DMS or DD

☒ Street address of well ☐ Nearest address32521 HIGHWAY 99ETANGENT OR. 97389**(10) STATIC WATER LEVEL**

	Date	SWL (psi)	+	SWL (ft)
Existing Well / Pre-Alteration				
Completed Well	8/13/2026			21

Flowing Artesian? ☐ Dry Hole? ☐

WATER BEARING ZONES

Depth water was first found 40.00

SWL Date	From	To	Est Flow	SWL (psi)	+	SWL (ft)
8/13/2026	40	64	15			21
8/13/2026	64	102	60			21

(11) WELL LOGGround Elevation 251.30 FT

Material	From	To
Topsoil	0	2
Clay Brown Sticky	2	15
Clay Brown w/ Gravel	15	25
Gravel w/ Sand & Silt Brown	25	40
Sand Brown w/ Some Gravel	40	50
Gravel Black Small	50	64
Sand w/ Some Gravel Black	64	76
Gravel Black w/ Sand Large	76	87
Sand w/ Gravel Black	87	91
Gravel Black Large	91	94
Sand Black Packed w/ Clay Gray	94	102

Construction

Begin Date 8/11/2026 Begin Time 14 00 End Date 8/13/2026**(unbonded) Water Well Constructor Certification**

I certify that the work I performed on the construction, deepening, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

License Number 1974 Date 8/17/2026Signed CJ NUGENT (E-filed)**(bonded) Water Well Constructor Certification**

I accept responsibility for the construction, deepening, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

License Number 664 Date 8/17/2026Signed CHARLES NUGENT (E-filed)Drilling Company: Nugent Drilling Co. Lebanon OR. 541-258-7816

ORIGINAL - WATER RESOURCES DEPARTMENT

THIS REPORT MUST BE SUBMITTED TO THE WATER RESOURCES DEPARTMENT WITHIN 30 DAYS OF COMPLETION OF WORK Form Version:

New exempt use wells must be submitted with a map and recording fee.

(2a) PRE-ALTERATION

Dia	+	From	To	Gauge	Stl	Plstc	Wld	Thrd

Material	From	To	Amt	sacks/lbs

(5) BORE HOLE CONSTRUCTION

BORE HOLE			SEAL			sacks/ lbs	
Dia	From	To	Material	From	To		Amt
			Calculated				
			Calculated				
			Calculated				
			Calculated				

FILTER PACK			
From	To	Material	Size

(6) CASING/LINER

[illegible]

(7) PERFORATIONS/SCREENS

[illegible]

(8) WELL TESTS: Minimum testing time is 1 hour

Type of Test	Yield (gal/min)	Drawdown	Drill Stem/ Pump Depth	Duration (hr)

Water Quality Concerns

[illegible]

(10) STATIC WATER LEVEL

[illegible]

(11) WELL LOG

[illegible]

Name of person(s) who assisted with construction and Trainee License # / Helper #

Assistant Name	Type	#
NATHAN CONNELLY	HELPER WATER	8889012

Comments/Remarks

Well output may fluctuate slightly. Hole Naturally caved back to 94'.

WATER SUPPLY WELL REPORT - Map with location identified must be attached and shall include an approximate scale and north arrow

LINN 65223

8/17/2026

Map of Hole

STATE OF OREGON WELL LOCATION MAP

This map is supplemental to the WATER SUPPLY WELL REPORT

Oregon Water Resources Department

725 Summer St NE, Salem OR 97301
(503)986-0900



LOCATION OF WELL

Latitude: 44.52823309 Datum: WGS84

Longitude: -123.10949220

Township/Range/Section/Quarter-Quarter Section:

WM12.00S3.00W18SWNW

Address of Well:

32521 HIGHWAY 99E

TANGENT OR. 97389

Well Label: 157429

Printed: August 17, 2026

DISCLAIMER: This map is intended to represent the approximate location the well. It is not intended to be construed as survey accurate in any manner.

Provided by well constructor

