

NOTICE TO WATER WELL CONTRACTOR

The original and first copy
of this report are to be
filed with the

STATE ENGINEER, SALEM, OREGON 97310
within 30 days from the date
of well completion.

RECEIVED
DEC 29 1967
STATE ENGINEER

WATER WELL REPORT

STATE OF OREGON
(Please type or print)

State Well No. 12/2w-10

State Permit No. _____

(1) OWNER:

Name CITY OF LEBANON
Address Recorder's office
Lebanon, Oregon

(2) LOCATION OF WELL:

County Linn Driller's well number _____
1/4 Section 10 T. 12S R. 2W W.M.
Bearing and distance from section or subdivision corner _____

(3) TYPE OF WORK (check):

Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐
If abandonment, describe material and procedure in Item 12.

(4) PROPOSED USE (check):

Domestic ☐ Industrial ☐ Municipal ☐
Irrigation ☒ Test Well ☐ Other ☐
Dug ☐ Bored ☐

(5) TYPE OF WELL:

Rotary ☐ Driven ☐
Cable ☒ Jetted ☐
Dug ☐ Bored ☐

(6) CASING INSTALLED:

Threaded ☐ Welded ☒
8" Diam. from 1 ft. to 199 ft. Gage 250
" Diam. from _____ ft. to _____ ft. Gage _____
" Diam. from _____ ft. to _____ ft. Gage _____

(7) PERFORATIONS:

Perforated? ☒ Yes ☐ No

Type of perforator used MILLS
Size of perforations 1/2 in. by 6 in.
75 perforations from 89 ft. to 102 ft.
perforations from _____ ft. to _____ ft.
perforations from _____ ft. to _____ ft.
perforations from _____ ft. to _____ ft.
perforations from _____ ft. to _____ ft.

(8) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name _____ Model No. _____
Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.
Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.

(9) CONSTRUCTION:

Well seal—Material used in seal Cement
Depth of seal 20 ft. Was a packer used? NO
Diameter of well bore to bottom of seal 14 in.
Were any loose strata cemented off? ☐ Yes ☒ No Depth _____
Was a drive shoe used? ☒ Yes ☐ No
Was well gravel packed? ☐ Yes ☒ No Size of gravel: _____
Gravel placed from _____ ft. to _____ ft.
Did any strata contain unusable water? ☐ Yes ☒ No
Type of water? _____ depth of strata _____
Method of sealing strata off _____

(10) WATER LEVELS:

Static level 20 ft. below land surface Date 4/25
Artesian pressure _____ lbs. per square inch Date _____

(11) WELL TESTS:

Drawdown is amount water level is
lowered below static level

Was a pump test made? ☒ Yes ☐ No If yes, by whom? Ramsey & Waid Co.
Yield: 2.36 gal./min. with 31.8 ft. drawdown after 2 hrs.

" " " "
" " " "
" " " "

Ball test gal./min. with _____ ft. drawdown after _____ hrs.

Artesian flow g.p.m. Date _____

Temperature of water _____ Was a chemical analysis made? ☐ Yes ☐ No

(12) WELL LOG:

Diameter of well below casing 8

Depth drilled 202 ft. Depth of completed well 202 ft.

Formation: Describe by color, character, size of material and structure, and show thickness of aquifers and the kind and nature of the material in each stratum penetrated, with at least one entry for each change of formation.

MATERIAL	FROM	TO
Top Soil	0	4
brown clay	4	8
Clay and medium gravel	8	22
Coarse gravel, medium boulders	22	28
Medium sand and gravel	28	33
dark grey clay, small gravel	33	35
dark grey clay	35	51
dark grey clay and gravel	51	58
Coarse sand	58	62
Medium sand	62	75
Medium sand and gravel	75	85
Medium sand and coarse gravel	85	108
Blue clay with brown sand streaks	108	168
Brown sand and gravel	168	183
blue clay and gravel	183	195
blue clay stone	195	202
blue gravel	202	

12- TRACK & Pambellon drillers on this job -

Work started 3/15 1967 Completed 3/25 1967

Date well drilling machine moved off of well 3/26 1967

(13) PUMP:

Manufacturer's Name _____ Type: _____ H.P. _____

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

NAME VALLEY WELL DRILLERS
(Person, firm or corporation) (Type or print)

Address P.O. Box 885

Drilling Machine Operator's License No. 310
Phone 926-3400

[Signed] Edward Rute
(Water Well Contractor)

Contractor's License No. 253 Date 12-3, 1967