

NOTICE TO WATER WELL CONTRACTOR
The original and first copy
of this report are to be
filed with the

WATER WELL REPORT

STATE ENGINEER, SALEM, OREGON 97310
within 30 days from the date
of well completion.

RECEIVED

STATE OF OREGON

(Please type or print)

SEP - 2 1975

(Do not write above this line)

LINN

State Well No.

115/4W-22

8412

State Permit No.

(1) OWNER:

Name LEROY SCHROEDER
Address 9320 S.E. 7 mile lane
ALBANY ORE

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐
If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☐ Driven ☐
Cable ☒ Jetted ☐
Dug ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐
Irrigation ☐ Test Well ☐ Other ☐

(5) CASING INSTALLED:

Threaded ☐ Welded ☐
6" Diam. from 0 ft. to 70 ft. Gage 1250
" Diam. from ft. to ft. Gage
" Diam. from ft. to ft. Gage

(6) PERFORATIONS:

Perforated? ☒ Yes ☐ No.
Type of perforator used Touche
Size of perforations 3/16 in. by 6 in.
25 perforations from 58 ft. to 68 ft.
perforations from ft. to ft.
perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No
Manufacturer's Name
Type Model No.
Diam. Slot size Set from ft. to ft.
Diam. Slot size Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is
lowered below static level
Was a pump test made? ☐ Yes ☐ No If yes, by whom?
Yield: gal./min. with ft. drawdown after hrs.
" " " "
" " " "
Bailer test 25 gal./min. with 12 ft. drawdown after 20 hrs.
Artesian flow g.p.m.
Temperature of water 52° Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Well seal—Material used Portland cement
Well sealed from land surface to 18 ft.
Diameter of well bore to bottom of seal 10 in.
Diameter of well bore below seal 6 in.
Number of sacks of cement used in well seal 5 sacks
Number of sacks of bentonite used in well seal sacks
Brand name of bentonite
Number of pounds of bentonite per 100 gallons
of water lbs./100 gals.
Was a drive shoe used? ☒ Yes ☐ No Plugs Size: location ft.
Did any strata contain unusable water? ☐ Yes ☒ No
Type of water? depth of strata
Method of sealing strata off
Was well gravel packed? ☐ Yes ☒ No Size of gravel:
Gravel placed from ft. to ft.

(10) LOCATION OF WELL:

County LINN Driller's well number 99
SE 1/4 NW 1/4 Section 22 T. 115 R. 4W W.M.

Bearing and distance from section or subdivision corner 185'
N. 65' west from the SE corner
of the SE 1/4

(11) WATER LEVEL: Completed well.

Depth at which water was first found 33 ft.
Static level 20 ft. below land surface. Date 8/1/75
Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing
Depth drilled 70 ft. Depth of completed well 70 ft.

Formation: Describe color, texture, grain size and structure of materials;
and show thickness and nature of each stratum and aquifer penetrated,
with at least one entry for each change of formation. Report each change in
position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
Top soil	0	3	
GREY CLAY	3	12	
BROWN CLAY	12	18	
GRAVEL + BROWN CLAY	18	42	
BROWN CLAY	42	59	
COARSE BROWN SAND	59	69	
Blue CLAY	69	70	

Work started 7/29 1975 Completed 8/1/75 19
Date well drilling machine moved off of well 8/1/75 19

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision.
Materials used and information reported above are true to my
best knowledge and belief.

[Signed] Pat Riddens Date 8/3/75 19
(Drilling Machine Operator)

Drilling Machine Operator's License No. 898

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is
true to the best of my knowledge and belief.

Name FRANK WAGY WELL DRILLING
(Person, firm or corporation) (Type or print)

Address 2435 PINE LANE ALBANY OREGON

[Signed] Frank Wagy
(Water Well Contractor)

Contractor's License No. 423 Date 8-25 1975