

WATER WELL REPORT
STATE OF OREGON

RECEIVED

AUG 08 1984

WATER RESOURCES DEPT
PLEASE TYPE OR PRINT IN INK
SALEM, OREGON

State Well No. 135/1W-1766

State Permit No. _____

(1) OWNER:

Name Bonnie Bonish
Address 38495 Hwy 228
City Swick' Horn State Oregon

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary Air ☒ Driven ☐ Domestic ☒ Industrial ☐ Municipal ☐
Rotary Mud ☐ Dug ☐ Irrigation ☐ Test Well ☐ Other ☐
☐ Bored ☐ Thermal: Withdrawal ☐ Reinjection ☐

(4) PROPOSED USE (check):

(5) CASING INSTALLED:

Steel ☒ Plastic ☐
Threaded ☐ Welded ☒
6" Diam. from 0 ft. to 100 ft. Gauge 250
" Diam. from ft. to ft. Gauge

LINER INSTALLED:

4" Diam. from 0 ft. to 140 ft. Gauge 160

(6) PERFORATIONS:

Perforated? ☒ Yes ☐ No
Type of perforator used Hand Drill
Size of perforations 5/8 in. by in.
5/8" perforations from 100 ft. to 120 ft.
5/8" perforations from 120 ft. to 140 ft.
perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No
Manufacturer's Name _____
Type _____ Model No. _____
Diam. _____ Slot Size _____ Set from ft. to ft.
Diam. _____ Slot Size _____ Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is lowered below static level
Was a pump test made? ☐ Yes ☒ No If yes, by whom?
id: gal./min. with ft. drawdown after hrs.
Air test 15 plus gal./min. with drill stem at 120 ft. 1 hrs.
Bailer test gal./min. with ft. drawdown after hrs.
Artesian flow g.p.m.
Temperature of water Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Special standards: Yes ☐ No ☐
Well seal—Material used Cemented
Well sealed from land surface to 18 ft.
Diameter of well bore to bottom of seal 10 in.
Diameter of well bore below seal 6 in.
Number of sacks of cement used in well seal 12 sacks
How was cement grout placed? pumped
Was pump installed? _____ Type _____ HP _____ Depth _____ ft.
Was a drive shoe used? ☒ Yes ☐ No Plugs _____ Size: location _____ ft.
Did any strata contain usable water? ☐ Yes ☒ No
Type of Water? _____ depth of strata _____
Method of sealing strata off
Was well gravel packed? ☐ Yes ☒ No Size of gravel: _____
Gravel placed from ft. to ft.

(10) LOCATION OF WELL:

County LINN Driller's well number
NN 1/4 NW 1/4 Section 17 T. 15S R. 1W W.M.
Tax Lot # _____ Lot _____ Blk _____ Subdivision _____

Address at well location: Some about 3 miles from Valley on Right side of Road

(11) WATER LEVEL: Completed well.

Depth at which water was first found 120 ft.
Static level 16 ft. below land surface. Date July 17-84
Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing 6
Depth drilled 140 ft. Depth of completed well 140 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
Soil	0	4	
clay	4	9	
clay & gravel	9	24	
gravel & boulders	24	42	
clay & gravel	42	80	
gray clay	80	96	
sandstone	96	105	
clay	105	115	
Hard sandstone	115	140	

Work started July 14 19 84 Completed July 17 19 84
Date well drilling machine moved off of well 17 19 84

(unbonded) Water Well Constructor Certification (if applicable):

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.
[Signed] Howard Arms Date July 17, 1984

Bonded Water Well Constructor Certification:

Bond 113050 Issued by: United Pacific
(number) Surety Company Name
This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.
Name ATMST. SCHILLING WELL DRILLING
(Person, firm or corporation) (Type or print)
Address 29030 S.A.M. Hwy. SWEET HOME
[Signed] Howard Arms Water Well Constructor
Date July 17, 19 84

NOTICE TO WATER WELL CONSTRUCTOR
The original and first copy of this report are to be filed with the

WATER RESOURCES DEPARTMENT,
SALEM, OREGON 97310
within 30 days from the date of well completion.

SP*45292-690