

NOTICE TO WATER WELL CONTRACTOR
The original and first copy of this report
are to be filed with the

WATER RESOURCES DEPARTMENT,
SALEM, OREGON 97310
within 30 days from the date
of well completion.

WATER WELL REPORT

STATE OF OREGON

(Please type or print)

(Do not write above this line)

State Well No. 85146E-36bd

State Permit No. 1272 Malheur

(1) OWNER:

Name Tom Tucker
Address ONTARIO ORE

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☐ Driven ☐
Pneumatically ☐ Jetted ☐
Auger ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐
Irrigation ☐ Test Well ☐ Other ☐

CASING INSTALLED:

Threaded ☐ Welded ☒

8" Diam. from 71 ft. to 30 ft. Gage
" Diam. from _____ ft. to _____ ft. Gage
" Diam. from _____ ft. to _____ ft. Gage

PERFORATIONS:

Perforated? ☐ Yes ☒ No

Type of perforator used _____

Size of perforations in. by in.
_____ perforations from _____ ft. to _____ ft.
_____ perforations from _____ ft. to _____ ft.
_____ perforations from _____ ft. to _____ ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name _____ Model No. _____
Type _____
Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.
Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.

(8) WELL TESTS:

Drawdown is amount water level is
lowered below static level

a pump test made? ☒ Yes ☐ No If yes, by whom DRILLER
Yield: 30 gal./min. with 65 ft. drawdown after 1 hrs.
with pump set at 130'

Artesian flow gal./min. with ft. drawdown after hrs.
Artesian flow g.p.m.
Temperature of water 62.8 Depth artesian flow encountered _____ ft.

(9) CONSTRUCTION:

Well seal—Material used Cement Grout
Well sealed from land surface to 30 ft.
Diameter of well bore to bottom of seal 6" 10" in.
Diameter of well bore below seal 6" in.
Number of sacks of cement used in well seal 7 sacks
How was cement grout placed? with pressure
Grout machine

Was a drive shoe used? ☒ Yes ☐ No Plugs _____ Size: location _____ ft.
Did any strata contain unusable water? ☐ Yes ☒ No
Type of water? _____ depth of strata _____
Method of sealing strata off _____
Was well gravel packed? ☐ Yes ☒ No Size of gravel: _____
Gravel placed from _____ ft. to _____ ft.

(10) LOCATION OF WELL:

County Malheur Driller's well number _____
S. E 1/4 N. W. 1/4 Section 36 T. 18 S. R. 46 E. W.M.
Bearing and distance from section or subdivision corner _____

(11) WATER LEVEL: Completed well.

Depth at which water was first found 100' ft.
Static level 75' ft. below land surface. Date _____
Artesian pressure _____ lbs. per square inch. Date _____

(12) WELL LOG:

Diameter of well below casing 6

Depth drilled 219 ft. Depth of completed well 219' ft.

Formation: Describe color, texture, grain size and structure of materials;
and show thickness and nature of each stratum and aquifer penetrated,
with at least one entry for each change of formation. Report each change in
position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
CLAY	0	2	
CLAY BROWN SANDY	2	25	
ROCK SAND ROCK	25	90	
SAND STREAK	90	91	91
CLAY BROWN sticky	91	132	91
CLAY BLUE	132	135	91
CLAY BROWN	135	152	91
CLAY BLUE	152	157	91
CLAY BROWN	157	176	91
ROCK SAND	176	205	84
CLAY BLUE	205	208	84
SAND ROCK	208	209	75
SAND ROCK	209	219	75

RECEIVED

SEP 6 - 1979

WATER RESOURCES DEPT
SALEM, OREGON

Work started Aug 19 1979 Completed Aug 20 1979
Date well drilling machine moved off of well Aug 27 1979

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision.
Materials used and information reported above are true to my
best knowledge and belief.

[Signed] Edy Belisle Date 8-27, 1979
(Drilling Machine Operator)

Drilling Machine Operator's License No. 1195

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is
true to the best of my knowledge and belief.

Name HOLLOWAY DRILLING Co.
(Person, firm or corporation) (Type or print)

Address ONTARIO ORE

[Signed] Max Holloway
(Water Well Contractor)

Contractor's License No. 16 Date 8-27 1979