

The original and first copy
of this report are to be
filed with the

within 30 days from the date
of well completion.

RECEIVED WATER

JUN 18 1968

STATE OF OREGON

(Please type or print)

~~Do not~~ Write above this line)

STATE ENGINEER
SALEM, OREGON

State Well No. 18/47-9A

State Permit No.

Name 7 REA SURE Valley (b) (6)
Address ONTARIO OREGON

If abandonment, describe material and procedure in Item 12.

Domestic ☐ Industrial ☐ Municipal ☐
Irrigation ☒ Test Well ☐ Other ☐

16" Diam. from 0 ft. to 33 ft. Gage 4
" Diam. from ft. to ft. Gage
" Diam. from ft. to ft. Gage

Type of perforator used	TORCH			
Size of perforations	3/8"	in. by	1"6"	in.
144	perforations from	21'	ft. to	33'
	perforations from		ft. to	
	perforations from		ft. to	
	perforations from		ft. to	
	perforations from		ft. to	

Manufacturer's Name

Type Model No.

Diam. Slot size Set from ft. to ft.

Diam. Slot size Set from ft. to ft.

Static level 16 ft. below land surface Date 5-18-68
Pneumatic pressure _____ lbs. per square inch Date _____

Was a pump test made? ☒ Yes ☐ No If yes, by whom? DRILLER
Yield: 400 gal./min. with 64 ft. drawdown after 15 1/2 hrs.

Artesian flow _____ g.p.m. Date _____

Temperature of water 58° Was a chemical analysis made? ☐ Yes ☒ No

Well seal—Material used BENTONITE CEMENT
 Depth of seal 21 ft.
 Diameter of well bore to bottom of seal 24" in.
 Were any loose strata cemented off? ☐ Yes ☒ No Depth _____
 Was a drive shoe used? ☒ Yes ☐ No
 Did any strata contain unusable water? ☐ Yes ☒ No
 Type of water? _____ depth of strata _____
 Method of sealing strata off _____
 Was well gravel packed? ☒ Yes ☐ No Size of gravel: 3/4" X 3/8"
 Gravel placed from 71' ft. to 31' ft.

County MALHEAR Driller's well number
NW 1/4 SE 1/4 Section 9 T. 18S R. 47E W.M.
Bearing and distance from section or subdivision corner

Depth drilled 100 ft. Depth of completed well 96' ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level as drilling proceeds. Note drilling rates.

MATERIAL	From	To	SWL
SOIL SANDY	0	3	
CLAY YELLOW	3	10	
CLAY SANDY	10	21	21'
SANDY GRAVEL	21	31	21'
BLUE CLAY	31	60	18'
SAND BLACK	60	61	18'
CLAY BLUE	61	80	18'
SAND BLACK.	80	82	16'
CLAY BLUE	82	100	16'

Work started 5-14 1968 Completed 5-18 1968

Date well drilling machine moved off of well 5-20 1968

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] Max Halbury Date 6-18, 1968
(Drilling Machine Operator)

Drilling Machine Operator's License No. 100

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

NAME HOLLOWAY DRILLING CO.
(Person, firm or corporation) (Type or print)

Address ONTARIO WYCHON

[Signed] Max Holloway (Water Well Contractor)

Contractor's License No. 16 Date 6-18-11, 1965