

NOTICE TO WATER WELL CONTRACTOR

The original and first copy of this report are to be filed with the

STATE ENGINEER, SALEM 10, OREGON within 30 days from the date of well completion.

RECEIVED

APR 19 1963

WATER WELL REPORT

STATE OF OREGON
(Please type or print)

Malheur
1713

State Well No. 185/47-278

State Permit No.

(1) OWNER:

Name

Address

DR. WEESE
ONTARIO ORE.

(2) LOCATION OF WELL:

County MALHEUR Driller's well number

SE 1/4 SE 1/4 Section 27 T. 18 R. 47 E W.M.

Bearing and distance from section or subdivision corner

Well located 30' West and 40' South of Section corner.

(3) TYPE OF WORK (check):

Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐
Abandonment, describe material and procedure in Item 12.

(4) PROPOSED USE (check):

Domestic ☐ Industrial ☐ Municipal ☐
Irrigation ☒ Test Well ☐ Other ☐

(5) TYPE OF WELL:

Rotary ☐ Driven ☐
Cable ☒ Jetted ☐
Dug ☐ Bored ☐

(6) CASING INSTALLED:

Threaded ☐ Welded ☒

16" Diam. from -1 ft. to 40 ft. Gage 4"
" Diam. from ft. to ft. Gage
" Diam. from ft. to ft. Gage

(7) PERFORATIONS:

Perforated? ☒ Yes ☐ No

Type of perforator used TORCH

Size of perforations 3/8 in. by 6 in.
440 perforations from 19' 6" ft. to 40 ft.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.

(8) SCREENS:

Well screen installed ☐ Yes ☒ No

Manufacturer's Name

Model No.

Slot size Set from ft. to ft.
Diam. Slot size Set from ft. to ft.

(9) CONSTRUCTION:

Well seal—Material used in seal BENTONITE
Depth of seal 12 ft. Was a packer used? SAND
Diameter of well bore to bottom of seal 20 in.
Were any loose strata cemented off? ☐ Yes ☒ No Depth
Was a drive shoe used? ☒ Yes ☐ No
Was well gravel packed? ☐ Yes ☒ No Size of gravel:
Gravel placed from ft. to ft.
Did any strata contain unusable water? ☐ Yes ☒ No
Type of water? Depth of strata
Method of sealing strata off

(10) WATER LEVELS:

Static level 9 ft. below land surface Date 4-17-63
Artesian pressure lbs. per square inch Date

(11) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? ☒ Yes ☐ No If yes, by whom?

Yield: 660 gal./min. with 30 ft. drawdown after 6 hrs.

" " " "

" " " "

Bailer test gal./min. with ft. drawdown after hrs.

Artesian flow g.p.m. Date

Temperature of water 61° Was a chemical analysis made? ☐ Yes ☒ No

(12) WELL LOG:

Diameter of well below casing 15 3/4

Depth drilled 50 ft. Depth of completed well 50 ft.

Formation: Describe by color, character, size of material and structure, and show thickness of aquifers and the kind and nature of the material in each stratum penetrated, with at least one entry for each change of formation.

MATERIAL	FROM	TO
Soil Heavy	0	4
CLAY	4	12
GRAVEL Medium	12	37
SAND Coarse	37	39
CLAY Blue	39	50

Work started 4-12 1963 Completed 4-17 1963
Date well drilling machine moved off of well 19

(13) PUMP:

Manufacturer's Name No Pump Yet
Type:

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

NAME Holloway Drilling Co.
(Person, firm or corporation) (Type or print)

Address ONTARIO OREGON

Drilling Machine Operator's License No. 101

[Signed] Max Holloway
(Water Well Contractor)

Contractor's License No. 16 Date 4-18, 1963